

# *Former Remington Rand Facility*

180 Johnson Street  
Middletown,  
Connecticut

---

Prepared for    Economic Development Committee  
                         Middletown, Connecticut

Prepared by    **VHB**/Vanasse Hangen Brustlin, Inc.  
                         Watertown, Massachusetts

June 1997



54 Tuttle Place  
Middletown  
Connecticut 06457  
860 632 1500  
FAX 860 632 7879

June 27, 1997

Ref: 40163

Mr. Gerald Daley, Chairman  
Economic Development Committee  
The City of Middletown  
P.O. Box 1300, Municipal Office Building  
245 Dekoven Drive  
Middletown, CT 06457-1300

Re: Phase II Environmental Site Assessment  
Former Remington Rand Facility  
180 Johnson Street, Middletown, CT

Dear Mr. Daley:

Vanasse Hangen Brustlin, Inc. (VHB) is pleased to submit this final report that summarizes Phase II investigation activities and findings for the property captioned above (Site). This report was prepared in accordance with the terms of the City of Middletown's Purchase Order No. 059465 (RFP No. 9697-049). Our submittal is made before the 45-day contractual deadline and fulfills our professional obligations under the current agreement.

Phase II site assessment findings of particular importance to the City's North End redevelopment plans include:

- Adverse environmental impacts at the Site associated with landfill leachate migration from the Municipal Landfill were not identified in the overburden aquifer during this investigation. Water table elevations indicate that local groundwater flows northeasterly toward the Municipal Landfill and adjacent wetland area.
- Ten soil contaminant release areas and two groundwater impact areas have been identified at the Site which will require additional response actions pursuant to the DEP's Remediation Standard Regulations (RSRs). The RSRs provide the City flexibility in addressing existing environmental conditions through contaminated soil excavation, on-site contaminated soil treatment and reuse, and/or institution of Environmental Land Use Restrictions (ELURs) where soil cleanup activities would be prohibitively expensive or technically infeasible.
- Groundwater test results reported solvent constituent concentrations in monitoring wells MW-1, MW-4, and MW-5. Additional investigation activities will be required to assess whether groundwater impacts have resulted from potential on-site migration from hydrologically upgradient property(ies) or past on-site solvent storage. To resolve this issue, we recommend that the City install additional groundwater monitoring wells along the Site's western and southwestern property lines to determine if off-Site solvent release(s) have impacted the Site.



- A preliminary estimate of probable remediation costs has been developed which projects soil cleanup expenditures at approximately \$1.4 million, including environmental engineering fees, anticipated laboratory analytical costs, and a 30% contingency. We have based our soil remediation cost estimate upon achieving applicable RSR Residential Direct Exposure Criteria and Pollutant Mobility Criteria; however, the application of RSR Industrial/Commercial Direct Exposure Criteria and institution of ELURs will reduce actual soil remediation costs incurred during Site redevelopment activities.

VHB appreciates the opportunity to participate in this important urban redevelopment project. As discussed during the June 9 Economic Development Committee meeting, we offer to meet with the Committee at a future date to discuss project-related issues. Please contact David Carlson (617/924-1770, extension 1320) or me with any questions you may have regarding this project. We look forward to providing continuing support to the City on this project.

Very truly yours,

VANASSE HANGEN BRUSTLIN, INC.

A handwritten signature in cursive script, reading "James L. Fuda".

James L. Fuda, P.E.  
Principal

JLF/rjr

A handwritten signature in cursive script, reading "David A. Carlson".

David A. Carlson, L.S.P.  
Senior Project Manager

CC: Alan Hanscom, VHB  
File


## *Former Remington Rand Facility*

180 Johnson Street  
Middletown,  
Connecticut

---

Prepared for    **Economic Development Committee**  
245 Dekoven Drive  
Middletown, Connecticut 06457

Prepared by    **VHB/Vanasse Hangen Brustlin, Inc.**  
Transportation, Land Development, Environmental Services  
101 Walnut Street  
P.O. Box 9151  
Watertown, Massachusetts 02272  
617 924 1770

Project Engineer:   
Marc J. Richards, E.I.T.

Senior Project Manager:   
David A. Carlson

Director of  
Environmental  
Engineering:   
Alan D. Hanscom, P. E.

June 1997



# Table of Contents

|                                                                    |    |
|--------------------------------------------------------------------|----|
| Executive Summary .....                                            | 1  |
| Introduction .....                                                 | 4  |
| Site Location and Description .....                                | 4  |
| Summary of Previous Environmental Site Assessment Activities ..... | 5  |
| Test Pit and Hand Auger Investigations .....                       | 6  |
| Right-Of-Way Waste Disposal Area .....                             | 6  |
| Underground Storage Tank Investigation .....                       | 7  |
| UST 1 Area .....                                                   | 8  |
| UST 2 Area .....                                                   | 8  |
| UST 3 Area .....                                                   | 8  |
| UST 4 Area .....                                                   | 9  |
| Electrical Transformers .....                                      | 9  |
| Aboveground Storage Tank Investigation .....                       | 10 |
| Surficial Stained Soil .....                                       | 10 |
| Soil Boring and Groundwater Monitoring Well Installations .....    | 11 |
| GeoProbe Soil Sampling .....                                       | 11 |
| Groundwater Monitoring Well Installation and Sampling .....        | 13 |
| Groundwater Elevations and Flow Direction .....                    | 14 |
| Soil and Groundwater Analytical Results .....                      | 15 |
| Soil Analytical Results .....                                      | 15 |
| Right-Of-Way Disposal Area .....                                   | 15 |
| Underground Storage Tank Release Areas .....                       | 15 |
| Railroad Spur Waste Disposal Area .....                            | 16 |
| Electrical Transformers .....                                      | 16 |
| Aboveground Storage Tank Release Area .....                        | 16 |
| Surficial Stained Soil Areas .....                                 | 16 |
| SPLP Soil Sample Results .....                                     | 17 |
| Groundwater Analytical Results .....                               | 17 |
| Right-Of-Way Waste Disposal Area .....                             | 17 |
| Underground Storage Tank Release Areas .....                       | 17 |
| Waste Disposal Area .....                                          | 18 |
| Suspect Landfill Leachate Area .....                               | 18 |

|                                                                             |           |
|-----------------------------------------------------------------------------|-----------|
| <b>Regulated Building Components and Hazardous Materials Inventory.....</b> | <b>19</b> |
| Asbestos Material Inspection .....                                          | 19        |
| Asbestos Sampling Inspection Results .....                                  | 20        |
| Lead-Based Paint Inspection .....                                           | 21        |
| Lead-Based Paint Inspection Results .....                                   | 21        |
| Polychlorinated Biphenyl and Mercury-Containing Equipment .....             | 22        |
| Interior Drainage Inlet Structures .....                                    | 23        |
| Metal Dust.....                                                             | 24        |
| Hazardous Materials Inventory .....                                         | 24        |
| <b>Regulatory Compliance Issues.....</b>                                    | <b>25</b> |
| Soil and Groundwater Cleanup Objectives .....                               | 25        |
| Soil Contaminant Releases.....                                              | 26        |
| Right-Of-Way (ROW) Waste Disposal Area .....                                | 26        |
| UST 2 Area.....                                                             | 27        |
| UST 4 Area.....                                                             | 27        |
| Suspect UST 5 Area.....                                                     | 27        |
| AST 2 Area.....                                                             | 28        |
| Railroad Spur Waste Disposal Area .....                                     | 28        |
| Surficial Stained Soil Areas .....                                          | 29        |
| Electrical Transformer Installations .....                                  | 29        |
| Groundwater Contaminant Releases.....                                       | 29        |
| UST 4 Area.....                                                             | 29        |
| Railroad Spur Waste Disposal Area .....                                     | 30        |
| <b>Preliminary Estimates of Probable Remediation Costs .....</b>            | <b>31</b> |
| Underground Storage Tank Removals.....                                      | 31        |
| Aboveground Storage Tank Removals .....                                     | 32        |
| Right-Of-Way Waste Disposal Area .....                                      | 32        |
| AST 2 Release Area .....                                                    | 33        |
| Railroad Spur Waste Disposal Area.....                                      | 33        |
| Surficial Stained Soil .....                                                | 33        |
| Electrical Transformers .....                                               | 33        |
| Asbestos-Containing Materials .....                                         | 34        |
| Lead-Based Paint.....                                                       | 34        |
| Containers of Oil and Hazardous Materials .....                             | 35        |
| Engineering and Laboratory Analytical Allowance .....                       | 35        |
| Summary of Probable Remediation Cost Estimate .....                         | 36        |
| <b>Summary of Findings.....</b>                                             | <b>37</b> |
| <b>References .....</b>                                                     | <b>40</b> |

## Figures

| Figure No. | Title                                |
|------------|--------------------------------------|
| 1          | Site Location Map                    |
| 2          | Site Plan                            |
| 3a         | Asbestos Location Plan, First Floor  |
| 3b         | Asbestos Location Plan, Second Floor |
| 3c         | Asbestos Location Plan, Roof         |

## Tables

| Table No. | Title                                           |
|-----------|-------------------------------------------------|
| 1         | Test Pit Soil Sampling Results                  |
| 2         | Soil Boring and Surface Soil Sampling Results   |
| 3         | Groundwater Monitoring Well Results             |
| 4         | Wipe Sampling Results                           |
| 5         | Summary Estimates of Probable Remediation Costs |

## Appendices

| Appendix | Description                                                       |
|----------|-------------------------------------------------------------------|
| A        | Limitations                                                       |
| B        | Site Photographs                                                  |
| C        | Test Pit and Soil Boring Logs                                     |
| D        | Soil, Groundwater, and Wipe Sample Laboratory Analytical Results  |
| E        | Asbestos Summary Tables and Laboratory Analytical Results         |
| F        | Lead-Based Paint Summary Tables and Laboratory Analytical Results |
| G        | Inventory of Oil and Hazardous Materials                          |

## Executive Summary

At the request of the City of Middletown acting through the Economic Development Committee (City), Vannasse Hangen Brustlin, Inc. (VHB) provided environmental consulting services for the Former Remington Rand facility located at 180 Johnson Street in Middletown, Connecticut (Site). VHB undertook a Phase II Environmental Site Assessment in accordance with the Connecticut Transfer Act Site Assessment Standard to support the City's due diligence activities related to the prospective property acquisition.

Suspect areas of environmental concern at the Site were previously identified during a Phase I Site assessment conducted by Soil Science and Environmental Services, Inc. of Cheshire, Connecticut. The Phase II investigation was conducted to assess subsurface conditions associated with suspect contaminant sources, identify regulated building components, inventory miscellaneous containers of hazardous and special wastes, and develop estimates of probable remediation costs.

Based on the results of the subsurface investigation, localized areas of residual soil and groundwater contamination exist at the Site in the vicinity of known and suspect contaminant sources. Laboratory analytical testing confirmed contaminant concentrations that exceed applicable DEP soil and groundwater standards in the following underground storage tank (UST), aboveground storage tank (AST), and waste disposal areas:

- *Right-Of-Way Waste Disposal Area* - Residual TPH, arsenic, copper, and lead contamination in soil/fill.
- *UST 2 Area* - Residual total petroleum hydrocarbons (TPH) contamination in soil. A UST was reported in this area; however, a concrete pad and subsurface piping prevented access to further investigate the UST under the current scope of services.
- *UST 4 Area* - Residual TPH contamination in soil and VOC and zinc contamination in groundwater. The existence of a 500-gallon single-wall steel UST has been confirmed.
- *Suspect UST 5 Area* - Residual TPH contamination in soil at a depth of four to 12 feet indicates that UST(s) may be present within this area.
- *AST 2 Area* - Residual TPH and arsenic contamination in soil.

- *Railroad Spur Waste Disposal Area* - Residual TPH, SVOC, and arsenic contamination in waste disposal area and copper and zinc contamination in groundwater.
- *Electrical Transformers* - Residual PCB contamination in soil beneath Transformer 2 and Transformer 4.
- *Surficial Stained Soil Areas 1 and 2* - Residual TPH and SVOC contamination.

The following regulated building components and miscellaneous containers of hazardous and special waste were also identified at the Site:

- Asbestos containing thermal pipe insulation, floor tile, and insulation on electrical equipment;
- Lead-based paint on fire doors, door jambs, window casings, brick and wood walls, and exterior siding;
- PCB-containing electrical equipment consisting of four electrical transformers, fluorescent light ballasts, and electrical switches. The electrical transformers belong to Northeast Utilities who is responsible for their maintenance and disposal;
- Mercury-containing fluorescent tubes and mercury-vapor lamps located throughout the buildings; and
- Residual heavy metal dust located on window sills, floors, and other horizontal surfaces within the interiors of Buildings 4, 5, and 10.

Phase II site assessment findings of particular importance to the City's North End redevelopment plans include:

- Adverse environmental impacts at the Site associated with landfill leachate migration from the Municipal Landfill were not identified in the overburden aquifer during this investigation. Water table elevations indicate that local groundwater flows northeasterly toward the Municipal Landfill and adjacent wetland area.
- Groundwater test results reported solvent constituent concentrations in monitoring wells MW-1, MW-4, and MW-5. Additional investigation activities will be required to assess whether groundwater impacts have resulted from potential on-site migration from hydrologically upgradient property(ies) or past on-site solvent storage. To resolve this issue, it is recommended that the City install additional groundwater monitoring wells along the Site's western and southwestern property lines to determine if off-site solvent release(s) have impacted the Site.
- Ten soil contaminant release areas and two groundwater impact areas have been identified at the Site which will require additional response actions

pursuant to the DEP's Remediation Standard Regulations (RSRs). The RSRs provide the City flexibility in addressing existing environmental conditions through contaminated soil excavation, on-site contaminated soil treatment and reuse, and/or institution of Environmental Land Use Restrictions (ELURs) where soil cleanup activities would be prohibitively expensive or technically unfeasible.

- A preliminary estimate of probable remediation costs has been developed which projects soil cleanup expenditures at approximately \$1.4 million, including engineering fees, anticipated laboratory analytical costs, and a 30% contingency. Soil remediation cost estimates are based upon achieving applicable RSR Residential Direct Exposure Criteria and Pollutant Mobility Criteria; however, the application of RSR Industrial/Commercial Direct Exposure Criteria and institution of ELURs will reduce actual soil remediation costs incurred during Site redevelopment activities.

This report was prepared on behalf of the City and is subject to the terms and conditions of the Agreement between the City and VHB and the Limitations provided in Appendix A.

# Introduction

At the request of the City of Middletown acting through the Economic Development Committee (City), Vannase Hangen Brustlin, Inc. (VHB) provided environmental consulting services for the Former Remington Rand facility located at 180 Johnson Street in Middletown, Connecticut (Site). VHB undertook a Phase II Environmental Site Assessment in accordance with the Connecticut Transfer Act Site Assessment Standard to support the City's due diligence activities related to the prospective property acquisition.

Suspect areas of environmental concern at the Site were previously identified during a Phase I Site assessment conducted by Soil Science and Environmental Services, Inc. of Cheshire, Connecticut. The Phase II investigation was conducted to assess subsurface conditions associated with suspect contaminant sources, identify regulated building components, inventory miscellaneous containers of hazardous and special wastes, and develop estimates of probable remediation costs.

This report was prepared on behalf of the City and is subject to the terms and conditions of the Agreement between the City and VHB and the Limitations provided in Appendix A.

---

## Site Location and Description

The Site is located at 180 Johnson Street in Middletown, Connecticut in an industrial redevelopment zoned area. The Site is bound by the Middletown Landfill to the north, undeveloped wetlands and the Mattabesset River to the east, railroad right-of-way and E.I.S. Division of Standard Motor Products to the south, and the Hubert E. Butler Construction Company and the Coginchaug River to the west.

The Site includes approximately 10.5 acres with approximately 190,00 square feet of building area. The majority of the Site buildings were constructed from 1897 to 1934. Currently, the Site is serviced by City water, sanitary sewer, natural gas, telephone, and electric utilities. The Phase I report identified that a portion of the Site though may be connected to an on-site septic system located in the vicinity of the right-of-way.

The Site topography is fairly flat with surface elevations generally sloping towards the Mattabesset River to the northeast. The Site is located within the Mattabesset and Coginchaug River drainage basin which are tributaries to the Connecticut River located to the east.

## **Summary of Previous Environmental Site Assessment Activities**

Soil Science and Environmental Services of Cheshire, Connecticut prepared a Phase I Environmental Site Assessment report, dated April 6, 1993 (Phase I Report). The following environmental concerns were summarized in the report:

- Four suspect existing or former underground storage tank locations;
- Two aboveground storage tanks;
- Five electrical transformers;
- Waste disposal area within a right-of-way;
- Interior floor drains and inlet structures;
- Miscellaneous containers of hazardous and special wastes;
- Suspect asbestos and lead-based paint;
- Suspect polychlorinated biphenyl-containing equipment; and
- Surficial stained soils and stressed vegetation.

Past industrial activities reported at the Site included the manufacturing of bicycles, automobiles, typewriters, and metal goods. Industrial wastes, including ink, carbon, wax, oil, detergents, acetone, dye, and nickel, have been historically discharged to the Mattabesset River and the City sewer system.



## Test Pit and Hand Auger Investigations

VHB conducted limited subsurface investigations to obtain information about known and suspect contaminant sources and residual concentrations of oil and hazardous materials (OHM) in soil and groundwater at the Site. This phase of the investigation included the excavation of test pits using a backhoe and investigating surficial soil using a hand auger. Test pitting was conducted on May 15 and May 16, 1997 by P.F. Civetti General Contractor, Inc. of West Springfield, Massachusetts and hand auguring was performed on May 21, 1997 by VHB. VHB directed all excavation activities, observed soil conditions, screened soil samples, and collected soil samples. Photographs illustrating the investigation activities are presented in Appendix B.

Suspect soil samples were field screened using a photo-ionization detector (PID) calibrated to an isobutylene standard. Samples were field screened using a standard methodology for the jar headspace analytical screening procedure which measures total volatile organic compounds (TVOCs). Soil samples submitted for laboratory analyses were collected, based upon elevated headspace readings, marked changes in soil strata, or, in the absence of overt evidence of oil or hazardous material (OHM) contamination, proximity to the apparent water table.

---

### Right-Of-Way Waste Disposal Area

A series of test pits were excavated using a Case 580 backhoe to observe and document the nature and extent of fill material previously identified within Northeast Utilities overhead electric right-of-way (ROW) located in the Site's eastern sector. Each test pit was excavated through the existing fill material to the interface with the underlying natural soil layer. Eleven test pits were excavated within the ROW to depths ranging from four to ten feet below existing grade. Test pits were designated as ROW/TP-1 to ROW/TP-11. Test pit logs are included in Appendix C.

Fill materials consisting of white ash, metal, glass, cinders, and some brick were identified in test pits ROW/TP-1 through ROW/TP-5 and ROW/TP-8. The ash fill layer extended from ground surface to 2-5 feet below grade. Various ash layers of suspect prussian blue and green material were observed within these test pits. No overt evidence

(visual or olfactory) of OHM was observed within these six test pits. Reddish-brown silty soil with some clay was observed beneath the fill layer within each test pit. Soil samples were collected from ROW/TP-1 and ROW/TP-3 and submitted for analysis for 13 priority pollutant metals and semi-volatile organic compounds (SVOCs) by EPA Method 8270 in accordance with the site investigation work plan. VHB also submitted soil samples for total cyanide analysis with prior City approval.

Fill materials containing melted rock/metal/slag, glass, metal, and some brick were identified in test pits ROW/TP-6, ROW/TP-7, and ROW/TP-9. The fill extended from ground surface to five to seven feet below grade. Mild petroleum odors were observed within TP-7. Oil saturated soil was observed in TP-9 from 6.5 to 8.5 feet below grade. Soil samples were collected from ROW/TP-6, ROW/TP-7, and ROW/TP-9 and submitted for analysis for total petroleum hydrocarbons (TPH) by EPA Method 418.1, 13 priority pollutant metals, SVOCs by EPA Method 8270, and volatile organic compounds (VOCs) by EPA Method 8240.

Fill materials were encountered in test pit ROW/TP-10 which consisted of glass, metal, and some brick. No ash material was observed within this test pit. Fill was observed from ground surface to a depth of two feet. Strong solvent/motor oil odors were observed from a depth of four to six feet below grade within this test pit. Dark brown silty clay was observed from six to seven feet. No solvent or motor oil odors were observed at this depth. Soil samples were collected from ROW/TP-10 and submitted for analysis TPH by EPA Method 418.1, 13 priority pollutant metals, SVOCs by EPA Method 8270, and VOCs by EPA Method 8240.

Fill material were observed in ROW/TP-11 to a depth of three to four feet below grade. Fill consisted of alternating layers of brown, white, and gray plastic resin. The plastic resin had apparently been poured on the surface, solidified and covered with additional fill. The plastic resin did not extend past the three foot depth horizon. Soil samples were collected from ROW/TP-11 and submitted for analysis TPH by EPA Method 418.1 and SVOCs by EPA Method 8270.

Representative soil samples were collected from test pits ROW/TP-1, ROW/TP-3, ROW/TP-6, ROW/TP-7, and ROW/TP-9 to ROW/TP-11 to characterize right-of-way fill materials. Similar fill materials identified in adjacent test pits ROW/TP-2, ROW/TP-4, ROW/TP-5, and ROW/TP-8 were not sampled in accordance with the RFP.

---

## Underground Storage Tank Investigation

To investigate for the presence of underground storage tanks (USTs) and to help identify subsurface impacts within existing and former UST locations, test pits were excavated within the four existing/former UST locations identified in the Phase I Report.

---

**UST 1 Area**

Three test pits were excavated within in the vicinity of suspect UST 1, as shown on Figure 2. The three test pits are designated as UST1/TP-1 to UST1/TP-3. Test pits UST1/TP-1 and UST1/TP-3 were excavated to a depth of approximately four feet. Groundwater was encountered at a depth of four feet in both test pits. No overt evidence of OHM releases were observed in either test pit. PID field screening results from a soil sample collected at the groundwater interface within UST1/TP-1 did not detect any TVOC concentrations. Test pit UST1/TP-2 was terminated at a depth of two feet after encountering an undocumented two-inch steel pipe.

No soil samples were collected for analyses from these test pits. No existing USTs or evidence of former USTs were observed within the test pits excavated within this area of the Site.

---

**UST 2 Area**

One test pit was excavated near suspect UST 2 (see Figure 2). Site constraints (i.e., concrete slab, subsurface electric, water, and steam lines), permitted the excavation of only one test pit (UST2/TP-1) to a depth of approximately 6.5 feet where groundwater was encountered. At a depth of five to seven feet below grade, strong gasoline odors were encountered within a light gray silty sand layer. PID field screening results from a sample collected at a depth of six feet identified a TVOC concentration of 75 parts per million (ppm).

No USTs were located within the test pit; however, subsurface contamination indicates that a UST may exist near UST2/TP-1 test pit location. Soil samples were collected from UST2/TP-1 and submitted for analysis for TPH by EPA Method 418.1, VOCs by EPA Method 8240, and total lead.

During the attempted excavation of a test pit near suspect UST 2, approximately ten, six-inch long by two-inch diameter artillery shells were identified, as shown in Photograph 3 included in Appendix B. Following VHB's report of the discovery to City officials, the Middletown Police and Connecticut State Police responded to the Site. The artillery shells were identified as tank artillery shells used during World War II. The shells contained no explosive charge and were deemed to be harmless.

---

**UST 3 Area**

Three test pits (UST3/TP-1 to UST3/TP-3) were excavated in the vicinity of suspect UST 3 (see Figure 2). Test pit UST3/TP-1 was excavated to a depth of approximately six feet. Groundwater was not encountered within this test pit. Rock and melted rock/metal/slag was observed from zero to two feet below grade. Mild tar odors were also observed throughout the zero to two foot depth interval. From two to four feet

below grade, a very hard, dark black tar layer was encountered. Natural soil was encountered from a depth of four to six feet.

Soil samples were collected from UST3/TP-1 from within the rock/slag fill layer and within the tar later and submitted for analysis for TPH by EPA Method 418.1, SVOC by EPA Method 8270, 13 priority pollutant metals, and polychlorinated biphenyls (PCB) by EPA Method 8080.

Within this area of the Site, four concrete tank cradles were identified which formerly supported two aboveground storage tanks (ASTs). Two test pits were excavated between the cradles. Reddish brown silty soil with some clay was observed in both test pits to a depth of six feet. No overt evidence of OHM was observed within these two test pits. No existing USTs or evidence of former USTs were observed within the test pits excavated in this area of the Site.

---

## UST 4 Area

One test pit (UST4/TP-1) was excavated adjacent to an existing fill pipe near UST 4. The test pit identified one 500 gallon single-walled steel UST which was full of water. The water in the tank did not display any sheens or odors. The UST's proximity to adjacent building, steam lines, and concrete pad prevented the excavation of additional test pits around the remaining sides of the tank.

Light brown fine silty sand was encountered to a depth of eight feet in the UST4/TP-1 test pit. No overt evidence of OHM was observed within the zero to eight foot depth interval. From a depth of eight to nine feet below grade, light brown fine to medium sand with strong gasoline/solvent odors was observed. Groundwater was encountered at a depth of eight feet. PID field screening results from a sample collected at a depth of eight to nine feet identified a TVOC concentration of 492 ppm. Sheens were observed on groundwater entering the test pit. Soil samples were collected from UST4/TP-1 and submitted for analysis for TPH by EPA Method 418.1, VOC by EPA Method 8020, and total lead.

---

## Electrical Transformers

Four active pole-mounted electrical transformers and the location of one former pole-mounted electrical transformer were identified on the Site. Surficial soil samples (0 to 1 foot) were collected beneath each of the five existing/former transformer locations. Each sample collected was composited from four discrete sample locations beneath each transformer. Composite soil samples collected were submitted for analysis for PCBs by EPA Method 8080.

Sampling of electrical transformer oil was not conducted since the transformers were connected to the power grid. Based on the age of the transformers, it is likely that the transformer oil contains PCBs.

On June 9, 1997, VHB contacted Northeast Utilities to confirm ownership of the existing transformers. Based on information made available to VHB, the transformers located at the Site belong to Northeast Utilities. Northeast Utilities is responsible for transformer maintenance and disposal.

---

## Aboveground Storage Tank Investigation

Two aboveground storage tanks (ASTs) were identified to the east of the Building 7, as shown on Figure 2. The tanks are 1,000 and 20,000-gallon single-walled steel vessels (AST 1 and AST 2, respectively). The 1,000-gallon AST contains four inches (approximately 50 gallons) of No. 2/No. 4 fuel oil and sludge. The 20,000-gallon AST contains four feet (approximately 6,500 gallons) of No. 4 fuel oil and sludge.

Surficial soil conditions (0-1 foot) were assessed by collecting soil samples with a hand auger beneath each AST. No stained soil was observed beneath AST 1. Fuel oil-saturated soil was observed at the south end of AST 2. The AST 2 impacted soil area was limited to an approximate 20 square foot area and a depth of approximately one foot. No soil samples were submitted for laboratory analyses from this location.

---

## Surficial Stained Soil

Two surficial stained soil areas with stressed vegetation were observed south of the Main Building (see Figure 2). Soil samples were collected in Areas 1 and 2 using a hand auger from a depth of zero to one foot. Stained soil within Area 1 was identified to a depth of two feet below grade with an approximate area of 1,500 square feet. The soil within Area 1 consisted of black, fine to medium with coal ash/slag.

Surficial soil conditions in Area 2 were similar as to Area 1. Stained soil within Area 2 continued to a depth of two feet below grade within an approximate area of 250 square feet. One composite sample was collected from each surficial stained area and submitted for analysis for SVOC by EPA Method 8270, 13 priority pollutant metals, and PCBs by EPA Method 8080.

## Soil Boring and Groundwater Monitoring Well Installations

To further assess release conditions identified during the test pit investigation program, GeoProbe® soil borings were advanced within suspect contaminant source areas at the Site. A total of 25 soil borings, designated as B-1 to B-25, were advanced near identified areas of environmental concern. Soil boring locations are shown on Figure 2. Soil boring advancement and groundwater monitoring well installation activities were conducted on May 20 and May 21, 1997 by Technical Drilling Services (TDS) of Leominster, Massachusetts. VHB directed the field investigation, observed soil conditions, screened soil samples, and collected soil and groundwater samples. Photographs illustrating the soil boring advancement and groundwater monitoring well installation activities are presented in Appendix B.

---

### GeoProbe Soil Sampling

Soil borings were advanced by a van-mounted GeoProbe®, enabling continuous sampling from ground surface to approximately 12 feet below grade. Soil samples were collected by the GeoProbe® using one- and two-inch diameter stainless steel core barrels with dedicated acetate sleeve liners. Soil samples were collected to characterize existing soil conditions during each boring advancement. Soil boring logs are included in Appendix C.

Various soil samples were field screened using a photo-ionization detector (PID) calibrated to an isobutylene standard. Samples were field screened using a standard methodology for the jar headspace analytical screening procedure. Field screening results are summarized in the soil boring reports included in Appendix C. Soil samples submitted for laboratory analyses were collected from depth intervals that indicated elevated headspace readings, marked changes in soil strata, or, in the absence of overt evidence of oil or hazardous material (OHM) contamination, proximity to the apparent water table.

In general, native soil at the Site consists of a light brown fine to medium sand with some silts to a depth of 10 to 12 feet. A light brown silty clay layer was observed throughout the Site at a depth of 12 feet and greater. The following findings were made during soil boring advancement activities:

- Fill materials were observed from ground surface to 4-6 feet below grade within the right-of-way area and at soil boring location B-10.
- Mild solvent odors were observed at a depth of eight to 12 feet in soil borings B-1, B-2, and B-3. PID screening results from the 10 to twelve foot depth interval ranged from 3.3 to 7.2 parts per million (ppm). As indicated by field screening results, the solvent odors were not observed at the groundwater interface, but were generally observed below encountered groundwater just above the clay confining layer.
- Soil boring B-4 identified fill to depths of four feet. Strong gasoline odors (PID result of 142 ppm) were observed at an approximate depth of two feet and strong motor oil odors (PID result of 39 ppm) were observed at a depth of six to ten feet below grade. The clay layer was encountered at a depth of 11.5 feet.
- Soil borings B-5, B-6, and B-7 were advanced near a suspect UST location. Strong gasoline odors, with associated PID screening results up to 138 ppm, were observed at a depth of six to ten feet below grade in soil boring B-5. Mild gasoline odors, with associated PID screening result up to 4 ppm, were observed in soil boring B-7 and no odors were observed in B-6. Soil samples were not submitted from B-6.
- Soil boring B-8 was advanced within the right-of-way. Fill materials consisting of ash, coal, and metal were observed in B-8, similar to fill observed within adjacent test pits. Mild gasoline/solvent odors were observed from six to twelve feet below grade. PID screening results within this depth interval ranged from 4 to 22 ppm.
- Soil boring B-9 was advanced on the north side of the concrete containment system surrounding the 20,000-gallon AST near the Site's eastern perimeter. Fuel oil-saturated soil (No. 4 or No. 6 fuel oil) was observed from a depth of eight to twelve feet below grade.
- A heavy tar layer was observed at a depth of six feet in soil boring B-10. Fill material containing coal, coal ash, slag, and metal was observed to a depth of six feet similar to fill observed in the nearby test pit UST3/TP-1.
- Soil borings B-11 to B-17 did not indicate any overt evidence of oil or hazardous materials. Soil samples were not submitted from soil borings B-14 and B-17.
- Soil borings B-18, B-21, B-22, B-24 displayed strong gasoline/diesel fuel odors from four to ten feet below grade. PID screening results for these four soil borings ranged from 5 to 224 ppm. Soil boring B-23 did not display any gasoline/diesel fuel odors. Based on soil boring data, a magnetometer survey was conducted between borings B-18 and B-23. Survey results identified an area that may contain one or more undocumented USTs. This area is identified as suspect UST 5, as shown on Figure 2.

- No overt evidence of OHM was observed in soil borings B-19 and B-20. Soil boring B-25 identified an organic septic sludge at a depth of eight to ten feet below grade. No other indication of OHM was observed within soil boring B-25.

Following sample collection and preservation on ice, soil samples were submitted to a Connecticut-certified laboratory and analyzed for selected target analytes. Based on field observations, the samples were submitted for TPH, VOCs, SVOCs, metals, and/or PCBs.

## Groundwater Monitoring Well Installation and Sampling

Phase II investigation activities included the installation and sampling of six overburden groundwater monitoring wells (see Figure 2). Groundwater sampling was conducted to assess the potential adverse impacts to local groundwater quality from the identified contaminant source areas and the potential migration of leachate from the adjacent municipal landfill.

The six monitoring wells (MW-1 to MW-6) were installed to depths of 12 to 16 feet below grade within soil borings B-3, B-7, B-8, B-10, B-14, and B-18. Each well was constructed of 3/4-inch diameter PVC well materials with ten feet of screen. A sand pack was placed from the soil boring terminus to one foot above the screen followed by a clay bentonite seal. Each well was either capped and locked with a protective riser pipe or a flush-mounted road box. Each well was completed at a depth (approximately 12 feet) that was consistent with penetrating less than six to twelve inches of the silty clay soil confining layer observed throughout the Site. None of the soil borings penetrated throughout the entire thickness of the identified confining layer.

On May 27, 1997, VHB purged and sampled the six monitoring wells. Three to five well volumes of groundwater were removed from the wells prior to sampling. After well stabilization, groundwater samples were collected using dedicated disposable bailers for VOC sample collection. A peristaltic pump equipped with dedicated teflon tubing for each of the site monitoring wells was used to collect samples for analyses of the remainder of the groundwater parameters. Groundwater sample collection was performed in accordance with the USEPA Region I Low Stress (low flow) Purging and Sampling Procedures for the Collection of Groundwater Samples from Monitoring Wells, dated July 30, 1996. All groundwater samples were preserved on ice and delivered to a Connecticut-certified laboratory for chemical analyses.



In addition to sampling the six wells for TPH, VOCs, SVOCs, PCBs, metals, and herbicides, monitoring wells MW-3 and MW-5 were sampled for landfill leachate parameters (i.e., BOD 5-day, chloride, nitrate, ammonia, total iron, total manganese, total dissolved solids, total suspended solids, pH, specific conductance, and alkalinity) in accordance with the Request for Proposal (RFP) prepared by City of Middletown.

## Groundwater Elevations and Flow Direction

On June 12, 1997, the casings for all six monitoring wells were surveyed to determine groundwater elevations. As shown on Figure 2, an assumed datum of 100 feet was set at a utility pole #8400 located near the Johnson Street entrance to the Site. All measurements are based on this assumed datum. The following data were recorded during groundwater gauging and wellhead surveying activities:

| Monitoring Well | Existing Ground Surface<br>Elevation (feet) | Depth to Groundwater from<br>Ground Surface (feet) |
|-----------------|---------------------------------------------|----------------------------------------------------|
| MW-1            | 96.2                                        | 90.2                                               |
| MW-2            | 96.9                                        | 89.62                                              |
| MW-3            | 93.2                                        | 86.01                                              |
| MW-4            | 96.5                                        | 87.27                                              |
| MW-5            | 97.6                                        | 89.53                                              |
| MW-6            | 95.4                                        | 91.0                                               |

Note: Apparent water table elevations were gauged on May 27, 1997.

Apparent water table elevations vary from approximately four to nine feet below ground surface across the Site. Triangulation of apparent water table elevations between groundwater monitoring wells indicates that local groundwater flows across the Site in an easterly to northeasterly direction.

## Soil and Groundwater Analytical Results

This section summarizes the soil and groundwater analytical results related to subsurface investigation activities at the Site. Soil and groundwater laboratory analytical results were compared to applicable standards established by the Connecticut Department of Environmental Protection Remediation Standard Regulations (RSR), Section 22a-133k to help assess regulatory compliance issues for the Site.

---

### Soil Analytical Results

All soil analytical results are summarized in Tables 1 and 2. Applicable RSR Residential Direct Exposure Criteria, Industrial/Commercial Direct Exposure Criteria, and Pollutant Mobility Criteria for GB areas (RSR standards) are listed in Tables 1 and 2. Laboratory analytical reports are included in Appendix D.

---

### Right-Of-Way Disposal Area

Eleven soil samples were submitted for analysis for various target analytes from within the right-of-way waste disposal area located in the northeastern sector of the Site. TPH, arsenic, lead, and copper concentrations were reported above applicable RSR standards in samples ROW/TP-06/3'-4', ROW/TP-07/2'-3', ROW/TP-09/6'-8', ROW/TP-10/4'-6', B-4/0'02', B-4/8'-10', and B-08/8'-10'.

---

### Underground Storage Tank Release Areas

Three release areas in the vicinity of existing or suspect former UST locations were identified during test pitting and GeoProbe® activities. Laboratory results for soil samples UST2/TP-01/6' and B-5/6'-8', collected from suspect UST 2 area, reported TPH concentrations ranging from 4,490 milligrams per kilogram (mg/kg) to 9,380 mg/kg which exceeds applicable RSR standards.

Laboratory results for soil sample UST4/TP-01/8', collected from the existing UST 4 area, reported a TPH concentration of 37,700 mg/kg which also exceeds applicable RSR standards.

Laboratory analytical results for soil sample B-18/5'-7', reported a TPH concentration of 5,200 mg/kg. Additional soil borings (B-21, B-22, and B-24), advanced for initial delineation purposes near B-18, identified characteristically similar strong petroleum odors and elevated field headspace results. Based on the overt evidence of a release, a magnetometer was used to help identify the potential presence of a nearby UST source. As shown on Figure 2, the area south of B-18 was identified as a possible location of one or more undocumented UST(s).

---

### **Railroad Spur Waste Disposal Area**

A waste disposal area was identified within the southeastern corner of the Site (see Figure 2). Soil samples collected from within this area, UST3/TP-01/0'-2', UST3/TP-01/3'-4', and B-10/6'-7', identified TPH, SVOCs, arsenic, copper, lead, nickel, and thallium concentrations that exceed their respective RSR standard, as shown in Tables 1 and 2.

---

### **Electrical Transformers**

Surficial soil samples were collected from beneath each of the four existing and one former electrical transformer location. PCB concentrations were reported to range from 0.383 mg/kg to 1.68 mg/kg. All five PCB concentrations reported are below the RSR Industrial/Commercial Direct Exposure Criterion of 10 mg/kg; however, PCB concentrations from two of the five samples (Tran-2 and Tran-4) exceeds the RSR Residential Direct Exposure Criterion of 1 mg/kg.

---

### **Aboveground Storage Tank Release Area**

Laboratory analytical results for soil boring, B-9, advanced north of the 20,000-gallon fuel oil AST, reported a TPH concentration of 62,500 mg/kg and an arsenic concentration of 42.9 mg/kg at a depth of nine to 11 feet below grade. Both the TPH and arsenic concentrations exceed their respective RSR standards. The release identified in B-9 may be associated with the AST; however, surficial soil observations directly beneath the AST were inconclusive.

---

### **Surficial Stained Soil Areas**

Surficial soil samples (Sur-1 and Sur-2) were collected from a depth of zero to one feet within the two surficial stained areas. As shown in Table 2, arsenic and various semi-volatile organic compounds (SVOC) were reported at concentrations which exceed their respective RSR standards.

---

## SPLP Soil Sample Results

In accordance with the RFP, the Synthetic Precipitation Leaching Procedure (SPLP) was performed on soil samples which were reported to contain metal concentrations that exceed the "20 times" rule for leachability when compared to applicable RSR GB Pollutant Mobility Criteria (PMC) standards. Based on the reported metal results, 12 samples contained metal concentrations which exceed 20 times the applicable PMC. The 12 soil samples were reanalyzed for 13 priority pollutant metals by SPLP. The results are summarized in Table 4. Based on the reported SPLP metal results, three samples (UST3/TP-1/0-2', ROW/TP-6/3'-4', and B-10/6'-7') contained nickel and/or lead concentrations which exceeded the applicable PMC.

---

## Groundwater Analytical Results

Groundwater analytical results are summarized in Table 3. RSR Surface Water Protection Criteria, Residential Volatilization Criteria, and Industrial/Commercial Volatilization Criteria (RSR standards) are shown in Table 3. Laboratory analytical reports are included in Appendix D.

---

## Right-Of-Way Waste Disposal Area

Monitoring well MW-3 was installed within the right-of-way to assess groundwater impacts associated with fill materials located within the right-of-way and the potential migration of leachate from the adjacent municipal landfill. Significant findings include:

- No RSR standards were exceeded in monitoring well MW-3 installed within the right-of-way.
- Based on the reported results for landfill leachate parameters, no indications of landfill leachate impacts to Site groundwater were observed in MW-3.

---

## Underground Storage Tank Release Areas

Monitoring wells MW-1, MW-2, and MW-6 were installed in the presumed downgradient position with respect to confirmed and suspect UST locations, as shown on Figure 2. Significant findings include:

- Monitoring well MW-1 was installed to the south of the Quonset Building. As shown in Table 3, trichloroethylene, 1,1-dichloroethylene, and vinyl chloride and zinc exceeded their respective RSR standards.

- No RSR standards were exceeded in monitoring well MW-2 installed to the north of suspect UST 2.
- No RSR standards were exceeded in monitoring well MW-6 installed to the north of suspect UST 5.

---

### **Waste Disposal Area**

Monitoring well MW-4 was installed within the waste disposal area located in the southeast corner of the property. Reported copper and zinc concentrations exceeded applicable RSR standards.

---

### **Suspect Landfill Leachate Area**

Monitoring well MW-5 was installed in the northern corner of the Site to assess potential groundwater impacts associated with the migration of leachate from the adjacent municipal landfill. The following significant results are noted:

- No RSR standards were exceed in monitoring well MW-5.
- Based on the reported results for landfill leachate parameters, no indications of landfill leachate impacts to Site groundwater were observed in MW-5.

## Regulated Building Components and Hazardous Materials Inventory

VHB conducted an environmental building audit at the Site to identify regulated building components and the presence of other regulated hazardous materials. The following materials were identified:

- Asbestos-containing materials (ACM);
- Building components coated with Lead-Based Paint (LBP);
- Items which contain Polychlorinated Biphenyls (PCBs);
- Mercury-containing lamps/tubes;
- Equipment which contain chlorofluorocarbons (CFCs); and
- Miscellaneous containers of oil and other hazardous materials (OHM).

An interview with the caretaker of the property, Mr. John Erickson was performed prior to commencing the inspection. Mr. Erickson provided information related to locations of suspect asbestos-containing materials (ACM), suspect lead-based paint (LBP), and locations of abandoned miscellaneous oil and hazardous materials (OHM).

---

### Asbestos Material Inspection

A comprehensive building inspection was performed in all accessible interior and exterior areas of all structures located at the site. Pursuant to the RFP from the City of Middletown, three samples of all suspect friable (easily crumbled or crushed to powder by hand pressure) and nonfriable ACM were collected in analyzed for asbestos content. If a material was determined to contain greater than 1 percent asbestos, it is considered an ACM pursuant to State of Connecticut Department of Health Services regulations located at Chapter 19a-332a-1(h). Mr. Tim Downey of VHB performed the inspection and is certified by the DHS as an Asbestos Inspector/Management Planner (000062).

Bulk sample analysis was performed using Polarized Light Microscopy with Dispersion Staining (PLM/DS) in accordance with EPA protocol (Title 40 CFR,

"Interim Method for the Determination of Asbestos in Bulk Insulation Samples", October, 1987) by Hygeia Proscience, Inc. laboratory located in Woburn, Massachusetts. A total of 63 samples of suspect ACM were collected and submitted for laboratory analyses. Each suspect material was assigned a homogeneous area (HA) number. A homogeneous area as defined by EPA is an area of surfacing material, thermal system insulation or miscellaneous material that is uniform in color and texture and materials appeared to have been installed at the same time. Samples of the following suspect materials were collected and submitted for analysis:

- Floor tiles and associated mastic adhesives or paper backings;
- Spray-applied fireproofings/insulations;
- Sheet rock/joint compounds;
- Interior fire door insulations;
- Floor and ceiling plasters;
- Paper-type pipe insulation;
- Block-type pipe insulation;
- Cementitious wall board (transite) ;
- Roof flashing cements;
- Plaster;
- Asphaltic roofing materials; and
- Asphaltic roofing shingles.

Asbestos sample locations are shown on Figures 3a, 3b, and 3c.

## Asbestos Sampling Inspection Results

The following materials were determined to contain greater than one percent asbestos:

- Interior fire door insulation (2 doors);
- Paper-type pipe insulation (1,825 linear feet);
- Block-type pipe insulation (715 linear feet);
- Plaster (125 square feet);
- Transite electrical switches (260 square feet); and
- Floor tiles (9"x 9") and associated mastics (2,200 square feet).

A summary table of suspect and identified ACM at the facility are included in Appendix E along with the laboratory analytical results.

## Lead-Based Paint Inspection

A lead inspection was performed using the State of Connecticut, Department of Health Services regulations (Chapter 19a-111) as a guideline. The surface of each different painted building component was tested for total lead concentration. Toxicity Characteristic Leaching Procedure (TCLP) testing of selected LBP-coated building materials was not performed during the assessment.

The interior surfaces of the buildings were visually inspected for surfaces coated with paint to identify different colors of paint, approximate quantities of building components coated with paint, and locations of the painted components. The survey was performed with an X-Ray Fluorescence (XRF) spectrum analyzer. A Niton Corporation (Model XL-309; Serial # 278) was used to determine lead in paint concentrations during this inspection. The concentrations were reported as milligrams per square centimeter ( $\text{mg}/\text{cm}^2$ ) of surface area. The XRF uses a radioactive source which excites lead atoms when present. As the atoms return to their normal state, they emit x-rays that are characteristic of lead, if present. The XRF identifies and quantifies these x-rays to provide a lead concentration in  $\text{mg}/\text{cm}^2$  of surface area. LBP was also inspected to provide the demolition/renovation contractor with information to take appropriate actions to protect employees and the environment (OSHA, 29 CFR, Part 1926.62, "Lead Exposure in Construction").

## Lead-Based Paint Inspection Results

Building components testing greater than  $2.5 \text{ mg}/\text{cm}^2$  should be segregated from general construction/demolition debris and recycled at appropriately licensed facilities and or disposed as RCRA-hazardous waste, as these materials generally do not pass hazardous waste characterization analysis. The following materials are recommended for segregation:

- |                          |                          |
|--------------------------|--------------------------|
| ➤ Fire doors             | ➤ Exterior shed          |
| ➤ Door jambs             | ➤ Exterior siding        |
| ➤ Window sashes          | ➤ Metal hand rails       |
| ➤ Window casings         | ➤ Concrete equipment pad |
| ➤ Doors                  | ➤ Metal hot water tank   |
| ➤ Walls (brick and wood) | ➤ Overhead garage doors  |
| ➤ Stairwell newel posts  | ➤ Red structural beams   |
| ➤ Inside stairwell walls |                          |

Locations and quantities of the above listed building components are identified in the summary table included in Appendix F.



Detectable levels of lead ( $> 0.1$  and  $< 1.2$  mg/cm<sup>2</sup>) were identified on several other building components. A summary table of LBP field testing results at the facility are included in Appendix F, along with the laboratory analytical results. This information should be provided in bidding documents for any demolition or renovation work scheduled to occur. Employees who are occupationally exposed to LBP at or above the OSHA Action Level of 30 micrograms per cubic meter of air ( $\mu\text{g}/\text{m}^3$ ) must receive hazardous waste training in accordance with OSHA, 29 CFR, Part 1910.120 ("Hazard Communication Standard").

### Polychlorinated Biphenyl and Mercury-Containing Equipment

The following quantities of PCB-containing light ballasts and mercury-containing light bulbs were observed:

| Building #                            | Ballasts                                 | Bulbs (four-foot long bulbs)                     |
|---------------------------------------|------------------------------------------|--------------------------------------------------|
| 1A, 1st Floor                         | 18                                       | 58                                               |
| 1A, 2nd Floor                         | 73                                       | 104                                              |
| 1B, 1st Floor                         | 18                                       | 43                                               |
| 1B, 2nd Floor                         | 59                                       | 96                                               |
| 1C, 1st Floor                         | 33                                       | 63                                               |
| 1C, 2nd Floor                         | 25                                       | 39                                               |
| 2                                     | 10                                       | 18                                               |
| 3                                     | 1                                        | 2                                                |
| 4                                     | 16                                       | 32                                               |
| 5                                     | 9                                        | 6                                                |
| 6, 1st Floor                          | 8                                        | 16                                               |
| 6, 2nd floor                          | 9                                        | 18                                               |
| 7                                     | 5                                        | 10                                               |
| 8, 1st Floor                          | 59                                       | 31                                               |
| 8, 2nd Floor                          | 21                                       | 41                                               |
| Hall between 8 & 1C (1st & 2nd floor) | 3                                        | 7                                                |
| 9, 1st Floor                          | 19                                       | 33                                               |
| 9, 2nd Floor                          | 24                                       | 53                                               |
| 11A to 11D                            | 81                                       | 187                                              |
| <b>Total</b>                          | <b>491 <math>\pm</math> PCB Ballasts</b> | <b>857 <math>\pm</math> Four Foot Long Bulbs</b> |

In addition to the four-foot mercury-containing fluorescent tubes, a total of 12 mercury vapor lights were identified in buildings 1C, 2, and 3.

## Interior Drainage Inlet Structures

Based on the results of the Phase I Report prepared by Soil Science and Environmental Services, Inc. and the RFP, a "black liquid sludge" was observed in various floor drains and trenches located in buildings 5, 10, and the addition between buildings 1 and 8. The location of the addition was interpreted by VHB to be building 12 as labeled by VHB. Accessible interior floor drains, inlet structures, and trenches were observed throughout every room. No indication of OHM were observed in any structure inspected, with the exception Quonset Building. The following observations and structures were observed (see Figure 2):

| Building #       | Quantity Observed                             | Observation                                                                                                                                                                                        |
|------------------|-----------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 5                | Six circular floor drains                     | No staining, sludge, or fluids observed within drainage inlet structures observed.                                                                                                                 |
| 7                | Two circular floor drains                     | No staining, sludge, or fluids observed within drain inlet structures observed.                                                                                                                    |
| 10               | One concrete vault and one square floor drain | Concrete vault was dry with a clean soil bottom. Floor drain filled to top with water. No sheens or odors on water. Sediments within drain did not display evidence of oil or hazardous materials. |
| 11B              | Three circular floor drains                   | No staining, sludge, or fluids observed within drain inlet structures observed.                                                                                                                    |
| 11D              | One circular floor drain                      | Visual staining and olfactory evidence of oil and hazardous materials discharged to floor drain.                                                                                                   |
| 12               | Two square floor drains                       | No staining, sludge, or fluids observed within drain inlet structures observed.                                                                                                                    |
| Quonset Building | One square floor drain                        | Drain contained overt and olfactory evidence of oil and hazardous materials. Drain structure did not appear to have an outlet pipe or a solid base.                                                |

Many rooms contained equipment used by tenants. Additional drains may be present, but were not observed during the site walk since access was obstructed.

The floor drain identified within the Quonset Building was sampled for TPH, PCBs, and herbicides. TPH and PCB concentrations were reported at 148 mg/kg and 0.383 mg/kg, respectively. Both concentrations are below their respective DEP Industrial Soil Standards. Herbicides concentrations were not reported above laboratory method detection limits.

## Metal Dust

Wipe samples were collected from various surfaces within rooms nickel plating, metal casting, and carbon coating operations were historically conducted. Wipe samples were collected from the following locations:

| Building # | Quantity | Wipe Sample Location                                             |
|------------|----------|------------------------------------------------------------------|
| 4          | 2        | East and west window sill                                        |
| 5          | 3        | East window sill, top of fire door, and top of electrical switch |
| 10         | 3        | Floor, north and south window sill                               |

Wipe samples were submitted for analysis for 13 priority pollutant metals. As shown in Table 4, antimony, arsenic, beryllium, cadmium, chromium, copper, lead, mercury, nickel, selenium, silver, and zinc were reported above laboratory method detection limits in many of the wipe samples submitted. The Connecticut Department of Public Health (DPH) has established a 500 microgram per square centimeter ( $\mu\text{g}/\text{cm}^2$ ) standard for lead wipe samples collected to assess indoor air quality. Lead results for wipe samples collected in Buildings 4, 5, and 10 were reported well below the 500  $\mu\text{g}/\text{cm}^2$  lead standard. No similar DPH or other DEP standards exist for the remaining 13 priority pollutant metals.

## Hazardous Materials Inventory

During the Site reconnaissance, VHB identified abandoned miscellaneous quantities of OHM containers throughout the buildings that would require removal prior to any scheduled building demolition or renovation. In general, the following materials were identified:

- Motor oil
- Solvents
- Greases
- Oils
- Roof sealant
- Corrosive liquids
- PCB fluids
- Pressurized paint cans
- Liquid cleaners
- Fuel oil
- Insecticides/herbicides
- Pressurized gas cylinders
- Latex and oil-based paints
- CFC-containing equipment

A full inventory of quantities of each type of material and location is included in Appendix G. Materials were inventoried if it was apparent that they were abandoned and not in use by tenants. Following departure of various tenants, OHM quantities will most likely change and an updated inventory should be compiled.

## Regulatory Compliance Issues

The Phase II Environmental Site Assessment identified soil and groundwater impacts at the Site that require response actions in accordance with Connecticut Department of Environmental Protection (DEP) Remediation Standard Regulations (RSR) Section 22a-133k. Environmental impacts at the Site have been attributed to past industrial/commercial work practices, known and suspect on-site contaminant sources, and/or activities on adjacent properties.

Laboratory test results for soil and groundwater samples collected during Phase II investigation activities were compared to applicable RSR standards to assess whether residual contaminant concentrations pose an unacceptable risk to human health associated with direct exposure (i.e., dermal contact, ingestion, or inhalation) or the environment associated with pollutants migrating from soil to groundwater. Although VHB understands that the City intends for the Site to remain in industrial/commercial use, the RSRs require comparison of soil and groundwater test results to applicable residential as well as industrial/commercial cleanup standards. This section outlines DEP environmental compliance options and associated remediation alternatives to address the identified contaminant release areas at the Site.

### Soil and Groundwater Cleanup Objectives

DEP Residential Direct Exposure Criteria, Industrial/Commercial Direct Exposure Criteria, and Pollutant Mobility Criteria for GB Areas (RSR standards) apply to the Site's soil. Residential Direct Exposure Criteria for soil apply to the Site since the RSRs require, whenever feasible, a reduction in residual soil contaminant concentrations to levels that pose no significant human health risk. Under circumstances where remediation activities are prohibitively expensive or technically unfeasible, the Site owner has the option to institute an Environmental Land Use Restriction (ELUR; ref. RSR Section 22a-133q-1) limiting future Site use solely for industrial/commercial purposes.

DEP Surface Water Protection Criteria, Residential Volatilization Criteria, and Commercial/Industrial Volatilization Criteria (RSR standards) apply to the Site's Class GB groundwater. Although groundwater is not used as a private or public water supply or other resource, groundwater analytical results have been compared to residential volatilization criteria for reasons similar to those noted above.

---

## Soil Contaminant Releases

Based upon comparisons to applicable RSR standards, VHB identified ten soil contaminant release areas during the Phase II Environmental Site Assessment activities requiring further action in accordance with RSR provisions. The following section discusses how each identified soil contaminant release area may be addressed under the RSRs and suggest appropriate soil management strategies. Preliminary estimates of probable remediation costs associated with each release area are presented in the Chapter 8.

---

### Right-Of-Way (ROW) Waste Disposal Area

Three characteristically different fill materials — coal ash, slag-like melted metal/glass, and variable layered plastic resin/darkly stained soil — were identified within the ROW waste disposal area. Test pits ROW/TP-1 through ROW/TP-5 identified coal ash containing a granulated matrix with detected inorganic concentrations below applicable RSR standards (i.e., Residential and Industrial/Commercial Direct Exposure Criteria and Pollutant Mobility Criteria). Test pits ROW/TP-6 through TP-9 identified slag-like materials with concentrations of total petroleum hydrocarbon (TPH), arsenic, copper, and lead above applicable RSR standards. Test pit ROW/TP-10 and Boring B-4 identified variable layered plastic resins and impacted soil containing residual TPH concentrations in soil above the corresponding RSR standard.

Lead, measured by the Synthetic Precipitation Leaching Procedure (SPLP), was the only one of the 13 priority pollutant metals that exceeded the applicable Pollutant Mobility Criterion for GB Areas (PMCs; ref. Table 1, Test Pit ROW/TP-6 soil result). No corresponding groundwater impacts above applicable RSR standards were identified at nearby Monitoring Well MW-3 located in the central portion of the ROW waste disposal area.

Based upon current information, two compliance options for management of ROW fill materials containing soil contaminant concentrations above applicable RSR standards have been identified. The first option includes soil excavation and off-site disposal of contaminated soil at a Subtitle C RCRA landfill. This remediation approach is appropriate if the City chose to use the ROW area for parking since existing compressible fill materials would have to be excavated and replaced to meet geotechnical load bearing requirements. Contaminated fill removal activities at the Site will eliminate exceedances of applicable RSR Residential Direct Exposure Criteria and PMCs, resulting in unrestricted future use of the ROW area.

The alternative option includes pursuit of a variance from the DEP under exemptions provided for Widespread Polluted Fill or Engineered Control of Polluted Soil under RSR Sections 2(f)(1) and 2(f)(2), respectively. This approach will require the City to restrict access to (e.g., by fencing the impacted area) or limit direct human contact (e.g., by paving the area) with contaminated soil. RSR provisions will require the City

to institute an Environmental Land Use Restriction (ELUR) on the ROW area, representing an encumbrance on the Site.

---

### **UST 2 Area**

Historic gasoline release(s) from the UST 2 area will require soil remediation in accordance with the RSRs. Phase II investigation activities identified residual TPH soil concentrations above applicable RSR standards from six to ten feet below grade at Test Pit UST 2/TP-1 and Soil Boring B-5; however, no corresponding groundwater impacts above applicable RSR groundwater standards were reported at Monitoring Well MW-2. Note that investigation activities in this area were hampered by unexpected subsurface obstructions associated with buried concrete and undocumented piping; therefore, the presence of a UST(s) could not be confirmed.

Based upon currently available information, excavation and recycling of contaminated soil as well as removal and disposal of UST 2 (if encountered) to meet applicable RSR Residential Direct Exposure Criteria would avoid the need to institute an ELUR in the UST 2 Area. Alternatively, soil remediation activities may be restricted to excavation of contaminated soil to levels below applicable RSR standards, with application of ELURs, to help reduce Site redevelopment costs.

---

### **UST 4 Area**

Phase II investigation activities identified a limited area where residual TPH soil concentrations exceed applicable RSR Residential and Industrial/Commercial Direct Exposure Criteria (six to ten feet below grade at Test Pit UST 4/TP-1). Visual and olfactory observations of subsurface soil at Soil Borings B-1 through B-3 also indicate the presence of solvent constituents. These observations were confirmed by soil analytical data reporting low-level trichloroethylene concentrations. A discussion of environmental compliance pathways to address groundwater impacts follows in Chapter 8.

Based upon currently available information, excavation and recycling of contaminated soil, as well as removal and disposal of UST 4, to meet applicable RSR Residential Direct Exposure Criteria would avoid the need to institute an ELUR in the UST 4 Area. Alternatively, soil remediation activities may be restricted to excavation of contaminated soil to levels below applicable RSR standards, with application of ELURs, to help reduce costs.

---

### **Suspect UST 5 Area**

Previously undocumented gasoline/diesel fuel release condition(s) were identified during the advancement of soil borings in the northern section of the Site. Analytical results for Soil Boring B-18 reported residual TPH concentrations in soil above applicable RSR standards. The laboratory analytical data were corroborated by field

headspace screening results which indicated elevated total volatile organic compound (TVOC) concentrations from four to eleven feet below grade in Soil Borings B-21, B-22, and B-24 advanced to help identify the extent of contamination. Further delineation of the limits of release will be required to estimate the actual volume of contaminated soil.

---

## AST 2 Area

VHB identified contaminated fill from zero to eight feet below grade overlying a No. 4/No. 6 fuel oil release observed from approximately eight to eleven feet below grade at Soil Boring B-9. The highest TPH concentration in soil encountered during the Phase II investigation was also reported at B-9, exceeding all applicable RSR standards. Laboratory test results for fill material reported arsenic concentrations in soil above applicable RSR Residential and Industrial/ Commercial Direct Exposure Criteria.

Extensive excavation and off-site and disposal of contaminated soil to meet applicable RSR standards would prevent further migration of the No. 4/No. 6 fuel oil release and avoid the need to institute an ELUR in the UST 2 Area. Heavily vegetated ground cover and sloping topography prevented further contaminant delineation in the AST 2 area.

---

## Railroad Spur Waste Disposal Area

Historic waste disposal practices near a railroad spur line in the southern sector of the Site will require soil remediation in accordance with the RSR. Phase II investigation activities identified residual soil concentrations of TPH, various semi-volatile organic compounds (SVOCs), arsenic, copper, lead, nickel, and thallium above applicable RSR Residential and/or Industrial/Commercial Direct Exposure Criteria from zero to approximately eight feet below grade at Test Pit UST 3/TP-1 and Soil Boring B-10.

SPLP analytical results for the Test Pit UST 3/TP-1 and Soil Boring B-10 soil samples reported nickel and lead concentrations, respectively, above applicable Pollutant Mobility Criteria for GB Areas (PMC). No other 13 priority pollutant metals measured by SPLP exceeded applicable PMCs. Groundwater quality data for this area is discussed in Chapter 8.

Based upon the limited environmental data currently available, extensive excavation and disposal of contaminated soil to meet applicable RSR Residential Direct Exposure Criteria would avoid the need to institute an ELUR in this area. Alternatively, soil remediation activities may be restricted to excavation of contaminated soil to levels below applicable RSR Industrial/Commercial Exposure Criteria, with application of ELURs, to help reduce Site redevelopment costs. Based upon current information, the estimate of probable remediation costs associated with the railroad spur waste disposal area may increase as additional environmental data is obtained. Additional contaminant delineation is recommended prior to implementing Site cleanup activities to more accurately estimate actual soil remediation costs.

---

## Surficial Stained Soil Areas

Laboratory analytical results reported TPH, SVOC, and/or arsenic concentrations in two stained soil areas, located southeast of the former Remington Rand manufacturing building, that exceed applicable RSR Residential and/or Industrial/Commercial Direct Exposure Criteria. Limited excavation and recycling or disposal of surficial contaminated soil to a depth of approximately two feet below grade conducted to meet applicable RSR Residential Direct Exposure Criteria would avoid the need to institute an ELUR in these areas. Alternatively, soil remediation activities may be restricted to excavation of contaminated soil to levels below applicable RSR Industrial/Commercial Exposure Criteria.

---

## Electrical Transformer Installations

Polychlorinated biphenyl (PCB) concentrations in soil were reported above the applicable RSR Residential Direct Exposure Criterion at two of the existing/former electrical transformer installations at the Site. Soil remediation activities associated with these electrical transformer locations are the responsibility of Northeast Utilities who owns and maintains all electrical transformer installations at the Site. The City should provide Northeast Utilities with the results of the surficial soil samples and request that Northeast Utilities conduct supplemental assessment activities to determine PMC compliance and appropriate soil remediation activities to reduce PCB-contaminated soil concentrations at the Site below the applicable RSR Residential Direct Exposure Criterion.

---

## Groundwater Contaminant Releases

Based upon comparisons to applicable Surface Water Protection Criteria, Residential Volatilization Criteria, and Industrial/Commercial Volatilization Criteria (RSR standards), VHB identified two groundwater contaminant release areas during the Phase II Environmental Site Assessment activities requiring further action pursuant to the RSR.

---

## UST 4 Area

Groundwater impacts from dissolved solvent constituent (i.e., trichloroethylene, 1,1-dichloroethylene, and vinyl chloride) concentrations above applicable RSR Volatilization Criteria were identified at Monitoring Well MW-1. Laboratory analytical results for Monitoring Wells MW-4 and MW-5 also reported trichloroethylene, chlorobenzene, and/or chloroethane concentration in groundwater below applicable RSR standards. Phase II investigation activities did not identify an on-Site source of solvent contamination. Determination of an appropriate DEP environmental compliance pathway to address groundwater impacts identified at



Monitoring Well MW-1 will require additional investigation. Based on the Site's easterly to northeasterly groundwater flow, existing contaminant distribution data suggest the following possible explanations for groundwater impacts identified near UST 4:

- Site impacts associated with a potential off-Site solvent release(s): VHB understands that solvent release(s) have occurred at property(ies) located hydrologically upgradient from the Site and migrated along preferential pathways (i.e., subsurface utility corridors, etc.) to the Site. Installation and sampling of additional groundwater monitoring wells along the Site's western and southwestern property lines will help determine if off-Site solvent release(s) have impacted the Site.

Should such off-Site release condition(s) exist, the responsible party(ies) would be obligated to conduct environmental site assessment activities and comply with applicable DEP regulations. Under this scenario, the Site owner would be afforded limited protection as an innocent landowner under the Connecticut General Statutes (ref. Section 22a-452d as amended by Public Act 95-190 Section 7). Remediation costs would be incurred by the property owner(s) responsible for such release condition(s).

- Potential past on-site solvent storage in UST 4: Further investigation may confirm past solvent storage in UST 4. Periodic collection and analysis of groundwater samples at the Site will document natural attenuation of solvent concentrations in groundwater over time.

If further investigation does not confirm the existence of an on-Site solvent source, additional groundwater sampling results may establish that dissolved solvent constituents are decreasing over time. Given plans to demolish the Quonset Building located near Monitoring Well MW-1, the City may choose to pursue an exemption from meeting the volatilization criteria under RSR Section 3(c)(5)(A)(ii) since natural attenuation, absent continuing release condition(s), will likely reduce solvent constituent concentrations within five years.

---

## Railroad Spur Waste Disposal Area

Laboratory analytical results for the Monitoring Well MW-4 groundwater sample reported dissolved copper and zinc concentrations above applicable Surface Water Protection (SWP) Criteria. Based upon current information, copper and zinc concentrations in groundwater appear to be leaching from overlying contaminated fill material (cf. Table 1, Test Pit UST 3/TP-1 soil results). Removal of contaminated fill material from the railroad spur waste disposal area are expected to result in a corresponding reduction in dissolved contaminant concentrations over time.

## 8

## Preliminary Estimates of Probable Remediation Costs

Based on a limited number of test pits, soil borings, groundwater monitoring wells and laboratory analytical data, VHB presents the following preliminary estimates of probable remediation costs for the identified contaminant release areas. The estimates are based upon the performance of contaminated soil remediation activities to achieve applicable RSR Remediation Direct Exposure Criteria. This approach has generated conservative estimates of probable remediation costs which would be reduced if the City chose to institute Environmental Land Use Restrictions (ELURs) at one or more identified contaminant release area(s).

Estimated remediation costs outlined in this chapter include the excavation, loading, transport, and backfill of all excavations, plus other incidental costs for laboratory analyses, environmental engineering support, documentation, and contingency funding. The estimate does not include labor and expenses associated with public involvement activities, project status presentations, site surveying, geotechnical design, and responses to DEP audits. Table 5 summarizes the preliminary estimates of probable remediation costs discussed in this section.

### Underground Storage Tank Removals

One 500 ± gallon UST has been confirmed at UST 4. USTs were not identified in suspect UST areas 1, 2, and 3. For budgetary purposes, it is assumed that two 5,000-gallon fuel oil USTs exist that have not been documented. The following cost breakdown has estimated to remove up to three USTs:

|                                       |          |
|---------------------------------------|----------|
| UST 2 Area, 1000-gallon UST.....      | \$2,500  |
| UST 4 Area, 500-gallon UST.....       | \$1,500  |
| UST 5 Area, 2- 5,000-gallon UST ..... | \$9,000  |
| Subtotal .....                        | \$13,000 |

The above costs include the management and disposal of tank contents, and the excavation, cleaning, removal, and recycling of the tank.

Contaminated soil has been identified within three existing/former UST areas, as shown on Figure 2. Based on field observations and reported laboratory analytical results, the following cost breakdown alternatives have been estimated to excavate, load, transport and on-site asphalt batch or off-site recycle the contaminated soil:

|                                                    |           |
|----------------------------------------------------|-----------|
| UST 2 Area - 200 c.y. of contaminated soil.....    | \$12,000  |
| UST 4 Area - 60 c.y. of contaminated soil.....     | \$3,600   |
| UST 5 Area - 3,000 c.y. of contaminated soil ..... | \$180,000 |
| Subtotal .....                                     | \$195,600 |

Cost savings may be realized under this item if on-site asphalt batching can be utilized.

## Aboveground Storage Tank Removals

One 1,000-gallon aboveground storage tank (AST) with 50 gallon of fuel oil and one 20,000-gallon AST with 6,500 gallons of fuel oil have been identified. The following cost breakdown has been estimated to remove and dispose of the ASTs and tank contents:

|                        |          |
|------------------------|----------|
| 1,000-gallon AST.....  | \$1,000  |
| 20,000-gallon AST..... | \$13,000 |
| Subtotal .....         | \$14,000 |

Estimated costs include the management and disposal of any tank contents, as well as the cleaning, removal, and recycling of the tanks.

## Right-Of-Way Waste Disposal Area

Based on the test pits TP-6 to TP-9 excavated and the reported soil analytical results, approximately 1,500 cubic yards of contaminated fill materials exist within the ROW. Due to the nature of the fill material encountered, the remediation alternative includes excavation, loading, and off-site disposal at a Subtitle C RCRA lined hazardous waste landfill.

Excavation and off-site disposal of 1,500 c.y. of RCRA soil ..... \$450,000

Test pit ROW/TP-10 and soil boring B-4 identified a TPH within the right-of way. Due to the nature of the contaminated soil encountered, the remediation alternative includes excavation, loading, and off-site asphalt batch recycling.

Excavation and off-site recycling of 600 c.y. of soil ..... \$36,000

---

## AST 2 Release Area

Soil boring B-9 identified separate phase No. 4/No. 6 oil at a depth of nine to 11 feet and arsenic concentrations from zero to eleven feet below grade. Based on the soil boring advanced and the reported soil analytical results, approximately 500 cubic yards of contaminated fill and soil materials. It is important to note that the separate phase oil was observed in this area and contaminant mobility over time will impact an increasing volume of soil. Due to the nature of the soil and fill material encountered, the remediation alternative includes excavation, loading, and off-site asphalt batch recycling.

AST 2 - 500 c.y. of contaminated soil ..... \$30,000

---

## Railroad Spur Waste Disposal Area

Approximately 450 cubic yards of contaminated soil are anticipated within the waste disposal area identified adjacent to soil boring B-10. Due to the nature of the fill material encountered, the preferred and cost effective remediation alternative is excavation, loading, and off-site disposal at a Subtitle C RCRA lined hazardous waste landfill.

Railroad Waste Disposal Area - 450 c.y. of contaminated soil . \$135,000

---

## Surficial Stained Soil

Approximately 130 cubic yards of contaminated soil are anticipated within the two surficial stained soil areas. Due to the nature of the fill material encountered, the remediation alternative includes the excavation, loading, off-site recycling at an asphalt batch recycling plant.

Surficial Stained Soil - 130 c.y. of contaminated soil ..... \$7,800

---

## Electrical Transformers

Management of four existing PCB-containing transformers and of PCB-impacted soil at two electrical transformer installations (Transformers 2 and 4) is the responsibility of Northeast Utilities. No costs will be incurred by the City associated with any transformer removal, soil remediation activities, or with any DEP response actions.

---

## Asbestos-Containing Materials

ACM located within the two buildings scheduled for demolition (Quonset Building and Boiler Room) must be removed prior to the start of demolition activities. The estimated cost to remove ACM from these two buildings is \$6,000. In buildings where renovation activities are proposed, ACM must be removed from areas that may be disturbed during renovation. Based on initial observations, approximately \$8,000 of ACM abatement activities will be necessary to remove damaged ACM within buildings which are anticipated to be renovated.

If ACM is left in place outside of areas that may be disturbed during renovation, an In-Place Operations and Maintenance (O&M) Plan must be developed and implemented when the building is occupied pursuant to OSHA (ref. Title 29 CFR, Chapter 1910.1101). The plan must define which ACM should be repaired or removed and periodically inspected. This information is dependent on proposed renovation plans. The estimated cost to prepare an O&M Program for the facility is \$4,000.

The estimated cost to remove all identified ACM from each building at the Site, except the roof flashing cement, is \$42,000. If all ACM is removed, no O&M Program would be necessary.

*Alternative 1: Abatement from buildings to be demolished, partial abatement from buildings to remain, and preparation of O&M Program*

|                                                  |          |
|--------------------------------------------------|----------|
| Abatement from buildings to be demolished .....  | \$6,000  |
| Partial abatement from buildings to remain ..... | \$8,000  |
| Preparation of O&M plan .....                    | \$4,000  |
| Subtotal .....                                   | \$18,000 |

*Alternative 2: Full abatement of all ACM*

|                     |          |
|---------------------|----------|
| ACM Abatement ..... | \$42,000 |
|---------------------|----------|

---

## Lead-Based Paint

Lead-based paint (LBP) building components should be removed and segregated prior to the start of demolition activities. In those buildings where renovation activities will disturb LBP, LBP must be removed prior to renovation activities. An O&M Plan must be produced and implemented when the building is occupied pursuant to OSHA located at Title 29 CFR, Chapter 1910.1025. This includes assessing what LBP should be repaired in-place and periodically inspected or

removed and will be dependent on the renovation plans. The estimated cost to prepare an O&M program for the facility is \$2,500.

The estimated cost to segregate and recycle or dispose all LBP-coated building components as RCRA-hazardous waste is \$20,000. In addition, approximately \$8,000 will be necessary to repair (prepare and repaint) damaged LBP-coated building components. Therefore, the estimated cost to remove all LBP located in the Quonset Building and the Boiler Room, and repair damaged LBP-coated building components in the structures to remain, and prepare the O&M Plan is \$30,500.

Note that metal building components coated with LBP may be recycled at a metal recycling dealer who accepts LBP-coated metal building components.

|                                     |          |
|-------------------------------------|----------|
| RCRA-hazardous waste disposal ..... | \$20,000 |
| Prepare and paint damaged LBP ..... | \$8,000  |
| Preparation of O&M plan .....       | \$4,000  |
| Subtotal .....                      | \$18,000 |

## Containers of Oil and Hazardous Materials

Based on the quantities of OHM containers included in Appendix G, the estimated cost to remove and recycle/dispose of current inventoried materials is \$20,000. This estimate also includes the removal of all mercury-containing bulbs and PCB-containing light ballasts. Once the existing tenants vacate and an additional inventory is compiled, the cost estimate to remove OHM containers may change.

|                                    |          |
|------------------------------------|----------|
| Management of OHM Containers ..... | \$20,000 |
|------------------------------------|----------|

## Engineering and Laboratory Analytical Allowance

Environmental engineering fees will include the preparation of contract documents for remediation activities, on-site representation and documentation during cleanup, and report preparation for submittal to DEP.

|                                 |          |
|---------------------------------|----------|
| Environmental Engineering ..... | \$75,000 |
|---------------------------------|----------|

During remediation activities, specific soil samples will be collected and submitted for laboratory analyses in accordance with applicable RSR provisions. Additional soil sampling will be required to further delineate contaminant release areas, close contaminated soil excavation areas, and characterize contaminated soil stockpiles before shipment to appropriate permitted recycling/disposal facilities. Additional

groundwater sampling is also anticipated to determine whether the Site has been impacted by on-site or off-site solvent releases.

Laboratory Analytical Allowance ..... \$50,000

## Summary of Probable Remediation Cost Estimate

Based upon site investigation limitations and previously stated assumptions, the following estimate of probable remediation costs to address identified release conditions under the current RSRs has been developed for the Site. Please note that this summary represents a conservative estimate of probable remediation costs. Soil remediation to meet applicable Industrial/Commercial Direct Exposure Criteria and associated institution of ELURs will significantly reduce Site redevelopment costs incurred during RSR compliance activities. Table 5 summarizes the preliminary estimates of probable remediation costs discussed in this section.

|                                                             |           |
|-------------------------------------------------------------|-----------|
| Underground Storage Tank Removals/Soil Management .....     | \$208,600 |
| Aboveground Storage Tank Removals.....                      | \$14,000  |
| Right-Of-Way Waste Disposal Area .....                      | \$486,000 |
| AST 2 Release Area .....                                    | \$30,000  |
| Railroad Spur Waste Disposal Area.....                      | \$135,000 |
| Surficial Stained Soil .....                                | \$7,800   |
| Asbestos-Containing Materials, <i>Alternative 2</i> : ..... | \$42,000  |
| Lead-Based Paint .....                                      | \$18,000  |
| Containers of Oil and Hazardous Materials .....             | \$20,000  |
| Environmental Engineering Support .....                     | \$75,000  |
| Laboratory Analytical Allowance .....                       | \$50,000  |

Subtotal..... \$1,086,400

30% Contingency..... \$325,900

**TOTAL .....** \$1,412,300

## 9

## Summary of Findings

The Phase II Environmental Site Assessment activities were conducted to help identify the nature and extent of residual contamination, associated with the generation, storage, and use of oil and hazardous materials at the Site. Based upon available environmental data, this report also identifies potential environmental liabilities that may be incurred upon Site acquisition. The subsurface investigation was performed to help evaluate subsurface conditions in the immediate vicinity of previously identified areas of environmental concern, including former and existing UST locations, existing AST locations and fill areas.

Based on the results of the subsurface investigation, localized areas of residual soil and groundwater contamination exist at the Site in association with previously and newly identified contaminant sources. Laboratory analytical testing confirmed contaminant concentrations that exceed applicable RSR soil and groundwater standards in the following areas associated with underground storage tanks (USTs), aboveground storage tanks (ASTs), and waste disposal sites:

- *Right-Of-Way Waste Disposal Area* - Residual TPH, arsenic, copper, and lead contamination in soil/fill.
- *UST 2 Area* - Residual total petroleum hydrocarbons (TPH) contamination in soil. A UST was reported in this area; however, a concrete pad and subsurface piping prevented access to further investigate the UST under the current scope of services.
- *UST 4 Area* - Residual TPH contamination in soil and VOC and zinc contamination in groundwater. The existence of a 500-gallon single-wall steel UST has been confirmed.
- *Suspect UST 5 Area* - Residual TPH contamination in soil at a depth of four to 12 feet indicates that UST(s) may be present within this area.
- *AST 2 Area* - Residual TPH and arsenic contamination in soil.
- *Railroad Spur Waste Disposal Area* - Residual TPH, SVOC, and arsenic contamination in waste disposal area and copper and zinc contamination in groundwater.
- *Electrical Transformers* - Residual PCB contamination in soil beneath Transformer 2 and Transformer 4.
- *Surficial Stained Soil Areas 1 and 2* - Residual TPH and SVOC contamination.



Regulated building components and miscellaneous containers of hazardous and special waste were also identified at the Site. Regulated building components consist of the following:

- Asbestos containing materials associated with thermal pipe insulation, floor tile, and electrical equipment;
- Lead-based paint associated with fire doors, door jambs, window casings, brick and wood walls, and exterior siding;
- PCB-containing electrical equipment. Four electrical transformers identified at belong to Northeast Utilities who is responsible for their maintenance and disposal;
- Mercury-containing lights associated with fluorescent light fixtures located throughout the buildings; and
- Residual metal dust located on window sills, floors, and other horizontal surfaces within the interiors of Buildings 4, 5, and 10.

Phase II site assessment findings of particular importance to the City's North End redevelopment plans include:

- Adverse environmental impacts at the Site associated with landfill leachate migration from the Municipal Landfill were not identified in the overburden aquifer during this investigation. Water table elevations indicate that local groundwater flows northeasterly toward the Municipal Landfill and adjacent wetland area.
- Groundwater test results reported solvent constituent concentrations in monitoring wells MW-1, MW-4, and MW-5. Additional investigation activities will be required to assess whether groundwater impacts have resulted from potential on-site migration from hydrologically upgradient property(ies) or past on-site solvent storage. To resolve this issue, it is recommended that the City install additional groundwater monitoring wells along the Site's western and southwestern property lines to determine if off-site solvent release(s) have impacted the Site.
- Ten soil contaminant release areas and two groundwater impact areas have been identified at the Site which will require additional response actions pursuant to the DEP's Remediation Standard Regulations (RSRs). The RSRs provide the City flexibility in addressing existing environmental conditions through contaminated soil excavation, on-site contaminated soil treatment and reuse, and/or institution of Environmental Land Use Restrictions (ELURs) where soil cleanup activities would be prohibitively expensive or technically unfeasible.
- A preliminary estimate of probable remediation costs has been developed which projects soil cleanup expenditures at approximately \$1.4 million, including engineering fees, anticipated laboratory analytical costs, and a 30% contingency. Soil remediation cost estimates are based upon achieving

applicable RSR Residential Direct Exposure Criteria and Pollutant Mobility Criteria; however, the application of RSR Industrial/Commercial Direct Exposure Criteria and institution of ELURs will reduce actual soil remediation costs incurred during Site redevelopment activities.

# References

Phase I Environmental Site Assessment, former Remington Rand Facility, Soil Science and Environmental Services, Inc., April 6, 1993.

City of Middletown, Request for Proposal #9697-049.


City of Middletown, Topographic Map with drainage Systems and Inland Wetlands Superimposed, Scale 1"=100', April 17, 1980.

Sanborn Fire Insurance Map, Middletown, Connecticut, 1924.

State of Connecticut Regulation of Department of Environmental Protection concerning Remediation Standard.

United States Department of the Interior Geological Survey Quadrangle, Middletown, Connecticut, 1965, Revised 1992.

# Figures



Source: USGS Quadrangle Middletown, CT

Vanasse Hangen Brustlin, Inc.

Site Location Map

Figure 1









Figure 2  
Site Plan  
Former Remington Rand Facility  
Middletown, Connecticut



Vanasse Hangen Brustlin, Inc.



Figure 3a  
Suspect ACM Sampling Locations  
First Floor  
Former Remington Rand Facility  
Middletown, Connecticut





Vanasse Hangen Brustlin, Inc.

Figure 3b  
Suspect ACM Sampling Locations  
Second Floor  
Former Remington Rand Facility  
Middletown, Connecticut



**Vanasse Hangen Brustlin, Inc.**  
 Figure 3c  
 Suspect ACM Sampling Locations  
 Third Floor  
 Former Remington Rand Facility  
 Middletown, Connecticut

**Table 1    Test Pit Soil Sampling Results**  
**Former Remington Rand Facility, 180 Johnson Street, Middletown, CT**

| Parameter    | Source Area                | ROW TP-1 | ROW TP-3 | ROW TP-6 | ROW TP-7 | ROW TP-9 | ROW TP-10 | ROW TP-11 | UST 2 TP-1 | UST 3 TP-1 | UST 3 TP-1 | UST 4 TP-1 | Residential Direct Exposure Criteria | Industrial/Commercial Direct Exposure Criteria | GB Pollutant Mobility Criteria |
|--------------|----------------------------|----------|----------|----------|----------|----------|-----------|-----------|------------|------------|------------|------------|--------------------------------------|------------------------------------------------|--------------------------------|
| EPA Test     | Sample Depth Interval      | 0'-2'    | 0'-2'    | 3'-4'    | 2'-3'    | 6'-8'    | 4'-6'     | 3'-4'     | 6'         | 0'-2'      | 3'-4'      | 8'         |                                      |                                                |                                |
| VOC 8020     | 1,2-Dichlorobenzene        | ns       | ns       | ns       | ns       | ns       | ns        | ns        | ~          | ns         | ns         | 0.159      | 500                                  |                                                |                                |
|              | Benzene                    | ns       | ns       | ns       | ns       | ns       | ns        | ns        | ~          | ns         | ns         | 0.089      | 21                                   |                                                |                                |
|              | Ethylbenzene               | ns       | ns       | ns       | ns       | ns       | ns        | ns        | 0.41       | ns         | ns         | 3.59       | 500                                  |                                                |                                |
|              | Toluene                    | ns       | ns       | ns       | ns       | ns       | ns        | ns        | ~          | ns         | ns         | 0.349      | 500                                  |                                                |                                |
|              | Xylene                     | ns       | ns       | ns       | ns       | ns       | ns        | ns        | 0.574      | ns         | ns         | 3.53       | 500                                  |                                                |                                |
| VOC 8240     | 2-Hexanone                 | ns       | ns       | ns       | ns       | ~        | 20.1      | ns        | ns         | ns         | ns         | ns         | nl                                   |                                                |                                |
|              | Ethylbenzene               | ns       | ns       | ns       | ns       | ~        | 0.55      | ns        | ns         | ns         | ns         | ns         | 500                                  |                                                |                                |
|              | Xylene                     | ns       | ns       | ns       | ns       | ~        | 3.5       | ns        | ns         | ns         | ns         | ns         | 500                                  |                                                |                                |
| TPH 418.1    | Various Hydrocarbons       | ns       | ns       | ns       | 38,200   | 3,000    | 7,450     | 35.2      | 9,380      | ns         | 830        | 37,700     | 500                                  | 2,500                                          | 2,500                          |
| SVOC 8270    | 2-Methylnaphthalene        | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 129        | ns         | nl                                   |                                                |                                |
|              | Acenaphthene               | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 146        | ns         | nl                                   |                                                |                                |
|              | Anthracene                 | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 316        | ns         | 1,000                                |                                                |                                |
|              | Benzo(a)pyrene             | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 400        | ns         | 1                                    | 1                                              | 1                              |
|              | Bis(2-ethylhexyl)phthalate | ~        | ns       | ~        | ~        | ~        | 3.6       | ~         | ns         | ns         | ~          | ns         | 44                                   |                                                |                                |
|              | Chrysene                   | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 548        | ns         | nl                                   |                                                |                                |
|              | Dibenzofuran               | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 73.3       | ns         | nl                                   |                                                |                                |
|              | Fluoranthene               | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 1,270      | ns         | 1,000                                | 2,500                                          |                                |
|              | Fluorene                   | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 85.3       | ns         | 1,000                                |                                                | 56                             |
|              | Indeno(1,2,3-cd)pyrene     | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 163        | ns         | nl                                   |                                                |                                |
|              | Naphthalene                | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 76.7       | ns         | 1,000                                |                                                |                                |
|              | Phenanthrene               | ~        | ns       | ~        | ~        | ~        | ~         | ~         | ns         | ns         | 1,270      | ns         | 1,000                                | 2,500                                          | 40                             |
| Pyrene       | ~                          | ns       | ~        | ~        | ~        | ~        | ~         | ns        | ns         | 1,130      | ns         | 1,000      | 2,500                                | 40                                             |                                |
| 13 PP Metals | Antimony                   | ~        | ns       | 6.23     | ~        | ns       | ~         | ns        | ~          | ns         | ~          | ns         | 27                                   |                                                |                                |
|              | Arsenic                    | ~        | ns       | 36.1     | 28.9     | ns       | ~         | ns        | ns         | 87.3       | ns         | ns         | 10                                   | 10                                             |                                |
|              | Beryllium                  | 0.33     | ns       | 0.25     | 0.25     | ns       | 0.44      | ns        | ns         | 0.18       | ns         | ns         | 2                                    |                                                |                                |
|              | Cadmium                    | 2.54     | ns       | 17.1     | 7.9      | ns       | 0.14      | ns        | ns         | 3.1        | ns         | ns         | 34                                   |                                                |                                |
|              | Chromium*                  | 36.6     | ns       | 272      | 188      | ns       | 14.1      | ns        | ns         | 99.8       | ns         | ns         | 3,900                                |                                                |                                |
|              | Copper                     | 180      | ns       | 1,420    | 29,500   | ns       | 24.4      | ns        | ns         | 16,300     | ns         | ns         | 2,500                                | 76,000                                         |                                |
|              | Lead                       | 163      | ns       | 9,130    | 1,240    | ns       | 7.44      | ns        | ns         | 518        | ns         | ns         | 500                                  | 1,000                                          |                                |
|              | Mercury                    | 0.082    | ns       | ~        | 0.059    | ns       | ~         | ns        | ns         | 0.31       | ns         | ns         | 20                                   |                                                |                                |
|              | Nickel                     | 14.4     | ns       | 434      | 179      | ns       | 38.3      | ns        | ns         | 5,160      | ns         | ns         | 1,400                                | 7,500                                          |                                |
|              | Selenium                   | ~        | ns       | 5.77     | 15.2     | ns       | ~         | ns        | ns         | 85.1       | ns         | ns         | 340                                  |                                                |                                |
|              | Silver                     | 34.3     | ns       | 1.93     | ~        | ns       | ~         | ns        | ns         | ~          | ns         | ns         | 340                                  |                                                |                                |
|              | Thallium                   | ~        | ns       | ~        | ~        | ns       | ~         | ns        | ns         | 56.2       | ns         | ns         | 5.4                                  | 160                                            |                                |
|              | Zinc                       | 905      | ns       | 1,400    | 17,800   | ns       | 237       | ns        | ns         | 2,950      | ns         | ns         | 20,000                               |                                                |                                |
| Cyanide      |                            | ns       | 1.2      | ns       | ns       | ns       | ns        | ns        | ns         | ns         | ns         | ns         | 1,400                                |                                                |                                |
| SPLP Metals  | Chromium                   | ~        | ns       | 0.09     | ~        | ns       | ~         | ns        | ns         | ~          | ns         | ns         |                                      |                                                | 0.5                            |
|              | Copper                     | ~        | ns       | ~        | 0.09     | ns       | ~         | ns        | ns         | 0.16       | ns         | ns         |                                      |                                                | 13                             |
|              | Lead                       | ~        | ns       | 0.31     | ~        | ns       | ~         | ns        | ns         | ~          | ns         | ns         |                                      |                                                | 0.15                           |
|              | Nickel                     | ~        | ns       | ~        | 0.28     | ns       | 0.08      | ns        | ns         | 1.87       | ns         | ns         |                                      |                                                | 1                              |
|              | Zinc                       | 0.19     | ns       | 0.3      | 5.45     | ns       | 0.3       | ns        | ns         | 1.47       | ns         | ns         |                                      |                                                | 50                             |
| Lead 6010    |                            | ns       | ns       | ns       | ns       | ns       | ns        | ns        | 3.5        | ns         | ns         | 5.48       | 500                                  |                                                |                                |
| PCBs 8080    | Various Aroclors           | ns       | ns       | ns       | ns       | ns       | ns        | ns        | ns         | ns         | ~          | ns         |                                      |                                                |                                |

Notes: All analytical results are listed in milligrams per kilogram (mg/kg), roughly equivalent to parts per million (ppm), unless otherwise noted. SPLP analytical results are listed in milligrams per liter (mg/L), roughly equivalent to parts per million (ppm). ns, where present, indicates that no sample was collected for the corresponding laboratory analysis. Results appearing **bold typeface** were reported at concentrations that exceed the applicable CTDEP soil cleanup standard. nl, where present, indicates that a corresponding CTDEP standard is not listed. -, where present, indicates the result is less than the laboratory method detection limit. \* Based upon historic waste disposal activities, unstable hexavalent chromium is not likely to be present.

Table 2 Soil Boring and Surface Soil Sampling Results  
Former Remington Rand Facility, 180 Johnson Street, Middletown, CT

| Parameter       | Sample Identification            | B-1     | B-2     | B-3     | B-4    | B-4    | B-5   | B-7     | B-8    | B-9    | B-10   | B-11  | B-12  | B-13  | B-15  | B-16  | B-18  | Quon-1 | Tran-1 | Tran-2 | Tran-3 | Tran-4 | Tran-5 | Sur-1 | Sur-2 | Residential Direct Exposure Criteria | Industrial/Commercial Direct Exposure Criteria | GB Pollutant Mobility Criteria |
|-----------------|----------------------------------|---------|---------|---------|--------|--------|-------|---------|--------|--------|--------|-------|-------|-------|-------|-------|-------|--------|--------|--------|--------|--------|--------|-------|-------|--------------------------------------|------------------------------------------------|--------------------------------|
| EPA Test        | Sample Depth Interval            | 10'-12' | 10'-12' | 10'-12' | 0-2'   | 8'-10' | 6'-8' | 10'-11' | 8'-10' | 9'-11' | 6'-7'  | 4'-6' | 4'-6' | 6'-8' | 7'-8' | 5'-6' | 5'-7' | 0-1'   | 0-1'   | 0-1'   | 0-1'   | 0-1'   | 0-1'   | 0-1'  | 0-1'  |                                      |                                                |                                |
| VOC 8240        | Trichloroethylene                | 0.058   | -       | 0.029   | -      | -      | -     | -       | -      | ns     | ns     | ns    | ns    | ns    | -     | ns    | -     | ns     | ns     | ns     | ns     | ns     | ns     | ns    | ns    | 56                                   |                                                |                                |
|                 | Xylene                           | -       | -       | -       | 0.84   | -      | -     | -       | -      | ns     | ns     | ns    | ns    | ns    | -     | ns    | -     | ns     | ns     | ns     | ns     | ns     | ns     | ns    | ns    | 500                                  |                                                |                                |
| TPH 418.1       | Various Hydrocarbons             | 37.7    | -       | 47.6    | 12,300 | 4,870  | 4,490 | 46.2    | 4,920  | 62,500 | 10,400 | 34.2  | 25.8  | 33.5  | -     | 29    | 5,200 | 148    | ns     | ns     | ns     | ns     | ns     | 1,330 | 147   | 500                                  | 2,500                                          | 2,500                          |
| SVOC 8270       | 2,4-Dimethylphenol               | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 210    | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | nl                                   |                                                |                                |
|                 | 2-Methylnaphthalene              | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | 10.7   | 1,000  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | nl                                   |                                                |                                |
|                 | 2-Methylphenol (o-cresol)        | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 122    | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | nl                                   |                                                |                                |
|                 | 3- & 4-Methylphenol (m&p-cresol) | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 92     | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | nl                                   |                                                |                                |
|                 | Acenaphthene                     | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 528    | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | nl                                   |                                                |                                |
|                 | Acenaphthylene                   | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 656    | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 1.36  | 1,000                                |                                                | 84                             |
|                 | Anthracene                       | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 1,500  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 2.18  | 1,000                                | 2,500                                          |                                |
|                 | Benzo(a)anthracene               | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 1,560  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 11.7  | 1                                    | 7.8                                            |                                |
|                 | Benzo(a)pyrene                   | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 1,380  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 14.3  | 1                                    | 1                                              | 1                              |
|                 | Benzo(b)fluoranthene             | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 1,200  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | 10.4  | 15    | 1                                    | 7.8                                            |                                |
|                 | Benzo(g,h,i)perylene             | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | -      | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 13.1  | 8.4                                  | 78                                             | 56                             |
|                 | Benzo(k)fluoranthene             | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | -      | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 14.7  | nl                                   |                                                |                                |
|                 | Chrysene                         | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 1,590  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | 1,000                                |                                                |                                |
|                 | Di-n-butylphthalate              | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 11.2   | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | nl                                   |                                                |                                |
|                 | Dibenzo(a,h)anthracene           | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 184    | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 0.37  | nl                                   |                                                |                                |
|                 | Dibenzofuran                     | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 1,000  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | nl                                   |                                                |                                |
|                 | Fluoranthene                     | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 4,680  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | 13.5  | 21.3  | 1,000                                |                                                |                                |
|                 | Fluorene                         | ns      | ns      | ns      | ns     | 0.43   | ns    | ns      | -      | -      | 1,640  | ns    | ns    | ns    | ns    | -     | 2.11  | ns     | ns     | ns     | ns     | ns     | ns     | -     | 0.56  | 1,000                                | 2,500                                          | 56                             |
|                 | Indeno(1,2,3-cd)pyrene)          | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 684    | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 10    | nl                                   |                                                |                                |
|                 | Naphthalene                      | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 3,700  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | 1,000                                | 2,500                                          |                                |
|                 | Phenanthrene                     | ns      | ns      | ns      | ns     | 1.69   | ns    | ns      | 1.27   | -      | 6,540  | ns    | ns    | ns    | ns    | -     | 2.17  | ns     | ns     | ns     | ns     | ns     | ns     | -     | 9.57  | 1,000                                | 2,500                                          | 40                             |
|                 | Phenol                           | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 68.7   | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | 1,000                                |                                                |                                |
|                 | Pyrene                           | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 3,440  | ns    | ns    | ns    | ns    | -     | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 25.1  | 1,000                                | 2,500                                          | 40                             |
| 13 PP Metals    | Arsenic                          | ns      | ns      | ns      | ns     | 5.07   | ns    | ns      | -      | 42.9   | 11.7   | ns    | ns    | ns    | ns    | ns    | -     | ns     | ns     | ns     | ns     | ns     | ns     | 10.4  | 18    | 10                                   | 10                                             |                                |
|                 | Beryllium                        | ns      | ns      | ns      | ns     | 0.53   | ns    | ns      | 0.55   | 0.15   | -      | ns    | ns    | ns    | ns    | ns    | 0.42  | ns     | ns     | ns     | ns     | ns     | ns     | 0.36  | 0.47  | 2                                    |                                                |                                |
|                 | Cadmium                          | ns      | ns      | ns      | ns     | 0.06   | ns    | ns      | 0.07   | 0.26   | 2.82   | ns    | ns    | ns    | ns    | ns    | 0.06  | ns     | ns     | ns     | ns     | ns     | ns     | 0.98  | 0.45  | 34                                   |                                                |                                |
|                 | Chromium*                        | ns      | ns      | ns      | ns     | 14.8   | ns    | ns      | 13.9   | 4.42   | 18.2   | ns    | ns    | ns    | ns    | ns    | 10.9  | ns     | ns     | ns     | ns     | ns     | ns     | 45.8  | 118   | 3,900                                |                                                |                                |
|                 | Copper                           | ns      | ns      | ns      | ns     | 14.8   | ns    | ns      | 13.4   | 75.8   | 69.4   | ns    | ns    | ns    | ns    | ns    | 13    | ns     | ns     | ns     | ns     | ns     | ns     | 2,400 | 506   | 2,500                                |                                                |                                |
|                 | Lead                             | ns      | ns      | ns      | ns     | 7.84   | ns    | ns      | 8.54   | 44.4   | 296    | ns    | ns    | ns    | ns    | ns    | 7.51  | ns     | ns     | ns     | ns     | ns     | ns     | ns    | ns    | 0.073                                | 0.27                                           | 20                             |
|                 | Mercury                          | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | 0.044  | -      | ns    | ns    | ns    | ns    | ns    | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     | nl                                   |                                                |                                |
|                 | Nickel                           | ns      | ns      | ns      | ns     | 12.4   | ns    | ns      | 10.9   | 11.6   | 39.8   | ns    | ns    | ns    | ns    | ns    | 12.5  | ns     | ns     | ns     | ns     | ns     | ns     | 37    | 84.2  | 1,400                                |                                                |                                |
|                 | Selenium                         | ns      | ns      | ns      | ns     | -      | ns    | ns      | 5.5    | 8.8    | -      | ns    | ns    | ns    | ns    | ns    | 6.07  | ns     | ns     | ns     | ns     | ns     | ns     | 9.34  | 15.3  | 340                                  |                                                |                                |
|                 | Zinc                             | ns      | ns      | ns      | ns     | 39.7   | ns    | ns      | 26.5   | 21.2   | 1,300  | ns    | ns    | ns    | ns    | ns    | 27.5  | ns     | ns     | ns     | ns     | ns     | ns     | 944   | 127   | 20,000                               |                                                |                                |
| SPLP Metals     | Copper                           | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | 0.26   | 0.3    | ns    | ns    | ns    | ns    | ns    | -     | ns     | ns     | ns     | ns     | ns     | ns     | 1.07  | 0.73  |                                      |                                                | 13                             |
|                 | Lead                             | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 1.37   | ns    | ns    | ns    | ns    | ns    | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | -     |                                      |                                                | 0.15                           |
|                 | Nickel                           | ns      | ns      | ns      | ns     | -      | ns    | ns      | -      | -      | 0.16   | ns    | ns    | ns    | ns    | ns    | -     | ns     | ns     | ns     | ns     | ns     | ns     | -     | 0.33  |                                      |                                                | 1                              |
|                 | Zinc                             | ns      | ns      | ns      | ns     | 0.35   | ns    | ns      | 0.76   | 0.26   | 8.55   | ns    | ns    | ns    | ns    | ns    | 0.15  | ns     | ns     | ns     | ns     | ns     | ns     | 3.12  | 1.1   |                                      |                                                | 50                             |
| PCBs 8080       | Various Aroclors                 | ns      | ns      | ns      | ns     | ns     | ns    | ns      | ns     | ns     | 0.746  | ns    | ns    | ns    | ns    | ns    | ns    | 0.383  | 0.154  | 1.02   | 0.762  | 1.68   | 0.609  | -     | -     | 1                                    | 10                                             |                                |
| Herbicides 8150 |                                  | ns      | ns      | ns      | ns     | ns     | ns    | ns      | ns     | ns     | ns     | ns    | ns    | ns    | ns    | ns    | ns    | -      | ns     | ns     | ns     | ns     | ns     | ns    | ns    |                                      |                                                |                                |

Notes: All analytical results are listed in milligrams per kilogram (mg/kg), roughly equivalent to parts per million (ppm), unless otherwise noted.  
SPLP analytical results are listed in milligrams per liter (mg/l), roughly equivalent to parts per million (ppm).  
ns, where present, indicates that no sample was collected for the corresponding laboratory analysis.  
Results appearing bold typeface were reported at concentrations that exceed the applicable CTDEP soil cleanup standard.  
nl, where present, indicates that a corresponding CTDEP standard is not listed.  
-, where present, indicates the result is less than the laboratory method detection limit.  
\* Based upon historic waste disposal activities, unstable hexavalent chromium is not likely to be present.

**Table 3** Groundwater Monitoring Well Results  
Former Remington Rand Facility, 180 Johnson Street, Middletown, CT

| Parameter<br>EPA Test   | Sample Identification      | Well<br>MW-1 | Well<br>MW-2 | Well<br>MW-3 | Well<br>MW-4 | Well<br>MW-5 | Well<br>MW-6 | Surface Water<br>Protection Criteria | Residential<br>Volatilization Criteria | Industrial/Commercial<br>Volatilization Criteria |
|-------------------------|----------------------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------------------------------|----------------------------------------|--------------------------------------------------|
| VOC 8240                | Trichloroethylene          | 0.275        | -            | -            | 0.037        | 0.0167       | -            | 2.34                                 | 0.219                                  | 0.54                                             |
|                         | 1,1-Dichloroethylene       | 0.0031       | -            | -            | -            | -            | -            | 0.096                                | 0.001                                  | 0.006                                            |
|                         | cis-1,2-Dichloroethylene   | 0.0716       | -            | -            | -            | -            | -            | nl                                   | nl                                     | -                                                |
|                         | trans-1,2-Dichloroethylene | 0.0012       | -            | -            | -            | -            | -            | nl                                   | nl                                     | -                                                |
|                         | Vinyl Chloride             | 0.0179       | -            | -            | -            | -            | -            | 157.5                                | 0.002                                  | 0.002                                            |
|                         | Methyl Ter-Butyl Ether     | -            | 2.11         | -            | -            | -            | -            | nl                                   | 50                                     | -                                                |
|                         | Methylene Chloride         | -            | 0.061        | -            | -            | -            | -            | 48                                   | 50                                     | -                                                |
|                         | Chlorobenzene              | -            | -            | -            | -            | 0.0037       | -            | 420                                  | 1.8                                    | -                                                |
|                         | Chloroethane               | -            | -            | -            | -            | 0.0145       | -            | nl                                   | nl                                     | -                                                |
| TPH 418.1               | Various Hydrocarbons       | -            | 0.65         | 8.93         | -            | -            | 16.1         | nl                                   | -                                      | -                                                |
| SVOC 8270               | Various Compounds          | -            | -            | -            | -            | -            | -            | -                                    | -                                      | -                                                |
| 13 PP Metals            | Cadmium                    | 0.003        | -            | -            | -            | -            | -            | -                                    | -                                      | -                                                |
|                         | Copper                     | -            | -            | 0.0015       | 0.0824       | 0.0028       | 0.0016       | 0.006                                | -                                      | -                                                |
|                         | Nickel                     | 0.014        | 0.059        | 0.009        | 0.284        | 0.012        | -            | 0.048                                | -                                      | -                                                |
|                         | Zinc                       | 0.213        | 0.02         | 0.118        | 0.288        | 0.022        | 0.014        | 0.88                                 | -                                      | -                                                |
| PCBs 8080               | Various Aroclors           | -            | -            | -            | -            | -            | -            | 0.123                                | -                                      | -                                                |
| Herbicides 8150         | -                          | -            | -            | -            | -            | -            | -            | -                                    | -                                      | -                                                |
| BOD 5-day               | -                          | ns           | ns           | -            | ns           | 2.8          | ns           | nl                                   | -                                      | -                                                |
| Chloride                | -                          | ns           | ns           | 5.4          | ns           | 6.6          | ns           | nl                                   | -                                      | -                                                |
| Nitrate                 | -                          | ns           | ns           | -            | ns           | -            | ns           | nl                                   | -                                      | -                                                |
| Ammonia                 | -                          | ns           | ns           | 1.96         | ns           | -            | ns           | nl                                   | -                                      | -                                                |
| Total Iron              | -                          | ns           | ns           | 15           | ns           | 138          | ns           | nl                                   | -                                      | -                                                |
| Total Manganese         | -                          | ns           | ns           | 18.9         | ns           | 49.8         | ns           | nl                                   | -                                      | -                                                |
| TDS                     | -                          | ns           | ns           | 468          | ns           | 280          | ns           | nl                                   | -                                      | -                                                |
| TSS                     | -                          | ns           | ns           | 76           | ns           | 520          | ns           | nl                                   | -                                      | -                                                |
| pH                      | -                          | ns           | ns           | 6.45         | ns           | 6.07         | ns           | nl                                   | -                                      | -                                                |
| Conductivity (uohms/cm) | -                          | ns           | ns           | 740          | ns           | 520          | ns           | nl                                   | -                                      | -                                                |
| Alkalinity              | -                          | ns           | ns           | 390          | ns           | 300          | ns           | nl                                   | -                                      | -                                                |

Notes: Unless otherwise indicated, all analytical results are listed in milligrams per liter (mg/L), roughly equivalent to parts per million (ppm).  
ns, where present, indicates that no sample was collected for the corresponding laboratory analysis.  
Results appearing **bold typeface** were reported at concentrations that exceed the applicable CTDEP groundwater cleanup standard.  
nl, where present, indicates that a corresponding CTDEP standard is not listed.  
-, where present, indicates the result is less than the laboratory method detection limit.

Table 4 Wipe Sampling Results

## Former Remington Rand Facility, 180 Johnson Street, Middletown, CT

| Parameter<br>EPA Test | Source Area<br>Sample Identification<br>Location in Room | Wipe<br>10-F<br>Floor | Wipe<br>10-NW<br>North Sill | Wipe<br>10-SW<br>South Sill | Wipe<br>4-EW<br>East Sill | Wipe<br>4-WW<br>West Sill | Wipe<br>5-ES<br>Electric Switch | Wipe<br>5-EW<br>East Sill | Wipe<br>5-FD<br>Fire Door | CT DPH<br>Standard |
|-----------------------|----------------------------------------------------------|-----------------------|-----------------------------|-----------------------------|---------------------------|---------------------------|---------------------------------|---------------------------|---------------------------|--------------------|
| 13 PP Metals          |                                                          |                       |                             |                             |                           |                           |                                 |                           |                           |                    |
|                       | Antimony                                                 | ~                     | ~                           | ~                           | 0.07                      | ~                         | 0.09                            | ~                         | 0.12                      |                    |
|                       | Arsenic                                                  | 0.42                  | 0.47                        | 0.33                        | 0.58                      | 0.83                      | 0.37                            | 0.36                      | 0.62                      |                    |
|                       | Beryllium                                                | 0.003                 | 0.004                       | 0.007                       | 0.03                      | 0.004                     | 0.002                           | 0.003                     | 0.005                     |                    |
|                       | Cadmium                                                  | 0.07                  | 0.079                       | 0.144                       | 0.102                     | 0.135                     | 8.44                            | 0.211                     | 0.203                     |                    |
|                       | Chromium                                                 | 0.651                 | 0.627                       | 1.94                        | 4.05                      | 2.15                      | 0.428                           | 0.301                     | 0.779                     |                    |
|                       | Copper                                                   | 1.02                  | 1.26                        | 2.86                        | 1.71                      | 3.6                       | 0.717                           | 1.01                      | 1.55                      |                    |
|                       | Lead                                                     | 2.57                  | 5.15                        | 7.25                        | 3.81                      | 26.1                      | 6.23                            | 6.66                      | 37.7                      | 500                |
|                       | Mercury                                                  | 0.0052                | 0.007                       | 0.016                       | 0.004                     | 0.019                     | 0.006                           | 0.0044                    | 0.072                     |                    |
|                       | Nickel                                                   | 0.495                 | 0.502                       | 0.952                       | 1.11                      | 4.03                      | 0.2                             | 0.292                     | 0.595                     |                    |
|                       | Selenium                                                 | ~                     | 0.13                        | 0.16                        | ~                         | 0.5                       | ~                               | ~                         | 0.13                      |                    |
|                       | Silver                                                   | 0.02                  | ~                           | 0.02                        | 0.06                      | 0.48                      | ~                               | 0.02                      | ~                         |                    |
|                       | Thallium                                                 | ~                     | ~                           | ~                           | ~                         | ~                         | ~                               | ~                         | ~                         |                    |
|                       | Zinc                                                     | 7.92                  | 10.5                        | 12.2                        | 9.35                      | 46.1                      | 19.2                            | 10.6                      | 46                        |                    |

Notes: All analytical results are listed in micrograms per square centimeter ( $\mu\text{g}/\text{cm}^2$ ).

~, where present, indicates the result is less than the laboratory method detection limit.

**Table 5: Summary of Estimates of Probable Remediation Costs, Former Remington Rand Facility, 180 Johnson Street, Middletown, CT**

| Source Area                                | Remedial Action Alternative                     | Volume of Contaminated Soil<br>(cubic yards) | Estimated Cost     | Comments/Assumptions                                                                                                                     |
|--------------------------------------------|-------------------------------------------------|----------------------------------------------|--------------------|------------------------------------------------------------------------------------------------------------------------------------------|
| ROW Waste Disposal Area<br>(TP-6 to TP-9)  | Soil excavation and disposal at a RCRA landfill | 1,500                                        | \$450,000          | Institution of an ELUR in the ROW will reduce soil remediation costs                                                                     |
| ROW Waste Disposal Area<br>(TP-11 and B-4) | Soil excavation and off-site asphalt batching   | 600                                          | \$36,000           | Institution of an ELUR in the ROW will reduce soil remediation costs                                                                     |
| UST Area 2                                 | Soil excavation and off-site asphalt batching   | 200                                          | 12,000             | UST was not identified; further investigation of source and extent of release is warranted                                               |
| UST Area 4                                 | Soil excavation and off-site asphalt batching   | 60                                           | 3,600              | Further investigation of potential on-site solvent storage is warranted                                                                  |
| UST Area 5                                 | Soil excavation and off-site asphalt batching   | 3,000                                        | 180,000            | Extent of contamination is not fully delineated; further investigation is recommended                                                    |
| AST 2 Release Area                         | Soil excavation and off-site asphalt batching   | 500                                          | 30,000             | Extent of contamination is not fully delineated; separate phase oil is present; further investigation is warranted                       |
| Railroad Spur Waste Disposal Area          | Soil excavation and disposal at a RCRA landfill | 450                                          | 135,000            | Extent of contamination is not fully delineated; further investigation is warranted                                                      |
| Electrical Transformers                    | Soil excavation and off-site asphalt batching   | 60                                           | No Cost            | Additional testing and remediation of PCB-impacted soil is recommended; Northeast Utilities is responsible for additional RSR activities |
| Surficial Stained Soil Areas               | Soil excavation and off-site asphalt batching   | 130                                          | 7,800              | Pursuit of Residential Direct Exposure Criteria is recommended for this area                                                             |
| UST Removals                               | Tank removal and disposal                       | NA                                           | 13,000             |                                                                                                                                          |
| AST Removals                               | Tank removal and disposal                       | NA                                           | 14,000             |                                                                                                                                          |
| Asbestos                                   | Removal and off-site disposal                   | NA                                           | 42,000             | Most conservative cost estimate is presented here                                                                                        |
| Lead-Based Paint                           | Removal and off-site disposal                   | NA                                           | 18,000             |                                                                                                                                          |
| Containers of OHM                          | Consolidation and off-site recycling/disposal   | NA                                           | 20,000             | Current tenants should be required to appropriately managed OHM upon vacating premises                                                   |
| Analytical Allowance                       | NA                                              | NA                                           | 50,000             |                                                                                                                                          |
| Engineering Allowance                      | NA                                              | NA                                           | 75,000             |                                                                                                                                          |
| Subtotal                                   |                                                 |                                              | \$1,086,400        |                                                                                                                                          |
| 30% Contingency                            |                                                 |                                              | \$325,900          |                                                                                                                                          |
| <b>TOTAL</b>                               |                                                 |                                              | <b>\$1,412,300</b> |                                                                                                                                          |





---

# Appendix A Limitations

## Limitations

*Former Remington Rand Facility  
180 Johnson Street  
Middletown, Connecticut*


- This report has been prepared for the sole and exclusive use of the City of Middletown Economic Development Committee (Client) and is subject to and issued in connection with the Agreement and the provisions thereof. Any use or reliance upon information provided in this report, without the specific written authorization of Client and VHB, shall be at User's sole risk.
- In conducting this assessment, VHB has obtained and relied upon information from multiple sources to form certain conclusions regarding potential environmental issues at and in the vicinity of the subject parcel(s). Except as otherwise noted, VHB has not verified the accuracy or completeness of such information.
- The objectives of the assessment described in this report were to observe the physical characteristics of the subject parcels(s) with respect to evidence of past or present use, storage and/or disposal of oil or hazardous materials, as defined in applicable state and federal environmental law and regulations, and to gather information regarding current and past operations and environmental conditions at and in the vicinity of the subject parcel(s).
- No attempt has been made to assess the compliance status of any past or present Owner or Operator of the Site with any federal, state or local laws or regulations.
- The findings, observations and conclusions presented in this report, including the extent of subsurface explorations and other tests, are limited by the scope of services outlined in our Agreement. Furthermore, the assessment has been performed in accordance with generally accepted engineering practices. No other warranty, expressed or implied, is made.
- The assessment presented in this report is based solely upon information gathered to date, including a limited number of subsurface explorations made on the dates indicated. Should further environmental or other relevant information be developed at a later date, Client should bring the information to the attention of VHB as soon as possible. Based upon an evaluation, VHB may modify the report and its conclusions.

---


## Appendix B Site Photographs



Photograph 1: Suspect UST Area 1, Test Pit Excavation




Photograph 2: Test Pit Excavation Within Right-of-Way




Photograph 3: World War II Ordinance Within Suspect UST Area 2




Photograph 4: GeoProbe® Soil Boring B-17




Photograph 5: GeoProbe® Soil Boring B-3/MW-1




Photograph 6: GeoProbe® Soil Boring B-11




Photograph 7: Bags of Asbestos Within Room #1C



Photograph 8: Suspect Asbestos-Containing Floor Tile




Photograph 9: Asbestos Pipe Insulation in Boiler Room #7




Photograph 10: Asbestos Pipe Insulation in Room #8






Photograph 11: Fire Door Containing Asbestos in Room #1C




Photograph 12: Asbestos Pipe Insulation,  
and Fluorescent Light Fixture in Room #6a



Photograph 13: Mercury Vapor Lights Within Room #1C




Photograph 14: Electric Circuit Breaker Containing PCB Fluids and Asbestos



Photograph 15: 55-Gallon Drum of Waste Oil/Water Adjacent to Room #15



Photograph 16: Miscellaneous Containers of Paint in Boiler Room #7



Photograph 17: Glass Container of HCl and Unknown Drums of Liquids



Photograph 18: Miscellaneous Containers of Insecticides and Pesticides in Room #6

---

# Appendix C

## Test Pit and Soil Boring Logs



Job Number: 40163  
Test Pit No.: UST1, TP-1  
Ground Elev.:  
Equipment: Case 580 Backhoe

\\kirk\admin\ev\richards\pit.xls

Job Number: 40163  
Test Pit No.: UST1, TP-2  
Ground Elev.:  
Equipment: Case 580 Backhoe

|                                                                                                                                                                                                                                                                       |                                                                                                        |                                                                                                  |                                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| <p><u><b>Legend</b></u></p> <p>F = Fine M = Medium C = Coarse</p> <p>F/M = Fine to Medium F/C = Fine to Coarse</p> <p>V. = Very Lt. = Light Dk. = Dark</p> <p>Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange</p> <p>U.S.C. Code = Unified Soil Classification</p> | <p>Trace (Tr.) 0-10%</p> <p>Little (Li.) 10-20%</p> <p>Some (So.) 20-35%</p> <p>And (&amp;) 35-50%</p> | <p><u><b>Excavation Effort:</b></u></p> <p>E = Easy</p> <p>M = Moderate</p> <p>D = Difficult</p> |  <p>Groundwater</p> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|



Job Number: 40163  
Test Pit No.: UST1, TP-3  
Ground Elev.:  
Equipment: Case 580 Backhoe

[illegible]

Job Number: 40163  
Test Pit No.: UST2, TP-1  
Ground Elev.:  
Equipment: Case 580 Backhoe

|                                                                                                                                                                                                                                                                       |                                                                                                        |                                                                                                  |                                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| <p><u><b>Legend</b></u></p> <p>F = Fine M = Medium C = Coarse</p> <p>F/M = Fine to Medium F/C = Fine to Coarse</p> <p>V. = Very Lt. = Light Dk. = Dark</p> <p>Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange</p> <p>U.S.C. Code = Unified Soil Classification</p> | <p>Trace (Tr.) 0-10%</p> <p>Little (Li.) 10-20%</p> <p>Some (So.) 20-35%</p> <p>And (&amp;) 35-50%</p> | <p><u><b>Excavation Effort:</b></u></p> <p>E = Easy</p> <p>M = Moderate</p> <p>D = Difficult</p> |  <p>Groundwater</p> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|

Job Number: 40163  
Test Pit No.: UST3, TP-1  
Ground Elev.:  
Equipment: Case 580 Backhoe

|                                                                                                                                                                                                                                                                       |                                                                                                        |                                                                                                  |                                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| <p><u><b>Legend</b></u></p> <p>F = Fine M = Medium C = Coarse</p> <p>F/M = Fine to Medium F/C = Fine to Coarse</p> <p>V. = Very Lt. = Light Dk. = Dark</p> <p>Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange</p> <p>U.S.C. Code = Unified Soil Classification</p> | <p>Trace (Tr.) 0-10%</p> <p>Little (Li.) 10-20%</p> <p>Some (So.) 20-35%</p> <p>And (&amp;) 35-50%</p> | <p><u><b>Excavation Effort:</b></u></p> <p>E = Easy</p> <p>M = Moderate</p> <p>D = Difficult</p> |  <p>Groundwater</p> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|

Job Number: 40163  
Test Pit No.: UST3, TP-2  
Ground Elev.:  
Equipment: Case 580 Backhoe

\\kirk\admin\ev\richards\pit.xls

Job Number: 40163  
Test Pit No.: UST3, TP-3  
Ground Elev.:  
Equipment: Case 580 Backhoe

Work\admin\ey\richards\oit.xls

Job Number: 40163  
Test Pit No.: UST4, TP-1  
Ground Elev.:  
Equipment: Case 580 Backhoe

|                                                                                                                                                                                                                                                                       |                                                                                                        |                                                                                                  |                                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| <p><u><b>Legend</b></u></p> <p>F = Fine M = Medium C = Coarse</p> <p>F/M = Fine to Medium F/C = Fine to Coarse</p> <p>V. = Very Lt. = Light Dk. = Dark</p> <p>Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange</p> <p>U.S.C. Code = Unified Soil Classification</p> | <p>Trace (Tr.) 0-10%</p> <p>Little (Li.) 10-20%</p> <p>Some (So.) 20-35%</p> <p>And (&amp;) 35-50%</p> | <p><u><b>Excavation Effort:</b></u></p> <p>E = Easy</p> <p>M = Moderate</p> <p>D = Difficult</p> |  <p>Groundwater</p> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|

Job Number: 40163  
Test Pit No.: ROW, TP-1  
Ground Elev.:  
Equipment: Case 580 Backhoe

[illegible]

### Legend

F = Fine M = Medium C = Coarse  
F/M = Fine to Medium F/C = Fine to Coarse  
V. = Very Lt. = Light Dk. = Dark  
Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange  
U.S.C. Code = Unified Soil Classification

Trace (Tr.) 0-10%  
Little (Li.) 10-20%  
Some (So.) 20-35%  
And (&) 35-50%

Excavation Effort:

E = Easy  
M = Moderate  
D = Difficult



## Groundwater

**VHB**

## Test Pit Log

Date: 5/16/97

**Client:** City of Middletown

**Location:** Former Remington Rand Facility

180 Johnson Street, Middletown, CT

VHB Eng.: Marc Richards

Contractor: Civetti Excavation

Job Number: 40163

Test Pit No.: ROW, TP-2

Ground Elev.:

**Equipment:** Case 580 Backhoe

| <b>Sample #</b> | <b>Depth</b> | <b>Soil Description</b>                  | <b>Excav.<br/>Effort</b> | <b>Remarks</b> |
|-----------------|--------------|------------------------------------------|--------------------------|----------------|
|                 | 1            | Fill, ash, cinders, glass, metal, brick. | E                        | Fill           |
|                 | 2            |                                          |                          |                |
|                 | 3            | Reddish brown silty soil, some clay.     | E                        | Natural        |
|                 | 4            |                                          |                          |                |
|                 |              |                                          |                          |                |
|                 |              |                                          |                          |                |
|                 |              |                                          |                          |                |

### Legend

F = Fine M = Medium C = Coarse

F/M = Fine to Medium F/C = Fine to Coarse

V. = Very Lt. = Light Dk. = Dark

Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange

U.S.C. Code = Unified Soil Classification

Trace (Tr.) 0-10%

Little (Li.) 10-20%

**Some (So.) 20-35%**

And (&) 35-50%

**Excavation Effort:**

**E = Easy**

**M = Moderate**

**D = Difficult**



## Groundwater



Job Number: 40163  
Test Pit No.: ROW, TP-3  
Ground Elev.:  
Equipment: Case 580 Backhoe

|                                                                                                                                                                                                                                                                       |                                                                                                        |                                                                                                  |                                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| <p><b><u>Legend</u></b></p> <p>F = Fine M = Medium C = Coarse</p> <p>F/M = Fine to Medium F/C = Fine to Coarse</p> <p>V. = Very Lt. = Light Dk. = Dark</p> <p>Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange</p> <p>U.S.C. Code = Unified Soil Classification</p> | <p>Trace (Tr.) 0-10%</p> <p>Little (Li.) 10-20%</p> <p>Some (So.) 20-35%</p> <p>And (&amp;) 35-50%</p> | <p><b><u>Excavation Effort:</u></b></p> <p>E = Easy</p> <p>M = Moderate</p> <p>D = Difficult</p> |  <p>Groundwater</p> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|

Job Number: 40163  
Test Pit No.: ROW, TP-4  
Ground Elev.:  
Equipment: Case 580 Backhoe

[illegible]

### Legend

F = Fine M = Medium C = Coarse  
F/M = Fine to Medium F/C = Fine to Coarse  
V. = Very Lt. = Light Dk. = Dark  
Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange  
U.S.C. Code = Unified Soil Classification

Trace (Tr.) 0-10%  
Little (Li.) 10-20%  
Some (So.) 20-35%  
And (&) 35-50%

**Excavation Effort:**

E = Easy  
M = Moderate  
D = Difficult



## Groundwater

Job Number: 40163  
Test Pit No.: ROW, TP-5  
Ground Elev.:  
Equipment: Case 580 Backhoe

\\kirk\admin\ev\richards\pit.xls

Job Number: 40163  
Test Pit No.: ROW, TP-6  
Ground Elev.:  
Equipment: Case 580 Backhoe

|                                                                                                                                                                                                                                                                       |                                                                                                        |                                                                                                  |                                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| <p><u><b>Legend</b></u></p> <p>F = Fine M = Medium C = Coarse</p> <p>F/M = Fine to Medium F/C = Fine to Coarse</p> <p>V. = Very Lt. = Light Dk. = Dark</p> <p>Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange</p> <p>U.S.C. Code = Unified Soil Classification</p> | <p>Trace (Tr.) 0-10%</p> <p>Little (Li.) 10-20%</p> <p>Some (So.) 20-35%</p> <p>And (&amp;) 35-50%</p> | <p><u><b>Excavation Effort:</b></u></p> <p>E = Easy</p> <p>M = Moderate</p> <p>D = Difficult</p> |  <p>Groundwater</p> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|

Job Number: 40163  
Test Pit No.: ROW, TP-7  
Ground Elev.:  
Equipment: Case 580 Backhoe

[illegible]

### Legend

F = Fine M = Medium C = Coarse  
F/M = Fine to Medium F/C = Fine to Coarse  
V. = Very Lt. = Light Dk. = Dark  
Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange  
U.S.C. Code = Unified Soil Classification

Trace (Tr.) 0-10%  
Little (Li.) 10-20%  
Some (So.) 20-35%  
And (&) 35-50%

**Excavation Effort:**

E = Easy  
M = Moderate  
D = Difficult



## Groundwater

Job Number: 40163  
Test Pit No.: ROW, TP-8  
Ground Elev.:  
Equipment: Case 580 Backhoe

|                                                                                                                                                                                                                                                                       |                                                                                                        |                                                                                                  |                                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| <p><u><b>Legend</b></u></p> <p>F = Fine M = Medium C = Coarse</p> <p>F/M = Fine to Medium F/C = Fine to Coarse</p> <p>V. = Very Lt. = Light Dk. = Dark</p> <p>Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange</p> <p>U.S.C. Code = Unified Soil Classification</p> | <p>Trace (Tr.) 0-10%</p> <p>Little (Li.) 10-20%</p> <p>Some (So.) 20-35%</p> <p>And (&amp;) 35-50%</p> | <p><u><b>Excavation Effort:</b></u></p> <p>E = Easy</p> <p>M = Moderate</p> <p>D = Difficult</p> |  <p>Groundwater</p> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|

Job Number: 40163  
Test Pit No.: ROW, TP-9  
Ground Elev.:  
Equipment: Case 580 Backhoe

|                                                                                                                                                                                                                                                                       |                                                                                                        |                                                                                                  |                                                                                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| <p><u><b>Legend</b></u></p> <p>F = Fine M = Medium C = Coarse</p> <p>F/M = Fine to Medium F/C = Fine to Coarse</p> <p>V. = Very Lt. = Light Dk. = Dark</p> <p>Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange</p> <p>U.S.C. Code = Unified Soil Classification</p> | <p>Trace (Tr.) 0-10%</p> <p>Little (Li.) 10-20%</p> <p>Some (So.) 20-35%</p> <p>And (&amp;) 35-50%</p> | <p><u><b>Excavation Effort:</b></u></p> <p>E = Easy</p> <p>M = Moderate</p> <p>D = Difficult</p> |  <p>Groundwater</p> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|

Job Number: 40163  
Test Pit No.: ROW, TP-10  
Ground Elev.:  
Equipment: Case 580 Backhoe

|                                                                                                                                                                                                                                                                       |                                                                                                        |                                                                                                  |                                                                                                             |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------|
| <p><u><b>Legend</b></u></p> <p>F = Fine M = Medium C = Coarse</p> <p>F/M = Fine to Medium F/C = Fine to Coarse</p> <p>V. = Very Lt. = Light Dk. = Dark</p> <p>Gr. = Grey Br. = Brown Yel. = Yellow Org. = Orange</p> <p>U.S.C. Code = Unified Soil Classification</p> | <p>Trace (Tr.) 0-10%</p> <p>Little (Li.) 10-20%</p> <p>Some (So.) 20-35%</p> <p>And (&amp;) 35-50%</p> | <p><u><b>Excavation Effort:</b></u></p> <p>E = Easy</p> <p>M = Moderate</p> <p>D = Difficult</p> | <br><p>Groundwater</p> |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------|



Job Number: 40163  
Test Pit No.: ROW, TP-11  
Ground Elev.:  
Equipment: Case 580 Backhoe

\\kirk\admin\lev\richards\pit.xls

# VHB Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163****Boring #:**

**B-1**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/20/97  
Weather: Cloudy, misting

Boring Depth 12'  
Depth to Ground Water 7'  
VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million

NSR = No Sample Recovered

NA = Not Applicable

# VHB Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

**Boring #:**

**B-2**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/20/97

**Weather:** Cloudy, misting

Boring Depth 12'

Depth to Ground Water 6'

**VHB Representative Marc Richards**

[illegible]

PPM = Parts Per Million

NSR = No Sample Recovered

NA = Not Applicable

# VHB Soil Boring Report

## Site Data:

Former Remington Rand Facility  
180 Johnson Road  
Middletown, CT

Project # 40163

Boring #:

**MW-1/B-3**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/20/97  
Weather: Clear, Sunny

Boring Depth 12'  
Depth to Ground Water 6'  
VHB Representative Marc Richards

| Depth  | Sample # | Blow Counts | Recovery (in/in) | PID (PPM)   | Field Classification And Remarks                                    |
|--------|----------|-------------|------------------|-------------|---------------------------------------------------------------------|
| 0-2'   | S-1      | na          | 30/48            | 0           | 3" of dark brown fine to medium sand. Light brown fine silty sand.  |
| 2-4'   | S-2      | na          | --               | 0           | light brown fine silty sand                                         |
| 4-6'   | S-3      | na          | 30/48            | 0           | light brown fine sand, wet at 6'                                    |
| 6-8'   | S-4      | na          | --               | 0           | light brown fine sand, saturated, no odors                          |
| 8-10'  | S-5      | na          | 48/48            | 3.3         | light brown fine to medium sand, mild solvent odors, saturated      |
| 10-12' | S-6      | na          | --               | not sampled | medium to coarse sand, mild solvent odors, very tight clay at 11.5' |
|        |          |             |                  |             |                                                                     |
|        |          |             |                  |             |                                                                     |
|        |          |             |                  |             | Monitoring well set at 12'                                          |
|        |          |             |                  |             | 10 feet of screen                                                   |
|        |          |             |                  |             | Sand pack to one foot above screen                                  |
|        |          |             |                  |             | One foot clay bentonite seal                                        |
|        |          |             |                  |             |                                                                     |
|        |          |             |                  |             |                                                                     |
|        |          |             |                  |             |                                                                     |
|        |          |             |                  |             |                                                                     |

PPM = Parts Per Million

NSR = No Sample Recovered

NA = Not Applicable

# VHB Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

**Boring #:**

**B-4**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/20/97  
Weather: Clear, Sunny

Boring Depth 12'  
Depth to Ground Water 8'  
VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million

NSR = No Sample Recovered

NA = Not Applicable

# VHB Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

**Boring #:**

**B-5**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/20/97  
Weather: Clear, Sunny

Boring Depth 12'  
Depth to Ground Water 7'  
VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million

NSR = No Sample Recovered

NA = Not Applicable

**VHB**

# Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

Boring #:

**B-6**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/20/97  
Weather: Clear, Sunny

Boring Depth 12'  
Depth to Ground Water 7-8'  
VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million  
NSR = No Sample Recovered  
NA = Not Applicable

# VHB Soil Boring Report

## Site Data:

Former Remington Rand Facility  
180 Johnson Road  
Middletown, CT

Project # 40163

Boring #:

**MW-2/B-7**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/20/97  
Weather: Clear, Sunny

Boring Depth 12'  
Depth to Ground Water 7-8'  
VHB Representative Marc Richards

| Depth  | Sample # | Blow Counts | Recovery (in/in) | PID (PPM) | Field Classification And Remarks                                     |
|--------|----------|-------------|------------------|-----------|----------------------------------------------------------------------|
| 0-2'   | S-1      | na          | 30/48            | 0         | Fine silty sand, some brick, light brown to dark brown.              |
| 2-4'   | S-2      | na          | --               | 0         | Light to dark brown fine silty sand.                                 |
| 4-6'   | S-3      | na          | 24/48            | 0         | Fine to medium sand, some gravel. No odors.                          |
| 6-8'   | S-4      | na          | --               | 0         | Fine to medium sand, some gravel. No odors. satuated at 7 to 8 feet. |
| 8-10'  | S-5      | na          | 30/48            | 0         | Medium to coarse sand, some gravel. No odors. Saturated.             |
| 10-12' | S-6      | na          | --               | 4         | Medium to coarse sand, some gravel. Mild odors. Saturated.           |
|        |          |             |                  |           | Monitoring well set at 12'                                           |
|        |          |             |                  |           | 10 feet of screen                                                    |
|        |          |             |                  |           | Sand pack to one foot above screen                                   |
|        |          |             |                  |           | One foot clay bentonite seal above sand.                             |
|        |          |             |                  |           |                                                                      |
|        |          |             |                  |           |                                                                      |
|        |          |             |                  |           |                                                                      |
|        |          |             |                  |           |                                                                      |
|        |          |             |                  |           |                                                                      |

PPM = Parts Per Million

NSR = No Sample Recovered

NA = Not Applicable



# VHB Soil Boring Report

## Site Data:

Former Remington Rand Facility  
180 Johnson Road  
Middletown, CT

Project # 40163

Boring #:

**MW-3/B-8**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/20/97  
Weather: Clear, Sunny

Boring Depth 12'  
Depth to Ground Water 9'  
VHB Representative Marc Richards

| Depth  | Sample # | Blow Counts | Recovery (in/in) | PID (PPM) | Field Classification And Remarks                                 |
|--------|----------|-------------|------------------|-----------|------------------------------------------------------------------|
| 0-2'   | S-1      | na          | 32/48            | 0         | Ash, coal residue, medium sand, some metal filings.              |
| 2-4'   | S-2      | na          | --               | 0         | Ash, coal residue, medium sand, some metal filings.              |
| 4-6'   | S-3      | na          | 30/48            | 4         | Tight light brown silty clay, mild solvent/gasoline odors.       |
| 6-8'   | S-4      | na          | --               | 22        | Light gray fine silty sand. Gasoline/solvent odors. Moist at 8'. |
| 8-10'  | S-5      | na          | 30/48            | 15        | Light gray fine silty sand. Gasoline/solvent odors. Saturated.   |
| 10-12' | S-6      | na          | --               | 10        | Fine silty sand, some gravel. Mild gasoline/solvent odors.       |
|        |          |             |                  |           |                                                                  |
|        |          |             |                  |           |                                                                  |
|        |          |             |                  |           | Monitoring well set at 12'                                       |
|        |          |             |                  |           | 10 feet of screen                                                |
|        |          |             |                  |           | Sand pack to one foot above screen                               |
|        |          |             |                  |           | One foot clay bentonite seal above sand.                         |
|        |          |             |                  |           |                                                                  |
|        |          |             |                  |           |                                                                  |
|        |          |             |                  |           |                                                                  |
|        |          |             |                  |           |                                                                  |

PPM = Parts Per Million

NSR = No Sample Recovered

NA = Not Applicable

**VHB****Site Data:**

## Former Remington Rand Facility

**180 Johnson Road**

**Middletown, CT**

**Project # 40163**

**Boring #:**

**B-9**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/20/97

**Weather:** Clear, Sunny

Boring Depth 14'

Depth to Ground Water 9'

**VHB Representative Marc Richards**

| Depth  | Sample # | Blow Counts | Recovery (in/in) | PID (PPM) | Field Classification And Remarks                                                                                      |
|--------|----------|-------------|------------------|-----------|-----------------------------------------------------------------------------------------------------------------------|
| 0-2'   | S-1      | na          | 18/24            | 0         | Coal, ash, medium sand.                                                                                               |
| 2-4'   | S-2      | na          | 12/24            | 0         | Coal, ash, medium sand.                                                                                               |
| 4-6'   | S-3      | na          | 12/24            | 0         | Coal, ash, medium sand.                                                                                               |
| 6-8'   | S-4      | na          | 10/24            | 0         | Coal, ash, medium sand.                                                                                               |
| 8-10'  | S-5      | na          | 16/24            | --*       | Light brown medium sand from 8 to 9 feet. Dark black No. 4 to No 6 fuel oil stained soil from 9 to 10 feet.           |
| 10-12' | S-6      | na          | 24/24            | --*       | Heavy oil-saturated soil from 10 to 11 feet. Oil is migrating in to light brown tight silty fine sand from 11 to 12'. |
| 12-14' | S-7      | na          | 24/24            | 0         | Light brown tight silty fine sand. No oil.                                                                            |
|        |          |             |                  |           |                                                                                                                       |
|        |          |             |                  |           |                                                                                                                       |
|        |          |             |                  |           | * Due to limited soil, no samples were PID field screened from 8 to 12 feet.                                          |
|        |          |             |                  |           |                                                                                                                       |
|        |          |             |                  |           |                                                                                                                       |
|        |          |             |                  |           |                                                                                                                       |
|        |          |             |                  |           |                                                                                                                       |
|        |          |             |                  |           |                                                                                                                       |

PPM = Parts Per Million

NSR = No Sample Recovered

NA = Not Applicable

# VHB Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

Boring #:

**MW-4/B-10**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/20/97

**Weather:** Clear, Sunny

Boring Depth 16'

Depth to Ground Water 10'

### VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

*Vanasse Hangen Brustlin, Inc.*

kirk\admin\evrichards\soil.xls

**VHB****Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

**Boring #:**

**B-11**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/20/97  
Weather: Clear, Sunny

Boring Depth 8'  
Depth to Ground Water 4'  
VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

# VHB Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163****Boring #:**

**B-12**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/20/97

**Weather:** Clear, Sunny

Boring Depth 8'

Depth to Ground Water 4'

**VHB Representative Marc Richards**

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

***VHB*****Site Data:**

**Former Remington Rand Facility**  
180 Johnson Road  
Middletown, CT

**Project # 40163**

**Boring #:** -

**B-13**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/20/97

**Weather:** Clear, Sunny

Boring Depth 8'

Depth to Ground Water 4'

**VHB Representative Marc Richards**

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

# VHB Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

**Boring #:**

**MW-5/B-14**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/21/97  
Weather: Clear, Sunny

Boring Depth 12'  
Depth to Ground Water 4'  
VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million  
NSR = No Sample Recovered  
NA = Not Applicable

NS = Not Sampled

*Vanasse Hangen Brustlin, Inc.*

kirk\admin\evrichards\soit.xls

**VHB**

# Soil Boring Report

**Site Data:**

### Former Remington Rand Facility

**180 Johnson Road**

**Middletown, CT**

**Project # 40163**

**Boring #:**

**B-15**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/21/97

**Weather:** Clear, Sunny

Boring Depth 12'

Depth to Ground Water 4'

**VHB Representative Marc Richards**

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

*Vanasse Hangen Brustlin, Inc.*

kirk\admin\evrichards\soil.xls



**VHB**

# Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

Boring #:

**B-16**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/21/97  
Weather: Clear, Sunny

Boring Depth 8'  
Depth to Ground Water 4'  
VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million  
NSR = No Sample Recovered  
NA = Not Applicable

NS = Not Sampled

# VHB Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

**Boring #:**

**B-17**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/21/97

**Weather:** Clear, Sunny

Boring Depth 12'

Depth to Ground Water 4'

VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

# VHB Soil Boring Report

## Site Data:

Former Remington Rand Facility  
180 Johnson Road  
Middletown, CT

Project # 40163

Boring #:

**MW-6/B-18**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/21/97  
Weather: Clear, Sunny

Boring Depth 12'  
Depth to Ground Water 5'  
VHB Representative Marc Richards

| Depth  | Sample # | Blow Counts | Recovery (in/in) | PID (PPM) | Field Classification And Remarks                                                                                                             |
|--------|----------|-------------|------------------|-----------|----------------------------------------------------------------------------------------------------------------------------------------------|
| 0-2'   | S-1      | na          | 30/48            | 5         | Metal filings, fine to medium sand, some gravel.                                                                                             |
| 2-4'   | S-2      | na          | --               | 224       | Light gray fine sand. Strong gasoline/diesel odors.                                                                                          |
| 4-6'   | S-3      | na          | 35/48            | 200       | Light gray fine sand. Strong gasoline/diesel odors. Wet.                                                                                     |
| 6-8'   | S-4      | na          | --               | 62        | Light gray fine to medium sand. Strong gasoline/diesel odors. Saturated.                                                                     |
| 8-10'  | S-5      | na          | 33/48            | 119       | Light gray fine to medium sand. Strong gasoline/diesel odors. Saturated.                                                                     |
| 10-12' | S-6      | na          | --               | 0         | Light gray fine to medium sand. Strong gasoline/diesel odors from 10 to 11 feet.<br>Tight light brown clay from 11 to 12'. No odors in clay. |
|        |          |             |                  |           |                                                                                                                                              |
|        |          |             |                  |           |                                                                                                                                              |
|        |          |             |                  |           | Monitoring well set at 12'                                                                                                                   |
|        |          |             |                  |           | 10 feet of screen                                                                                                                            |
|        |          |             |                  |           | Sand pack to one foot above screen                                                                                                           |
|        |          |             |                  |           | One foot clay bentonite seal                                                                                                                 |
|        |          |             |                  |           |                                                                                                                                              |
|        |          |             |                  |           |                                                                                                                                              |
|        |          |             |                  |           |                                                                                                                                              |
|        |          |             |                  |           |                                                                                                                                              |

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

**VHB**

# Soil Boring Report

**Site Data:**

### Former Remington Rand Facility

**180 Johnson Road**

**Middletown, CT**

**Project # 40163**

**Boring #:**

**B-19**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/21/97

**Weather:** Clear, Sunny

Boring Depth 12'

Depth to Ground Water 5'

**VHB Representative Marc Richards**

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

# VHB Soil Boring Report

**Site Data:**

### Former Remington Rand Facility

**180 Johnson Road**

**Middletown, CT**

**Project # 40163**

**Boring #:**

## B-20

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/21/97

**Weather:** Clear, Sunny

Boring Depth 12'

Depth to Ground Water 5'

**VHB Representative Marc Richards**

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

*Vanasse Hangen Brustlin, Inc.*

kirk\admin\evrichards\soil.xls

***VHB***

# Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

Project # 40163

**Boring #:**

**B-21**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/21/97  
Weather: Clear, Sunny

Boring Depth 8'  
Depth to Ground Water 5'  
VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million  
NSR = No Sample Recovered  
NA = Not Applicable

NS = Not Sampled

# VHB Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

Boring #:

B-22

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/21/97

**Weather:** Clear, Sunny

Boring Depth 8'

Depth to Ground Water 5'

**VHB Representative Marc Richards**

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

***VHB*****Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163****Boring #:**

**B-23**

Driller: TDS  
Drill Rig: GeoProbe  
Technique: Direct Push  
Date: 5/21/97  
Weather: Clear, Sunny

Boring Depth 8'  
Depth to Ground Water 5'  
VHB Representative Marc Richards

[illegible]

PPM = Parts Per Million  
NSR = No Sample Recovered  
NA = Not Applicable

NS = Not Sampled



**VHB**

# Soil Boring Report

**Site Data:**

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163****Boring #:**

**B-24**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/21/97

**Weather:** Clear, Sunny

Boring Depth 8'

Depth to Ground Water 5'

VHB Representative **Marc Richards**

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

*Vanasse Hangen Brustlin, Inc.*

kirk\admin\evrichards\soil.xls

**VHB**

### Site Data:

**Former Remington Rand Facility**  
**180 Johnson Road**  
**Middletown, CT**

**Project # 40163**

**Boring #:**

**B-25**

Driller: TDS

Drill Rig: GeoProbe

### Technique: Direct Push

Date: 5/21/97

**Weather:** Clear, Sunny

Boring Depth 12'

Depth to Ground Water 6'

**VHB Representative Marc Richards**

[illegible]

PPM = Parts Per Million

NS = Not Sampled

NSR = No Sample Recovered

NA = Not Applicable

---



# Appendix D

## Soil, Groundwater, and Wipe Sample Laboratory Analytical Results





39 Spruce Street • 2nd Floor • East longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

REPORT DATE: 05/29/97

PURCHASE ORDER NUMBER: 40163  
PROJECT NUMBER: PRJ.# 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29603  
JOB NUMBER: 29603

The results of analyses performed on the following samples submitted to the CON-TEST Analytical Laboratory are found in this report

PROJECT LOCATION: MIDDLETOWN, CT

| FIELD SAMPLE # | LAB ID   | MATRIX | SAMPLE DESCRIPTION | TEST             |
|----------------|----------|--------|--------------------|------------------|
| UST3/TP-1/0-2' | 97808803 | SOIL   | BURN PIT           | metals(13pp)socp |
| UST3/TP-1/3-4' | 97808804 | SOIL   | BURN PIT           | 8270-soil bn-2   |
| UST3/TP-1/3-4' | 97808804 | SOIL   | BURN PIT           | 8270-soil bn1    |
| UST3/TP-1/3-4' | 97808804 | SOIL   | BURN PIT           | 8270-soil-acid   |
| UST3/TP-1/3-4' | 97808804 | SOIL   | BURN PIT           | pcb - soil       |
| UST3/TP-1/3-4' | 97808804 | SOIL   | BURN PIT           | tph gc 8100m     |

The CON-TEST Environmental Laboratory operates under the following certifications and accreditations:

|                             |                              |
|-----------------------------|------------------------------|
| AIHA 308                    | AIHA ELLAP (LEAD) 6838       |
| MASSACHUSETTS MA100         | MAINE (POTABLE/NON-POTABLE)  |
| CONNECTICUT PH-0567         | VERMONT DOH (LEAD) No. 15036 |
| NEW YORK ELAP 10899         | RHODE ISLAND (LIC. No. 112)  |
| OHIO (ENVIRO. LEAD) # 10005 |                              |
| NEW HAMPSHIRE 2516          |                              |

I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document.

Edward Denson 5/30/97  
SIGNATURE DATE

Tod Kopyscinski  
Director of Operations

Edward Denson  
Technical Director

MARC RICHARDS  
 VANASSE HANGEN BRUSTLIN, INC.  
 101 WALNUT STREET  
 WATERTOWN, MA 02272

 Purchase Order Number: 40163  
 Project Number: PRJ.# 40163

 05/29/97  
 page 1 of 9

 Project Location: MIDDLETOWN, CT  
 Date Received: 05/15/97

 LIMS-BAT #: LIMS-29603  
 Job Number: 29603  
 Sample Matrix: SOIL

 Sampled: 05/15/97  
 BURN PIT  
 UST3/TP-1/3-4'

|                             | Units | 97B08804 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| Acenaphthene                | mg/kg | 146      | 05/24/97      | WSD     | 13.3 |            |     |
| Acenaphthylene              | mg/kg | BDL      | 05/24/97      | WSD     | 13.3 |            |     |
| Aniline                     | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Anthracene                  | mg/kg | 316      | 05/24/97      | WSD     | 13.3 |            |     |
| Benzidene                   | mg/kg | ND       | 05/24/97      | WSD     | 93.3 |            |     |
| Benzoic Acid                | mg/kg | ND       | 05/24/97      | WSD     | 40.0 |            |     |
| Benzo(a)anthracene          | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Benzo(a)pyrene              | mg/kg | 400      | 05/24/97      | WSD     | 26.7 |            |     |
| Benzo(b)fluoranthene        | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Benzo(g,h,i)perylene        | mg/kg | BDL      | 05/24/97      | WSD     | 40.0 |            |     |
| Benzo(k)fluoranthene        | mg/kg | ND       | 05/24/97      | WSD     | 26.7 |            |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/24/97      | WSD     | 26.7 |            |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Butylbenzylphthalate        | mg/kg | ND       | 05/24/97      | WSD     | 26.7 |            |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/24/97      | WSD     | 26.7 |            |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Chrysene                    | mg/kg | 548      | 05/24/97      | WSD     | 26.7 |            |     |
| Dibenzofuran                | mg/kg | 73.3     | 05/24/97      | WSD     | 13.3 |            |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/24/97      | WSD     | 26.7 |            |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/24/97      | WSD     | 26.7 |            |     |
| Diethylphthalate            | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Dimethylphthalate           | mg/kg | ND       | 05/24/97      | WSD     | 26.7 |            |     |
| Di-n-butylphthalate         | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Di-n-octylphthalate         | mg/kg | ND       | 05/24/97      | WSD     | 26.7 |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/29/97  
page 2 of 9

Purchase Order Number: 40163  
Project Number: PRJ.# 40163

LIMS-BAT #: LIMS-29603  
Job Number: 29603  
Sample Matrix: SOIL

Sampled: 05/15/97  
BURN PIT  
UST3/TP-1/3-4'

|                            | Units | 97808804 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Fluoranthene               | mg/kg | 1270     | 05/24/97      | WSD     | 13.3 |            |     |
| Fluorene                   | mg/kg | 85.3     | 05/24/97      | WSD     | 13.3 |            |     |
| Hexachlprobenzene          | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | 163      | 05/24/97      | WSD     | 13.3 |            |     |
| Isophorone                 | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 2-Methylnaphthalene        | mg/kg | 129      | 05/24/97      | WSD     | 13.3 |            |     |
| Naphthalene                | mg/kg | 76.7     | 05/24/97      | WSD     | 13.3 |            |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| Phenanthrene               | mg/kg | 1270     | 05/24/97      | WSD     | 13.3 |            |     |
| Pyrene                     | mg/kg | 1130     | 05/24/97      | WSD     | 40.0 |            |     |
| Pyridine                   | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/24/97      | WSD     | 13.3 |            |     |

## Analytical Method(s):

SW846 8270

SAMPLES ARE EXTRACTED IN METHYLENE CHLORIDE/ACETONE AND  
FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

05/29/97  
page 3 of 9

Purchase Order Number: 40163  
Project Number: PRJ.# 40163

LIMS-BAT #: LIMS-29603  
Job Number: 29603  
Sample Matrix: SOIL

Sampled: 05/15/97  
BURN PIT  
UST3/TP-1/3-4'

|                                  | Units | 97808804 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/24/97         | WSD     | 26.7 |               |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/24/97         | WSD     | 13.3 |               |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/24/97         | WSD     | 13.3 |               |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/24/97         | WSD     | 53.3 |               |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/24/97         | WSD     | 13.3 |               |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/24/97         | WSD     | 13.3 |               |     |
| 2-Methylphenol (o-cresol)        | mg/kg | BDL      | 05/24/97         | WSD     | 13.3 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | BDL      | 05/24/97         | WSD     | 13.3 |               |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/24/97         | WSD     | 13.3 |               |     |
| 4-Nitrophenol                    | mg/kg | BDL      | 05/24/97         | WSD     | 13.3 |               |     |
| Pentachlorophenol                | mg/kg | ND       | 05/24/97         | WSD     | 13.3 |               |     |
| Phenol                           | mg/kg | BDL      | 05/24/97         | WSD     | 13.3 |               |     |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/24/97         | WSD     | 13.3 |               |     |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/24/97         | WSD     | 13.3 |               |     |

Analytical Method(s):

SW846 8270

SAMPLES ARE EXTRACTED IN METHYLENE CHLORIDE/ACETONE AND  
FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



05/29/97  
 page 4 of 9

 Purchase Order Number: 40163  
 Project Number: PRJ.# 40163

 LIMS-BAT #: LIMS-29603  
 Job Number: 29603  
 Sample Matrix: SOIL

 Sampled: 05/15/97  
 BURN PIT  
 UST3/TP-1/0-2'

|           | Units | 97B08803 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|-------|------------|-----|
| Antimony  | mg/kg | ND       | 05/22/97      | KLF     | 24.8  |            |     |
| Arsenic   | mg/kg | 87.3     | 05/22/97      | KLF     | 4.95  |            |     |
| Beryllium | mg/kg | 0.18     | 05/22/97      | KLF     | 0.10  |            |     |
| Cadmium   | mg/kg | 3.10     | 05/22/97      | KLF     | 0.05  |            |     |
| Chromium  | mg/kg | 99.8     | 05/22/97      | KLF     | 0.35  |            |     |
| Copper    | mg/kg | 16300    | 05/22/97      | KLF     | 0.10  |            |     |
| Lead      | mg/kg | 518      | 05/22/97      | KLF     | 2.48  | 1000       | P   |
| Mercury   | mg/kg | 0.310    | 05/21/97      | APP     | 0.020 |            |     |
| Nickel    | mg/kg | 5160     | 05/22/97      | KLF     | 0.25  |            |     |
| Selenium  | mg/kg | 85.1     | 05/22/97      | KLF     | 4.95  |            |     |
| Silver    | mg/kg | ND       | 05/22/97      | KLF     | 4.95  |            |     |
| Thallium  | mg/kg | 56.2     | 05/22/97      | KLF     | 9.90  |            |     |
| Zinc      | mg/kg | 2950     | 05/22/97      | KLF     | 0.50  |            |     |

## Analytical Method(s):

 Antimony  
 SW846 3050/6010

 SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
 INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

 Arsenic  
 SW846 3050/6010

 SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
 INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

 Beryllium  
 SW846 3050/6010

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/29/97  
page 5 of 9

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Cadmium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Chromium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Copper

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Lead

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Mercury

SW846 3050/7471

SAMPLES ARE DIGESTED WITH ACIDS AND THEN ANALYZED BY  
COLD VAPOR (FLAMELESS) ATOMIC ABSORPTION SPECTROPHOTOMETRY

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

05/29/97  
page 6 of 9Nickel  
SW846 3050/6010SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.Selenium  
SW846 3050/6010SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.Silver  
SW846 3050/6010SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.Thallium  
SW846 3050/6010SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.Zinc  
SW846 3050/6010SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

05/29/97  
 page 7 of 9

 Purchase Order Number: 40163  
 Project Number: PRJ.# 40163

 LIMS-BAT #: LIMS-29603  
 Job Number: 29603  
 Sample Matrix: SOIL

 Sampled: 05/15/97  
 BURN PIT  
 UST3/TP-1/3-4'

|               | Units | 97B08804 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| PCB 1221      | mg/kg | ND       | 05/23/97         | HFF     |       |               |     |
| PCB 1232      | mg/kg | ND       | 05/23/97         | HFF     |       |               |     |
| PCB 1242/1016 | mg/kg | ND       | 05/23/97         | HFF     |       |               |     |
| PCB 1248      | mg/kg | ND       | 05/23/97         | HFF     |       |               |     |
| PCB 1254      | mg/kg | ND       | 05/23/97         | HFF     |       |               |     |
| PCB 1260      | mg/kg | ND       | 05/23/97         | HFF     |       |               |     |
| Total PCB     | mg/kg | ND       | 05/23/97         | HFF     | 0.481 |               |     |

## Analytical Method(s):

SW846 8080

 SAMPLES ARE EXTRACTED INTO HEXANE AND ANALYZED BY GAS CHROMATOGRAPHY  
 WITH ELECTRON CAPTURE DETECTION.

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163  
 Project Number: PRJ.# 40163

 LIMS-BAT #: LIMS-29603  
 Job Number: 29603  
 Sample Matrix: SOIL

 Sampled: 05/15/97  
 BURN PIT  
 UST3/TP-1/3-4'

|                    | Units | 97B08804 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|--------------------|-------|----------|------------------|---------|-----|---------------|-----|
| OTHER HYDROCARBONS | MG/KG | 830      | 05/20/97         | JB      | 420 |               |     |

Analytical Method(s):

MODIFIED SW846 8100

SAMPLES ARE EXTRACTED INTO METHYLENE CHLORIDE AND ANALYZED BY GAS CHROMATOGRAPHY WITH FLAME IONIZATION DETECTION (FID). ALL PEAKS ELUTING IN THE PETROLEUM FUEL REGION ARE QUANTITATED AS #2 FUEL OIL.

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

The following notes were attached to the reported analysis:

Sample: 97B08803

Analysis: Antimony

ELEVATED METHOD DETECTION LIMIT DUE TO MATRIX INTERFERENCES.

Sample: 97B08803

Analysis: Silver

ELEVATED METHOD DETECTION LIMIT DUE TO MATRIX INTERFERENCES.

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or

regulatory level for comparison with data to

determine PASS (P) or FAIL (F) condition of results.



**QC SUMMARY REPORT**

**SAMPLE QC:** Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/28/97

Lims Bat #: LIMS-29603

Page 1 of 7

QC Batch Number: GC/ECD-1286

| Sample Id   | Analysis              | QC Analysis | Values | Units | Limits |
|-------------|-----------------------|-------------|--------|-------|--------|
| -----       | -----                 | -----       | -----  | ----- | -----  |
| BLANK-07891 | PCB 1232              | Blank       | 0.000  | mg/kg |        |
|             | PCB 1242/1016         | Blank       | 0.000  | mg/kg |        |
|             | PCB 1254              | Blank       | 0.000  | mg/kg |        |
|             | PCB 1260              | Blank       | 0.000  | mg/kg |        |
|             | PCB 1248              | Blank       | 0.000  | mg/kg |        |
|             | PCB 1221              | Blank       | 0.000  | mg/kg |        |
|             | Total PCB             | Blank       | <0.025 | mg/kg |        |
|             | Dibutylchloroendate ( | Blank       | 106.5  | %     |        |

**SAMPLE QC:** Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/28/97

Lims Bat #: LIMS-29603

Page 2 of 7

QC Batch Number: GC/FID-0762

| Sample Id   | Analysis           | QC Analysis | Values | Units         | Limits |
|-------------|--------------------|-------------|--------|---------------|--------|
| -----       | -----              | -----       | -----  | -----         | -----  |
| BLANK-07835 | OTHER HYDROCARBONS | Blank       | <8.3   | MG/KG         |        |
|             | OTHER HYDROCARBONS | Blank       | <8.3   | mg/kg dry wt. |        |



**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/28/97

Lims Bat #: LIMS-29603

Page 3 of 7

QC Batch Number: GCHS/SEMI-0731

| Sample Id   | Analysis               | QC Analysis        | Values | Units | Limits     |
|-------------|------------------------|--------------------|--------|-------|------------|
| -----       | -----                  | -----              | -----  | ----- | -----      |
| 97B08804    | Phenol - D6 mg/kg re   | Surrogate Recovery | 88.0   | %     | 24.0-113.0 |
|             | Nitrobenzene - D5 mg   | Surrogate Recovery | 80.0   | %     | 23.0-120.0 |
|             | 2-Fluorobipheny mg/k   | Surrogate Recovery | 91.0   | %     | 25.0-121.0 |
|             | 2,4,6-Tribromophenol   | Surrogate Recovery | 98.0   | %     | 19.0-122.0 |
|             | Terphenyl - D14 mg/k   | Surrogate Recovery | 60.0   | %     | 18.0-137.0 |
|             | 2-Fluorophenol mg/kg   | Surrogate Recovery | 85.5   | %     | 30.0-115.0 |
| BLANK-07915 | 1,4-Dichlorobenzene    | Blank              | <0.33  | mg/kg |            |
|             | Naphthalene            | Blank              | <0.33  | mg/kg |            |
|             | 1,2-Dichlorobenzene    | Blank              | <0.33  | mg/kg |            |
|             | 1,3-Dichlorobenzene    | Blank              | <0.33  | mg/kg |            |
|             | Acenaphthene           | Blank              | <0.33  | mg/kg |            |
|             | Acenaphthylene         | Blank              | <0.33  | mg/kg |            |
|             | Aniline                | Blank              | <0.33  | mg/kg |            |
|             | Anthracene             | Blank              | <0.33  | mg/kg |            |
|             | Benzidene              | Blank              | <2.33  | mg/kg |            |
|             | Benzo(a)anthracene     | Blank              | <0.33  | mg/kg |            |
|             | Benzo(a)pyrene         | Blank              | <0.67  | mg/kg |            |
|             | Benzo(b)fluoranthene   | Blank              | <0.33  | mg/kg |            |
|             | Benzo(g,h,i)perylene   | Blank              | <1.00  | mg/kg |            |
|             | Benzoic Acid           | Blank              | <1.00  | mg/kg |            |
|             | Benzyl Alcohol         | Blank              | <0.67  | mg/kg |            |
|             | Bis(2-chloroethyl)et   | Blank              | <0.33  | mg/kg |            |
|             | Bis(2-chloroethoxy)m   | Blank              | <0.33  | mg/kg |            |
|             | Bis(2-chloroisopropyl) | Blank              | <0.33  | mg/kg |            |
|             | Bis(2-ethylhexyl)pht   | Blank              | <0.33  | mg/kg |            |
|             | 4-Bromophenylphenyle   | Blank              | <0.33  | mg/kg |            |
|             | Butylbenzylphthalate   | Blank              | <0.67  | mg/kg |            |
|             | 4-Chloroaniline        | Blank              | <0.67  | mg/kg |            |
|             | 2-Chloronaphthalene    | Blank              | <0.33  | mg/kg |            |
|             | 4-Chlorophenylphenyl   | Blank              | <0.33  | mg/kg |            |
|             | Chrysene               | Blank              | <0.67  | mg/kg |            |
|             | Dibenz(a,h)anthracene  | Blank              | <0.67  | mg/kg |            |
|             | Dibenzofuran           | Blank              | <0.33  | mg/kg |            |
|             | 3,3'-Dichlorobenzidi   | Blank              | <0.67  | mg/kg |            |
|             | Diethylphthalate       | Blank              | <0.33  | mg/kg |            |
|             | Dimethylphthalate      | Blank              | <0.67  | mg/kg |            |
|             | Di-n-butylphthalate    | Blank              | <0.33  | mg/kg |            |
|             | 2,4-Dinitrotoluene     | Blank              | <0.33  | mg/kg |            |
|             | 2,6-Dinitrotoluene     | Blank              | <0.33  | mg/kg |            |

## QC SUMMARY REPORT

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/28/97

Lims Bat #: LIMS-29603

Page 4 of 7

QC Batch Number: GCMS/SEMI-0731

| Sample Id | Analysis             | QC Analysis | Values | Units | Limits |
|-----------|----------------------|-------------|--------|-------|--------|
| -----     | -----                | -----       | -----  | ----- | -----  |
|           | 1,2-Diphenylhydrazin | Blank       | <0.33  | mg/kg |        |
|           | Di-n-octylphthalate  | Blank       | <0.67  | mg/kg |        |
|           | Fluoranthene         | Blank       | <0.33  | mg/kg |        |
|           | Fluorene             | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorobenzene    | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorobutadiene  | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorocyclopenta | Blank       | <0.33  | mg/kg |        |
|           | Hexachloroethane     | Blank       | <0.33  | mg/kg |        |
|           | Indeno(1,2,3-cd)pyre | Blank       | <0.33  | mg/kg |        |
|           | Isophorone           | Blank       | <0.33  | mg/kg |        |
|           | 2-Methylnaphthalene  | Blank       | <0.33  | mg/kg |        |
|           | 2-Nitroaniline       | Blank       | <0.33  | mg/kg |        |
|           | 3-Nitroaniline       | Blank       | <0.33  | mg/kg |        |
|           | Nitrobenzene         | Blank       | <0.33  | mg/kg |        |
|           | N-Nitrosodimethylami | Blank       | <0.33  | mg/kg |        |
|           | N-Nitroso-di-n-propy | Blank       | <0.33  | mg/kg |        |
|           | N-Nitrosodiphenylami | Blank       | <0.33  | mg/kg |        |
|           | Phenanthrene         | Blank       | <0.33  | mg/kg |        |
|           | Pyrene               | Blank       | <1.00  | mg/kg |        |
|           | 1,2,4-Trichlorobenze | Blank       | <0.33  | mg/kg |        |
|           | 4-Chloro-3-methylphe | Blank       | <0.67  | mg/kg |        |
|           | 2-Chlorophenol       | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dichlorophenol   | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dimethylphenol   | Blank       | <1.33  | mg/kg |        |
|           | 4,6-Dinitro-2-methyl | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dinitrophenol    | Blank       | <0.33  | mg/kg |        |
|           | 2-Methylphenol (o-cr | Blank       | <0.33  | mg/kg |        |
|           | 3- & 4-Methylphenol  | Blank       | <0.33  | mg/kg |        |
|           | 2-Nitrophenol        | Blank       | <0.33  | mg/kg |        |
|           | 4-Nitrophenol        | Blank       | <0.33  | mg/kg |        |
|           | Phenol               | Blank       | <0.33  | mg/kg |        |
|           | 2,4,5-Trichloropheno | Blank       | <0.33  | mg/kg |        |
|           | 2,4,6-Trichloropheno | Blank       | <0.33  | mg/kg |        |
|           | Pentachlorophenol    | Blank       | <0.33  | mg/kg |        |
|           | Pyridine             | Blank       | <0.33  | mg/kg |        |
|           | Benzo(k)fluoranthene | Blank       | <0.67  | mg/kg |        |
|           | 4-Nitroaniline       | Blank       | <0.33  | mg/kg |        |

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/28/97

Lims Bat #: LIMS-29603

Page 5 of 7

QC Batch Number: HG-0491

| Sample Id     | Analysis | QC Analysis          | Values  | Units         | Limits |
|---------------|----------|----------------------|---------|---------------|--------|
| -----         | -----    | -----                | -----   | -----         | -----  |
| 97B08803      | Mercury  | Sample Amount        | 0.310   | mg/kg         |        |
|               |          | Duplicate Value      | 0.329   | mg/kg         |        |
|               |          | Duplicate RPD        | 5.961   | %             |        |
| LFBLANK-03934 | Mercury  | Lab Fort Blank Amt.  | 0.200   | mg/kg         |        |
|               |          | Lab Fort Blk. Found  | 0.230   | mg/kg         |        |
|               |          | Lab Fort Blk. % Rec. | 115.000 | %             |        |
|               |          | Dup Lab Fort Bl Amt. | 0.200   | mg/kg         |        |
|               |          | Dup Lab Fort Bl. Fnd | 0.230   | mg/kg         |        |
|               |          | Dup Lab Fort Bl %Rec | 115.000 | %             |        |
|               |          | Lab Fort Blank Range | 0.000   | units         |        |
|               |          | Lab Fort Bl. Av. Rec | 115.000 | %             |        |
|               | Mercury  | Lab Fort Blank Amt.  | 0.200   | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. Found  | 0.230   | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. % Rec. | 115.000 | %             |        |
|               |          | Dup Lab Fort Bl Amt. | 0.200   | mg/kg dry wt. |        |
|               |          | Dup Lab Fort Bl. Fnd | 0.230   | mg/kg dry wt. |        |
|               |          | Dup Lab Fort Bl %Rec | 115.000 | %             |        |
|               |          | Lab Fort Blank Range | 0.000   | units         |        |
|               |          | Lab Fort Bl. Av. Rec | 115.000 | %             |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/28/97

Lims Bat #: LIMS-29603

Page 6 of 7

QC Batch Number: ICP-1808

| Sample Id     | Analysis  | QC Analysis          | Values | Units | Limits |
|---------------|-----------|----------------------|--------|-------|--------|
| -----         | -----     | -----                | -----  | ----- | -----  |
| LFBLANK-03948 | Silver    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 68.20  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 68.20  | %     |        |
|               | Arsenic   | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 82.90  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 82.90  | %     |        |
|               | Barium    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 93.34  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 93.34  | %     |        |
|               | Beryllium | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.65  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.65  | %     |        |
|               | Cadmium   | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 83.45  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 83.45  | %     |        |
|               | Chromium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.75  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.75  | %     |        |
|               | Copper    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 88.00  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 88.00  | %     |        |
|               | Nickel    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.48  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.48  | %     |        |
|               | Lead      | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 86.70  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 86.70  | %     |        |
|               | Antimony  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 76.65  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 76.65  | %     |        |
|               | Selenium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 83.15  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 83.15  | %     |        |
|               | Thallium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 83.75  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 83.75  | %     |        |
|               | Zinc      | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 81.66  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 81.66  | %     |        |

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/28/97

Lims Bat #: LIMS-29603

Page 7 of 7

QC Batch Number: ICP-1808

| Sample Id     | Analysis  | QC Analysis          | Values | Units | Limits |
|---------------|-----------|----------------------|--------|-------|--------|
| -----         | -----     | -----                | -----  | ----- | -----  |
| LFBLANK-03949 | Silver    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 72.90  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 72.90  | %     |        |
|               | Arsenic   | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 83.80  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 83.80  | %     |        |
|               | Barium    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 92.18  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 92.18  | %     |        |
|               | Beryllium | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.25  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.25  | %     |        |
|               | Cadmium   | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 84.35  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 84.35  | %     |        |
|               | Chromium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.80  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.80  | %     |        |
|               | Copper    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 88.04  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 88.04  | %     |        |
|               | Nickel    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 88.28  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 88.28  | %     |        |
|               | Lead      | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.10  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.10  | %     |        |
|               | Antimony  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 75.20  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 75.20  | %     |        |
|               | Selenium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 86.15  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 86.15  | %     |        |
|               | Thallium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 84.80  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 84.80  | %     |        |
|               | Zinc      | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 82.62  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 82.62  | %     |        |

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

[illegible]



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

REPORT DATE: 05/29/97

PURCHASE ORDER NUMBER: 40163  
PROJECT NUMBER: 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29602  
JOB NUMBER: 29602

The results of analyses performed on the following samples submitted to the CON-TEST Analytical Laboratory are found in this report

PROJECT LOCATION: MIDDLETOWN, CT

| FIELD SAMPLE # | LAB ID   | MATRIX | SAMPLE DESCRIPTION | TEST          |
|----------------|----------|--------|--------------------|---------------|
| QUON-1         | 97808801 | SOIL   | FLOOR DRAIN        | pcb - soil    |
| QUON-1         | 97808801 | SOIL   | FLOOR DRAIN        | tph (mg/kg)   |
| TRAN-1         | 97808795 | SOIL   | TRANSFORMER        | pcb - soil    |
| TRAN-2         | 97808796 | SOIL   | TRANSFORMER        | pcb - soil    |
| TRAN-3         | 97808797 | SOIL   | TRANSFORMER        | pcb - soil    |
| TRAN-4         | 97808798 | SOIL   | TRANSFORMER        | pcb - soil    |
| TRAN-5         | 97808799 | SOIL   | TRANSFORMER        | pcb - soil    |
| UST4-8'        | 97808800 | SOIL   | UST #4             | 8020 - solid  |
| UST4-8'        | 97808800 | SOIL   | UST #4             | pb (mg/kg) aa |
| UST4-8'        | 97808800 | SOIL   | UST #4             | tph (mg/kg)   |

| FIELD SAMPLE # | LAB ID   | MATRIX | SAMPLE DESCRIPTION | TEST            | SUBCONTRACTOR LABORATORY |
|----------------|----------|--------|--------------------|-----------------|--------------------------|
| QUON-1         | 97808802 | SOIL   | FLOOR DRAIN        | herbicides-soil | SUBCONTRACTED            |

The CON-TEST Environmental Laboratory operates under the following certifications and accreditations:

|                             |                              |
|-----------------------------|------------------------------|
| AIHA 308                    | AIHA ELLAP (LEAD) 6838       |
| MASSACHUSETTS MA100         | MAINE (POTABLE/NON-POTABLE)  |
| CONNECTICUT PH-0567         | VERMONT DOH (LEAD) No. 15036 |
| NEW YORK ELAP 10899         | RHODE ISLAND (LIC. No. 112)  |
| OHIO (ENVIRO. LEAD) # 10005 |                              |
| NEW HAMPSHIRE 2516          |                              |

I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document.

*Edward Denson* 5/30/97

SIGNATURE

DATE

Tod Kopyscinski  
Director of Operations

Edward Denson  
Technical Director

39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332

MARC RICHARDS

05/29/97

VANASSE HANGEN BRUSTLIN, INC.

page 1 of 7

101 WALNUT STREET

WATERTOWN, MA 02272

Purchase Order Number: 40163

Project Number: 40163

Project Location: MIDDLETOWN, CT

Date Received: 05/15/97

LIMS-BAT #: LIMS-29602

Job Number: 29602

Sample Matrix: SOIL

Sampled: 05/15/97

UST #4

UST4-8'

|                                | Units | 97808800 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Benzene                        | ug/kg | 89.1     | 05/21/97         | MFF     | 20.0 |               |     |
| Chlorobenzene                  | ug/kg | ND       | 05/21/97         | MFF     | 50.0 |               |     |
| 1,2-Dichlorobenzene            | ug/kg | 159      | 05/21/97         | MFF     | 50.0 |               |     |
| 1,3-Dichlorobenzene            | ug/kg | ND       | 05/21/97         | MFF     | 50.0 |               |     |
| 1,4-Dichlorobenzene            | ug/kg | ND       | 05/21/97         | MFF     | 50.0 |               |     |
| Ethyl Benzene                  | ug/kg | 3590     | 05/21/97         | MFF     | 50.0 |               |     |
| Methyl tert-Butyl Ether (MTBE) | ug/kg | ND       | 05/21/97         | MFF     | 50.0 |               |     |
| Toluene                        | ug/kg | 349      | 05/21/97         | MFF     | 50.0 |               |     |
| p&m-Xylene                     | ug/kg | ND       | 05/21/97         | MFF     | 100  |               |     |
| o-Xylene                       | ug/kg | 3530     | 05/21/97         | MFF     | 50.0 |               |     |

Analytical Method(s):

SW846 8020

 CONCENTRATION BY PURGE AND TRAP FOLLOWED BY GAS CHROMATOGRAPHY ANALYSIS  
 WITH PHOTOIONIZATION DETECTION.

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.



05/29/97

page 2 of 7

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29602

Job Number: 29602

Sample Matrix: SOIL

Sampled: 05/15/97

FLOOR DRAIN

QUON-1

|          | Units | 97808802 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------|-------|----------|------------------|---------|------|---------------|-----|
| -----    | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 2,4-D    | mg/kg | ND       | 05/20/97         | SW      | 0.10 |               |     |
| 2,4,5-TP | mg/kg | ND       | 05/20/97         | SW      | 0.02 |               |     |

Analytical Method(s):

SW846 8150

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163  
 Project Number: 40163

LIMS-BAT #: LIMS-29602  
 Job Number: 29602  
 Sample Matrix: SOIL

Sampled: 05/15/97  
 UST #4  
 UST4-8'

|       | Units | 97B08800 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-------|-------|----------|------------------|---------|------|---------------|-----|
| ----- | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| LEAD  | MG/KG | 5.48     | 05/22/97         | APP     | 2.49 | 1000          | P   |

Analytical Method(s):

SW846 3050/7420

SAMPLES ARE DIGESTED IN NITRIC ACID AND ANALYZED BY FLAME ATOMIC  
 ABSORPTION SPECTROPHOTOMETRY.

MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29602

Job Number: 29602

Sample Matrix: SOIL

Sampled: 05/15/97

FLOOR DRAIN

QUON-1

|               | Units | 97808801 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| PCB 1221      | mg/kg | ND       | 05/29/97         | JB      |       |               |     |
| PCB 1232      | mg/kg | ND       | 05/29/97         | JB      |       |               |     |
| PCB 1242/1016 | mg/kg | ND       | 05/29/97         | JB      |       |               |     |
| PCB 1248      | mg/kg | ND       | 05/29/97         | JB      |       |               |     |
| PCB 1254      | mg/kg | ND       | 05/29/97         | JB      |       |               |     |
| PCB 1260      | mg/kg | 0.383    | 05/29/97         | JB      |       |               |     |
| Total PCB     | mg/kg | 0.383    | 05/29/97         | JB      | 0.025 |               |     |

Sampled: 05/14/97

TRANSFORMER

TRAN-1

|               | Units | 97808795 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| PCB 1221      | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| PCB 1232      | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| PCB 1242/1016 | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| PCB 1248      | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| PCB 1254      | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| PCB 1260      | mg/kg | 0.154    | 05/23/97         | JB      |       |               |     |
| Total PCB     | mg/kg | 0.154    | 05/23/97         | JB      | 0.024 |               |     |

Sampled: 05/14/97

TRANSFORMER

TRAN-2

|          | Units | 97808796 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|----------|-------|----------|------------------|---------|-----|---------------|-----|
| -----    | ----- | -----    | -----            | -----   | --- | -----         | --- |
| PCB 1221 | mg/kg | ND       | 05/23/97         | JB      |     |               |     |
| PCB 1232 | mg/kg | ND       | 05/23/97         | JB      |     |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163  
 Project Number: 40163

LIMS-BAT #: LIMS-29602  
 Job Number: 29602  
 Sample Matrix: SOIL

Sampled: 05/14/97  
 TRANSFORMER  
 TRAN-2

|               | Units | 97808796 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|---------------|-------|----------|---------------|---------|-------|------------|-----|
| PCB 1242/1016 | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1248      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1254      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1260      | mg/kg | 1.02     | 05/23/97      | JB      |       |            |     |
| Total PCB     | mg/kg | 1.02     | 05/23/97      | JB      | 0.024 |            |     |

Sampled: 05/14/97  
 TRANSFORMER  
 TRAN-3

|               | Units | 97808797 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|---------------|-------|----------|---------------|---------|-------|------------|-----|
| PCB 1221      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1232      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1242/1016 | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1248      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1254      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1260      | mg/kg | 0.762    | 05/23/97      | JB      |       |            |     |
| Total PCB     | mg/kg | 0.762    | 05/23/97      | JB      | 0.025 |            |     |

Sampled: 05/14/97  
 TRANSFORMER  
 TRAN-4

|               | Units | 97808798 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|---------------|-------|----------|---------------|---------|-----|------------|-----|
| PCB 1221      | mg/kg | ND       | 05/23/97      | JB      |     |            |     |
| PCB 1232      | mg/kg | ND       | 05/23/97      | JB      |     |            |     |
| PCB 1242/1016 | mg/kg | ND       | 05/23/97      | JB      |     |            |     |
| PCB 1248      | mg/kg | ND       | 05/23/97      | JB      |     |            |     |

MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29602

Job Number: 29602

Sample Matrix: SOIL

Sampled: 05/14/97

TRANSFORMER

TRAN-4

|           | Units | 97B08798 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|-------|------------|-----|
| -----     | ----- | -----    | -----         | -----   | ---   | -----      | --- |
| PCB 1254  | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1260  | mg/kg | 1.68     | 05/23/97      | JB      |       |            |     |
| Total PCB | mg/kg | 1.68     | 05/23/97      | JB      | 0.472 |            |     |

Sampled: 05/14/97

TRANSFORMER

TRAN-5

|               | Units | 97B08799 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|---------------|-------|----------|---------------|---------|-------|------------|-----|
| -----         | ----- | -----    | -----         | -----   | ---   | -----      | --- |
| PCB 1221      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1232      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1242/1016 | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1248      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1254      | mg/kg | ND       | 05/23/97      | JB      |       |            |     |
| PCB 1260      | mg/kg | 0.609    | 05/23/97      | JB      |       |            |     |
| Total PCB     | mg/kg | 0.609    | 05/23/97      | JB      | 0.025 |            |     |

Analytical Method(s):

SW846 8080

 SAMPLES ARE EXTRACTED INTO HEXANE AND ANALYZED BY GAS CHROMATOGRAPHY  
 WITH ELECTRON CAPTURE DETECTION.

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29602

Job Number: 29602

Sample Matrix: SOIL

Sampled: 05/15/97

FLOOR DRAIN

QUON-1

|                              | Units | 97B08801 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 148      | 05/27/97      | AC      | 20.0 |            |     |

Sampled: 05/15/97

UST #4

UST4-8'

|                              | Units | 97B08800 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 37700    | 05/28/97      | RCL     | 19.8 |            |     |

Analytical Method(s):

MODIFIED EPA 418.1

 INFRA-RED DETERMINATION FOLLOWING EXTRACTION OF HYDROCARBONS INTO  
 1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE (FREON 113)

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

## QC SUMMARY REPORT

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/29/97

Lims Bat #: LIMS-29602

Page 1 of 4

QC Batch Number: FLM/AA-1164

| Sample Id     | Analysis | QC Analysis          | Values | Units         | Limits |
|---------------|----------|----------------------|--------|---------------|--------|
| -----         | -----    | -----                | -----  | -----         | -----  |
| LFBLANK-03935 | LEAD     | Lab Fort Blank Amt.  | 99.42  | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. Found  | 105.39 | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. % Rec. | 106.00 | %             |        |
|               | LEAD     | Lab Fort Blank Amt.  | 99.42  | MG/KG         |        |
|               |          | Lab Fort Blk. Found  | 105.39 | MG/KG         |        |
|               |          | Lab Fort Blk. % Rec. | 106.00 | %             |        |
| LFBLANK-03936 | LEAD     | Lab Fort Blank Amt.  | 99.60  | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. Found  | 102.59 | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. % Rec. | 103.00 | %             |        |
|               | LEAD     | Lab Fort Blank Amt.  | 99.60  | MG/KG         |        |
|               |          | Lab Fort Blk. Found  | 102.59 | MG/KG         |        |
|               |          | Lab Fort Blk. % Rec. | 103.00 | %             |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/29/97

Lims Bat #: LIMS-29602

Page 2 of 4

QC Batch Number: GC/ECD-1287

| Sample Id   | Analysis             | QC Analysis          | Values | Units | Limits |
|-------------|----------------------|----------------------|--------|-------|--------|
| -----       | -----                | -----                | -----  | ----- | -----  |
| 97808795    | PCB 1232             | Sample Amount        | 0.000  | mg/kg |        |
|             |                      | Duplicate Value      | 0.000  | mg/kg |        |
|             | PCB 1242/1016        | Sample Amount        | 0.000  | mg/kg |        |
|             |                      | Duplicate Value      | 0.000  | mg/kg |        |
|             | PCB 1254             | Sample Amount        | 0.000  | mg/kg |        |
|             |                      | Duplicate Value      | 0.000  | mg/kg |        |
|             |                      | Sample Amount        | 0.000  | mg/kg |        |
|             |                      | Matrix Spk Amt Added | 38.400 | mg/kg |        |
|             |                      | MS Amt Measured      | 35.775 | mg/kg |        |
|             |                      | Matrix Spike % Rec.  | 93.163 | %     |        |
|             | PCB 1260             | Sample Amount        | 0.154  | mg/kg |        |
|             |                      | Duplicate Value      | 0.153  | mg/kg |        |
|             |                      | Duplicate RPD        | 1.116  | %     |        |
|             | PCB 1248             | Sample Amount        | 0.000  | mg/kg |        |
|             |                      | Duplicate Value      | 0.000  | mg/kg |        |
|             | PCB 1221             | Sample Amount        | 0.000  | mg/kg |        |
|             |                      | Duplicate Value      | 0.000  | mg/kg |        |
|             | Total PCB            | Sample Amount        | 0.154  | mg/kg |        |
|             |                      | Duplicate Value      | 0.153  | mg/kg |        |
|             |                      | Duplicate RPD        | 1.116  | %     |        |
|             |                      | Sample Amount        | 0.154  | mg/kg |        |
|             |                      | Matrix Spk Amt Added | 38.400 | mg/kg |        |
|             |                      | MS Amt Measured      | 35.775 | mg/kg |        |
|             |                      | Matrix Spike % Rec.  | 92.761 | %     |        |
|             |                      | Sample Amount        | 44.5   | %     |        |
|             | Dibutylchlorendate ( | Duplicate Value      | 54.0   | %     |        |
|             |                      | Duplicate RPD        | 19.3   | %     |        |
| BLANK-07902 | PCB 1232             | Blank                | 0.000  | mg/kg |        |
|             | PCB 1242/1016        | Blank                | 0.000  | mg/kg |        |
|             | PCB 1254             | Blank                | 0.000  | mg/kg |        |
|             | PCB 1260             | Blank                | 0.000  | mg/kg |        |
|             | PCB 1248             | Blank                | 0.000  | mg/kg |        |
|             | PCB 1221             | Blank                | 0.000  | mg/kg |        |
|             | Total PCB            | Blank                | <0.025 | mg/kg |        |
|             | Dibutylchlorendate ( | Blank                | 106.5  | %     |        |



SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike DuplicatesBATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/29/97

Lims Bat #: LIMS-29602

Page 3 of 4

QC Batch Number: GC/PID-1629

| Sample Id   | Analysis             | QC Analysis         | Values | Units | Limits     |
|-------------|----------------------|---------------------|--------|-------|------------|
| -----       | -----                | -----               | -----  | ----- | -----      |
| 97808800    | 1-Cl-2-Fluorobenzene | Sur. Recovery (PID) | 153.6  | %     | 70.2-130.0 |
| BLANK-07894 | Benzene              | Blank               | <1.0   | ug/kg |            |
|             | 1,4-Dichlorobenzene  | Blank               | <2.5   | ug/kg |            |
|             | Ethyl Benzene        | Blank               | <2.5   | ug/kg |            |
|             | Toluene              | Blank               | <2.5   | ug/kg |            |
|             | o-Xylene             | Blank               | <2.5   | ug/kg |            |
|             | p&m-Xylene           | Blank               | <5.0   | ug/kg |            |
|             | 1,2-Dichlorobenzene  | Blank               | <2.5   | ug/kg |            |
|             | 1,3-Dichlorobenzene  | Blank               | <2.5   | ug/kg |            |
|             | Methyl tert-Butyl Et | Blank               | <2.5   | ug/kg |            |
|             | Chlorobenzene        | Blank               | <2.5   | ug/kg |            |

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/29/97

Lims Bat #: LIMS-29602

Page 4 of 4

NOTES:

QC Batch No.: GC/PID-1629

Sample ID: 97808800

Analysis: 1-Cl-2-Fluorobenzene

QC Analysis: Sur. Recovery (PID)

SURROGATE RECOVERY OUTSIDE OF CONTROL LIMITS DUE TO SAMPLE MATRIX  
INTERFERENCE.



(413) 525-2332  
FAX (413) 525-6405

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

Client Name: Vanesse Hogen Brustlin  
Attn: Marie Richards  
Address: 101 Walnut St.  
Uxbridge, MA 01569  
Site Location: Uxbridge Town CT  
Sampled By: Marie Richards  
Call Results: Yes ☐ No ☒  
Fax Results: Yes ☒ No ☐

Telephone: 617-924-1770  
Batch #: 29102  
Project #: 40163  
Client P.O. #: 40163  
Fax #: 617-923-2336

| Field Sample I.D. | Sample Description | Lab #    | DATE SAMPLED    |                | Composite | Grab | MATRIX      |              |           |      |     | Preservative (Use Code) | Container (Use Code) | Analysis Required |           |          |                 |                |
|-------------------|--------------------|----------|-----------------|----------------|-----------|------|-------------|--------------|-----------|------|-----|-------------------------|----------------------|-------------------|-----------|----------|-----------------|----------------|
|                   |                    |          | Start Date/Time | Stop Date/Time |           |      | WASTE WATER | GROUND WATER | DKG WATER | Soil | Air | Other                   |                      |                   |           |          |                 |                |
| Tren-1            | Transformer        | 07308795 | 5/14            | 5/14           | X         |      |             |              |           | X    |     |                         | A                    | X                 | TPH 418.1 | VOC 8020 | Total Lead 7421 | Hexachlor 8150 |
| Tren-2            |                    | 08796    | 5/14            | 5/14           | X         |      |             |              |           | X    |     |                         | A                    | X                 |           |          |                 |                |
| Tren-3            |                    | 08797    | 5/14            | 5/14           | X         |      |             |              |           | X    |     |                         | A                    | X                 |           |          |                 |                |
| Tren-4            |                    | 08798    | 5/14            | 5/14           | X         |      |             |              |           | X    |     |                         | A                    | X                 |           |          |                 |                |
| Tren-5            |                    | 08799    | 5/14            | 5/14           | X         |      |             |              |           | X    |     |                         | A                    | X                 |           |          |                 |                |
| USTA-8            | WST # A            | 08800    | 5/15            | 5/15           | X         |      |             |              |           | X    |     |                         | 2G                   | X                 | X         | X        |                 |                |
| Quon-1            | Floor Drain        | 08801    | 5/15            | 5/15           | X         |      |             |              |           | X    |     |                         | G                    | X                 | X         |          |                 |                |
| +                 | +                  | 08802    | 5/15            | 5/15           | 1         |      |             |              |           | X    |     |                         |                      |                   |           |          |                 |                |

### CONTAINER CODE

P: PLASTIC (\_\_\_ Size) V = 40 ml vial G = Glass (\_\_\_ size) A = 1000 ml Amber 0 = Other

### PRESERVATIVE CODE:

I = ICED N = HNO<sub>3</sub> H = HCl S = NaOH T = Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub> O = OTHER

|                                                       |                             |                                                  |                                                                      |
|-------------------------------------------------------|-----------------------------|--------------------------------------------------|----------------------------------------------------------------------|
| Relinquished by: (Signature)<br><u>Marie Richards</u> | Date Time<br><u>5-15-97</u> | Received by: (Signature)<br><u>W. Phibbs</u>     | Turnaround Requested: _____ 24-Hour _____ 48-Hour _____ Normal _____ |
| Relinquished by: (Signature)<br><u>W. Phibbs</u>      | Date Time<br><u>5-15-97</u> | Received by: (Signature)<br><u>Edward Benson</u> | Date Required _____                                                  |
| Relinquished by: (Signature)<br><u>W. Phibbs</u>      | Date Time<br><u>5-15-97</u> | Received by: (Signature)<br><u>W. Phibbs</u>     | Remarks/Comments: <u>logged in by WMS</u>                            |
| Relinquished by: (Signature)<br><u>W. Phibbs</u>      | Date Time<br><u>5-15-97</u> | Received by: (Signature)<br><u>W. Phibbs</u>     | *MATRIX OTHER _____                                                  |

VANASSE HANGEN BRUSTLIN, INC.  
 101 WALNUT STREET  
 WATERTOWN, MA 02272  
 ATTN: MARC RICHARDS

REPORT DATE: 05/30/97

PURCHASE ORDER NUMBER: 40163

PROJECT NUMBER: 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29639

JOB NUMBER: 29639

The results of analyses performed on the following samples submitted to the CON-TEST Analytical Laboratory are found in this report

PROJECT LOCATION: MIDDLETOWN, CT.

| FIELD SAMPLE # | LAB ID   | MATRIX | SAMPLE DESCRIPTION | TEST             |
|----------------|----------|--------|--------------------|------------------|
| RCW/TP01/0-2'  | 97B09020 | SOIL   | R.O.W.             | 8270-soil bn-2   |
| RCW/TP01/0-2'  | 97B09020 | SOIL   | R.O.W.             | 8270-soil bn1    |
| RCW/TP01/0-2'  | 97B09020 | SOIL   | R.O.W.             | 8270-soil-acid   |
| RCW/TP01/0-2'  | 97B09020 | SOIL   | R.O.W.             | metals(13pp)socp |
| RCW/TP03/0-2'  | 97B09021 | SOIL   | R.O.W.             | cyanide-tot sold |
| RCW/TP06/3-4'  | 97B09022 | SOIL   | R.O.W.             | 8270-soil bn-2   |
| RCW/TP06/3-4'  | 97B09022 | SOIL   | R.O.W.             | 8270-soil bn1    |
| RCW/TP06/3-4'  | 97B09022 | SOIL   | R.O.W.             | 8270-soil-acid   |
| RCW/TP06/3-4'  | 97B09022 | SOIL   | R.O.W.             | metals(13pp)socp |
| RCW/TP07/2-3'  | 97B09023 | SOIL   | R.O.W.             | 8270-soil bn-2   |
| RCW/TP07/2-3'  | 97B09023 | SOIL   | R.O.W.             | 8270-soil bn1    |
| RCW/TP07/2-3'  | 97B09023 | SOIL   | R.O.W.             | 8270-soil-acid   |
| RCW/TP07/2-3'  | 97B09023 | SOIL   | R.O.W.             | metals(13pp)socp |
| RCW/TP07/2-3'  | 97B09023 | SOIL   | R.O.W.             | tph (mg/kg)      |
| RCW/TP09/6-8'  | 97B09024 | SOIL   | R.O.W.             | 8270-soil bn-2   |
| RCW/TP09/6-8'  | 97B09024 | SOIL   | R.O.W.             | 8270-soil bn1    |
| RCW/TP09/6-8'  | 97B09024 | SOIL   | R.O.W.             | 8270-soil-acid   |
| RCW/TP09/6-8'  | 97B09024 | SOIL   | R.O.W.             | tph (mg/kg)      |
| RCW/TP09/6-8'  | 97B09025 | SOIL   | R.O.W.             | 8240 - solid (a) |
| RCW/TP09/6-8'  | 97B09025 | SOIL   | R.O.W.             | 8240 - solid (b) |
| RCW/TP10/4-6'  | 97B09026 | SOIL   | R.O.W.             | 8270-soil bn-2   |
| RCW/TP10/4-6'  | 97B09026 | SOIL   | R.O.W.             | 8270-soil bn1    |
| RCW/TP10/4-6'  | 97B09026 | SOIL   | R.O.W.             | 8270-soil-acid   |
| RCW/TP10/4-6'  | 97B09026 | SOIL   | R.O.W.             | metals(13pp)socp |
| RCW/TP10/4-6'  | 97B09026 | SOIL   | R.O.W.             | tph (mg/kg)      |
| RCW/TP10/4-6'  | 97B09027 | SOIL   | R.O.W.             | 8240 - solid (a) |
| RCW/TP10/4-6'  | 97B09027 | SOIL   | R.O.W.             | 8240 - solid (b) |
| RCW/TP11/3-4'  | 97B09028 | SOIL   | R.O.W.             | 8270-soil bn-2   |
| RCW/TP11/3-4'  | 97B09028 | SOIL   | R.O.W.             | 8270-soil bn1    |
| RCW/TP11/3-4'  | 97B09028 | SOIL   | R.O.W.             | 8270-soil-acid   |
| RCW/TP11/3-4'  | 97B09028 | SOIL   | R.O.W.             | tph (mg/kg)      |
| UST 2-6'       | 97B09018 | SOIL   | TEST PST AT UST-2  | pb (mg/kg) aa    |
| UST 2-6'       | 97B09018 | SOIL   | TEST PST AT UST-2  | tph (mg/kg)      |
| UST 2-6'       | 97B09019 | SOIL   | TEST PST AT UST-2  | 8020 - solid     |



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.

REPORT DATE: 05/30/97

101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

PURCHASE ORDER NUMBER: 40163  
PROJECT NUMBER: 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29639  
JOB NUMBER: 29639

| FIELD SAMPLE # | LAB ID | MATRIX | SAMPLE DESCRIPTION | TEST |
|----------------|--------|--------|--------------------|------|
|----------------|--------|--------|--------------------|------|

The CON-TEST Environmental Laboratory operates under the following certifications and accreditations:

|                             |                              |
|-----------------------------|------------------------------|
| AIHA 308                    | AIHA ELLAP (LEAD) 6838       |
| MASSACHUSETTS MA100         | MAINE (POTABLE/NON-POTABLE)  |
| CONNECTICUT PH-0567         | VERMONT DOH (LEAD) No. 15036 |
| NEW YORK ELAP 10899         | RHODE ISLAND (LIC. No. 112)  |
| OHIO (ENVIRO. LEAD) # 10005 |                              |
| NEW HAMPSHIRE 2516          |                              |

I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document.

Edward Denson 6/2/97  
SIGNATURE DATE

Tod Kopyscinski  
Director of Operations

Edward Denson  
Technical Director

MARC RICHARDS  
 VANASSE HANGEN BRUSTLIN, INC.  
 101 WALNUT STREET  
 WATERTOWN, MA 02272

Purchase Order Number: 40163  
 Project Number: 40163

05/30/97  
 page 1 of 32

Project Location: MIDDLETOWN, CT.  
 Date Received: 05/16/97

LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

Sampled: 05/16/97  
 TEST PST AT UST-2  
 UST 2-6'

|                                | Units | 97809019 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Benzene                        | ug/kg | ND       | 05/23/97         | HFF     | 40.0 |               |     |
| Chlorobenzene                  | ug/kg | ND       | 05/23/97         | HFF     | 100  |               |     |
| 1,2-Dichlorobenzene            | ug/kg | ND       | 05/23/97         | HFF     | 100  |               |     |
| 1,3-Dichlorobenzene            | ug/kg | ND       | 05/23/97         | HFF     | 100  |               |     |
| 1,4-Dichlorobenzene            | ug/kg | ND       | 05/23/97         | HFF     | 100  |               |     |
| Ethyl Benzene                  | ug/kg | 410      | 05/23/97         | HFF     | 100  |               |     |
| Methyl tert-Butyl Ether (MTBE) | ug/kg | ND       | 05/23/97         | HFF     | 100  |               |     |
| Toluene                        | ug/kg | ND       | 05/23/97         | HFF     | 100  |               |     |
| p&m-Xylene                     | ug/kg | ND       | 05/23/97         | HFF     | 200  |               |     |
| o-Xylene                       | ug/kg | 574      | 05/23/97         | HFF     | 100  |               |     |

Analytical Method(s):

SW846 8020

CONCENTRATION BY PURGE AND TRAP FOLLOWED BY GAS CHROMATOGRAPHY ANALYSIS  
 WITH PHOTOIONIZATION DETECTION.

MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97

page 2 of 32

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29639

Job Number: 29639

Sample Matrix: SOIL

Sampled: 05/16/97

R.O.W.

ROW/TP09/6-8'

|                         | Units | 97809025 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-------------------------|-------|----------|---------------|---------|-------|------------|-----|
| Acetone                 | mg/kg | BDL      | 05/29/97      | WSD     | 0.161 |            |     |
| Acrolein                | mg/kg | ND       | 05/29/97      | WSD     | 0.200 |            |     |
| Acrylonitrile           | mg/kg | ND       | 05/29/97      | WSD     | 0.076 |            |     |
| Benzene                 | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| Bromodichloromethane    | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| Bromomethane            | mg/kg | ND       | 05/29/97      | WSD     | 0.012 |            |     |
| Bromoform               | mg/kg | ND       | 05/29/97      | WSD     | 0.012 |            |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/29/97      | WSD     | 0.120 |            |     |
| Carbon Disulfide        | mg/kg | ND       | 05/29/97      | WSD     | 0.005 |            |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/29/97      | WSD     | 0.005 |            |     |
| Chlorobenzene           | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/29/97      | WSD     | 0.005 |            |     |
| Chloroethane            | mg/kg | ND       | 05/29/97      | WSD     | 0.008 |            |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/29/97      | WSD     | 0.096 |            |     |
| Chloroform              | mg/kg | ND       | 05/29/97      | WSD     | 0.008 |            |     |
| Chloromethane           | mg/kg | ND       | 05/29/97      | WSD     | 0.012 |            |     |
| Dibromomethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.011 |            |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.008 |            |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.008 |            |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97      | WSD     | 0.024 |            |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97      | WSD     | 0.021 |            |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/29/97      | WSD     | 0.010 |            |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.007 |            |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.009 |            |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/29/97      | WSD     | 0.008 |            |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/29/97      | WSD     | 0.005 |            |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| Ethyl Benzene           | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/29/97      | WSD     | 0.008 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

05/30/97  
 page 3 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP09/6-8'

|                                | Units | 97809025 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|--------------------------------|-------|----------|---------------|---------|-------|------------|-----|
| -----                          | ----- | -----    | -----         | -----   | ---   | -----      | --- |
| 2-Hexanone                     | mg/kg | ND       | 05/29/97      | WSD     | 0.097 |            |     |
| Iodomethane                    | mg/kg | ND       | 05/29/97      | WSD     | 0.008 |            |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/29/97      | WSD     | 0.008 |            |     |
| Methylene Chloride             | mg/kg | BDL      | 05/29/97      | WSD     | 0.030 |            |     |
| 4-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/29/97      | WSD     | 0.088 |            |     |
| Styrene                        | mg/kg | ND       | 05/29/97      | WSD     | 0.007 |            |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.014 |            |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| Toluene                        | mg/kg | ND       | 05/29/97      | WSD     | 0.007 |            |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.009 |            |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.007 |            |     |
| Trichloroethylene              | mg/kg | ND       | 05/29/97      | WSD     | 0.010 |            |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/29/97      | WSD     | 0.007 |            |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/29/97      | WSD     | 0.013 |            |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/29/97      | WSD     | 0.164 |            |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| m-Xylene                       | mg/kg | ND       | 05/29/97      | WSD     | 0.013 |            |     |
| o&p-Xylene                     | mg/kg | ND       | 05/29/97      | WSD     | 0.005 |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.



05/30/97

page 4 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

Sampled: 05/16/97

R.O.W.

ROW/TP10/4-6'

|                         | Units | 97809027 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                   | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Acetone                 | mg/kg | BDL      | 05/29/97         | WSD     | 8.05  |               |     |
| Acrolein                | mg/kg | ND       | 05/29/97         | WSD     | 10.0  |               |     |
| Acrylonitrile           | mg/kg | ND       | 05/29/97         | WSD     | 3.80  |               |     |
| Benzene                 | mg/kg | ND       | 05/29/97         | WSD     | 0.300 |               |     |
| Bromodichloromethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.200 |               |     |
| Bromomethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.600 |               |     |
| Bromoform               | mg/kg | ND       | 05/29/97         | WSD     | 0.600 |               |     |
| 2-Butanone (MEK)        | mg/kg | BDL      | 05/29/97         | WSD     | 6.00  |               |     |
| Carbon Disulfide        | mg/kg | ND       | 05/29/97         | WSD     | 0.250 |               |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/29/97         | WSD     | 0.250 |               |     |
| Chlorobenzene           | mg/kg | ND       | 05/29/97         | WSD     | 0.300 |               |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.250 |               |     |
| Chloroethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.400 |               |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/29/97         | WSD     | 4.80  |               |     |
| Chloroform              | mg/kg | ND       | 05/29/97         | WSD     | 0.400 |               |     |
| Chloromethane           | mg/kg | ND       | 05/29/97         | WSD     | 0.600 |               |     |
| Dibromomethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.550 |               |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.400 |               |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.300 |               |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.400 |               |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 1.20  |               |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 1.05  |               |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/29/97         | WSD     | 0.500 |               |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.350 |               |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.450 |               |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/29/97         | WSD     | 0.300 |               |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/29/97         | WSD     | 0.400 |               |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/29/97         | WSD     | 0.300 |               |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/29/97         | WSD     | 0.250 |               |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/29/97         | WSD     | 0.200 |               |     |
| Ethyl Benzene           | mg/kg | 0.550    | 05/29/97         | WSD     | 0.300 |               |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/29/97         | WSD     | 0.400 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97  
page 5 of 32

Purchase Order Number: 40163  
Project Number: 40163

LIMS-BAT #: LIMS-29639  
Job Number: 29639  
Sample Matrix: SOIL

Sampled: 05/16/97  
R.O.W.  
ROW/TP10/4-6'

|                                | Units | 97809027 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|--------------------------------|-------|----------|---------------|---------|-------|------------|-----|
| -----                          | ----- | -----    | -----         | -----   | ---   | -----      | --- |
| 2-Hexanone                     | mg/kg | 20.1     | 05/29/97      | WSD     | 4.85  |            |     |
| Iodomethane                    | mg/kg | ND       | 05/29/97      | WSD     | 0.400 |            |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/29/97      | WSD     | 0.400 |            |     |
| Methylene Chloride             | mg/kg | BDL      | 05/29/97      | WSD     | 1.50  |            |     |
| 4-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/29/97      | WSD     | 4.40  |            |     |
| Styrene                        | mg/kg | ND       | 05/29/97      | WSD     | 0.350 |            |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.700 |            |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/29/97      | WSD     | 0.200 |            |     |
| Toluene                        | mg/kg | BDL      | 05/29/97      | WSD     | 0.350 |            |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.450 |            |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.350 |            |     |
| Trichloroethylene              | mg/kg | ND       | 05/29/97      | WSD     | 0.500 |            |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/29/97      | WSD     | 0.350 |            |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/29/97      | WSD     | 0.650 |            |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/29/97      | WSD     | 8.20  |            |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/29/97      | WSD     | 0.150 |            |     |
| m-Xylene                       | mg/kg | 1.35     | 05/29/97      | WSD     | 0.650 |            |     |
| o&p-Xylene                     | mg/kg | 2.15     | 05/29/97      | WSD     | 0.250 |            |     |

## Analytical Method(s):

SW846 8240

SAMPLES ARE CONCENTRATED BY PURGE AND TRAP, FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

05/30/97  
 page 6 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP01/0-2'

|                             | Units | 97809020 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| Acenaphthene                | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Acenaphthylene              | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Aniline                     | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Anthracene                  | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Benzidene                   | mg/kg | ND       | 05/22/97      | WSD     | 2.33 |            |     |
| Benzoic Acid                | mg/kg | ND       | 05/22/97      | WSD     | 1.00 |            |     |
| Benzo(a)anthracene          | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Benzo(a)pyrene              | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Benzo(b)fluoranthene        | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/22/97      | WSD     | 1.00 |            |     |
| Benzo(k)fluoranthene        | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | BDL      | 05/22/97      | WSD     | 0.33 |            |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Butylbenzylphthalate        | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Chrysene                    | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Dibenzofuran                | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Diethylphthalate            | mg/kg | BDL      | 05/22/97      | WSD     | 0.33 |            |     |
| Dimethylphthalate           | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Di-n-butylphthalate         | mg/kg | BDL      | 05/22/97      | WSD     | 0.33 |            |     |
| Di-n-octylphthalate         | mg/kg | BDL      | 05/22/97      | WSD     | 0.67 |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97

page 7 of 32

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29639

Job Number: 29639

Sample Matrix: SOIL

Sampled: 05/16/97

R.O.W.

ROW/TP01/0-2'

|                            | Units | 97B09020 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                      | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Fluoranthene               | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Fluorene                   | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Hexachloroethane           | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Isophorone                 | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2-Methylnaphthalene        | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Naphthalene                | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Nitrobenzene               | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Phenanthrene               | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Pyrene                     | mg/kg | BDL      | 05/22/97         | WSD     | 1.00 |               |     |
| Pyridine                   | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

05/30/97

page 8 of 32

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29639

Job Number: 29639

Sample Matrix: SOIL

Sampled: 05/16/97

R.O.W.

ROW/TP06/3-4'

|                             | Units | 97809022 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| Acenaphthene                | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Acenaphthylene              | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Aniline                     | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Anthracene                  | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Benzidene                   | mg/kg | ND       | 05/22/97      | WSD     | 2.33 |            |     |
| Benzoic Acid                | mg/kg | ND       | 05/22/97      | WSD     | 1.00 |            |     |
| Benzo(a)anthracene          | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Benzo(a)pyrene              | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Benzo(b)fluoranthene        | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/22/97      | WSD     | 1.00 |            |     |
| Benzo(k)fluoranthene        | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | BDL      | 05/22/97      | WSD     | 0.33 |            |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Butylbenzylphthalate        | mg/kg | BDL      | 05/22/97      | WSD     | 0.67 |            |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Chrysene                    | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Dibenzofuran                | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Diethylphthalate            | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Dimethylphthalate           | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| Di-n-butylphthalate         | mg/kg | BDL      | 05/22/97      | WSD     | 0.33 |            |     |
| Di-n-octylphthalate         | mg/kg | BDL      | 05/22/97      | WSD     | 0.67 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

05/30/97

page 11 of 32

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29639

Job Number: 29639

Sample Matrix: SOIL

Sampled: 05/16/97

R.O.W.

ROW/TP07/2-3'

|                            | Units | 97B09023 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                      | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Fluoranthene               | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Fluorene                   | mg/kg | BDL      | 05/22/97         | WSD     | 10.0 |               |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Hexachloroethane           | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Isophorone                 | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| 2-Methylnaphthalene        | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Naphthalene                | mg/kg | BDL      | 05/22/97         | WSD     | 10.0 |               |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Nitrobenzene               | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Phenanthrene               | mg/kg | BDL      | 05/22/97         | WSD     | 10.0 |               |     |
| Pyrene                     | mg/kg | ND       | 05/22/97         | WSD     | 30.0 |               |     |
| Pyridine                   | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

05/30/97  
 page 12 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP09/6-8'

|                             | Units | 97809024 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| Acenaphthene                | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| Acenaphthylene              | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Aniline                     | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Anthracene                  | mg/kg | BDL      | 05/22/97         | WSD     | 3.33 |               |     |
| Benidene                    | mg/kg | ND       | 05/22/97         | WSD     | 23.3 |               |     |
| Benzoic Acid                | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Benzo(a)anthracene          | mg/kg | BDL      | 05/22/97         | WSD     | 3.33 |               |     |
| Benzo(a)pyrene              | mg/kg | ND       | 05/22/97         | WSD     | 6.67 |               |     |
| Benzo(b)fluoranthene        | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Benzo(k)fluoranthene        | mg/kg | ND       | 05/22/97         | WSD     | 6.67 |               |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/22/97         | WSD     | 6.67 |               |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Butylbenzylphthalate        | mg/kg | ND       | 05/22/97         | WSD     | 6.67 |               |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 6.67 |               |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Chrysene                    | mg/kg | BDL      | 05/22/97         | WSD     | 6.67 |               |     |
| Dibenzofuran                | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/22/97         | WSD     | 6.67 |               |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/22/97         | WSD     | 6.67 |               |     |
| Diethylphthalate            | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Dimethylphthalate           | mg/kg | ND       | 05/22/97         | WSD     | 6.67 |               |     |
| Di-n-butylphthalate         | mg/kg | BDL      | 05/22/97         | WSD     | 3.33 |               |     |
| Di-n-octylphthalate         | mg/kg | ND       | 05/22/97         | WSD     | 6.67 |               |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97  
page 13 of 32

Purchase Order Number: 40163  
Project Number: 40163

LIMS-BAT #: LIMS-29639  
Job Number: 29639  
Sample Matrix: SOIL

Sampled: 05/16/97  
R.O.W.  
ROW/TP09/6-8'

|                            | Units | 97809024 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                      | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Fluoranthene               | mg/kg | BDL      | 05/22/97      | WSD     | 3.33 |            |     |
| Fluorene                   | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Isophorone                 | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 2-Methylnaphthalene        | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Naphthalene                | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Phenanthrene               | mg/kg | BDL      | 05/22/97      | WSD     | 3.33 |            |     |
| Pyrene                     | mg/kg | BDL      | 05/22/97      | WSD     | 10.0 |            |     |
| Pyridine                   | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.



05/30/97  
 page 14 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP10/4-6'

|                             | Units | 97809026 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| Acenaphthene                | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Acenaphthylene              | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Aniline                     | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Anthracene                  | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Benzidene                   | mg/kg | ND       | 05/22/97      | WSD     | 23.3 |            |     |
| Benzoic Acid                | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| Benzo(a)anthracene          | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Benzo(a)pyrene              | mg/kg | ND       | 05/22/97      | WSD     | 6.67 |            |     |
| Benzo(b)fluoranthene        | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| Benzo(k)fluoranthene        | mg/kg | ND       | 05/22/97      | WSD     | 6.67 |            |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/22/97      | WSD     | 6.67 |            |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Bis(2-chloroethyl)ether     | mg/kg | BDL      | 05/22/97      | WSD     | 3.33 |            |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | 3.60     | 05/22/97      | WSD     | 3.33 |            |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Butylbenzylphthalate        | mg/kg | BDL      | 05/22/97      | WSD     | 6.67 |            |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/22/97      | WSD     | 6.67 |            |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Chrysene                    | mg/kg | BDL      | 05/22/97      | WSD     | 6.67 |            |     |
| Dibenzofuran                | mg/kg | BDL      | 05/22/97      | WSD     | 3.33 |            |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/22/97      | WSD     | 6.67 |            |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/22/97      | WSD     | 6.67 |            |     |
| Diethylphthalate            | mg/kg | ND       | 05/22/97      | WSD     | 3.33 |            |     |
| Dimethylphthalate           | mg/kg | ND       | 05/22/97      | WSD     | 6.67 |            |     |
| Di-n-butylphthalate         | mg/kg | BDL      | 05/22/97      | WSD     | 3.33 |            |     |
| Di-n-octylphthalate         | mg/kg | ND       | 05/22/97      | WSD     | 6.67 |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97  
 page 15 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP10/4-6'

|                            | Units | 97B09026 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                      | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Fluoranthene               | mg/kg | BDL      | 05/22/97         | WSD     | 3.33 |               |     |
| Fluorene                   | mg/kg | BDL      | 05/22/97         | WSD     | 3.33 |               |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Hexachloroethane           | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Isophorone                 | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 2-Methylnaphthalene        | mg/kg | BDL      | 05/22/97         | WSD     | 3.33 |               |     |
| Naphthalene                | mg/kg | BDL      | 05/22/97         | WSD     | 3.33 |               |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Nitrobenzene               | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Phenanthrene               | mg/kg | BDL      | 05/22/97         | WSD     | 3.33 |               |     |
| Pyrene                     | mg/kg | ND       | 05/22/97         | WSD     | 10.0 |               |     |
| Pyridine                   | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97  
 page 16 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP11/3-4'

|                             | Units | 97B09028 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| Acenaphthene                | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Acenaphthylene              | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Aniline                     | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Anthracene                  | mg/kg | BDL      | 05/22/97         | WSD     | 0.33 |               |     |
| Benidene                    | mg/kg | ND       | 05/22/97         | WSD     | 2.33 |               |     |
| Benzoic Acid                | mg/kg | ND       | 05/22/97         | WSD     | 1.00 |               |     |
| Benzo(a)anthracene          | mg/kg | BDL      | 05/22/97         | WSD     | 0.33 |               |     |
| Benzo(a)pyrene              | mg/kg | BDL      | 05/22/97         | WSD     | 0.67 |               |     |
| Benzo(b)fluoranthene        | mg/kg | BDL      | 05/22/97         | WSD     | 0.33 |               |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/22/97         | WSD     | 1.00 |               |     |
| Benzo(k)fluoranthene        | mg/kg | BDL      | 05/22/97         | WSD     | 0.67 |               |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/22/97         | WSD     | 0.67 |               |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | BDL      | 05/22/97         | WSD     | 0.33 |               |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Butylbenzylphthalate        | mg/kg | BDL      | 05/22/97         | WSD     | 0.67 |               |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/22/97         | WSD     | 0.67 |               |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Chrysene                    | mg/kg | BDL      | 05/22/97         | WSD     | 0.67 |               |     |
| Dibenzofuran                | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/22/97         | WSD     | 0.67 |               |     |
| 1,2-Dichlorobenzene         | mg/kg | BDL      | 05/22/97         | WSD     | 0.33 |               |     |
| 1,3-Dichlorobenzene         | mg/kg | BDL      | 05/22/97         | WSD     | 0.33 |               |     |
| 1,4-Dichlorobenzene         | mg/kg | BDL      | 05/22/97         | WSD     | 0.33 |               |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/22/97         | WSD     | 0.67 |               |     |
| Diethylphthalate            | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Dimethylphthalate           | mg/kg | ND       | 05/22/97         | WSD     | 0.67 |               |     |
| Di-n-butylphthalate         | mg/kg | BDL      | 05/22/97         | WSD     | 0.33 |               |     |
| Di-n-octylphthalate         | mg/kg | BDL      | 05/22/97         | WSD     | 0.67 |               |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97  
page 17 of 32

Purchase Order Number: 40163  
Project Number: 40163

LIMS-BAT #: LIMS-29639  
Job Number: 29639  
Sample Matrix: SOIL

Sampled: 05/16/97  
R.O.W.  
ROW/TP11/3-4'

|                            | Units | 97809028 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                      | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Fluoranthene               | mg/kg | BDL      | 05/22/97      | WSD     | 0.33 |            |     |
| Fluorene                   | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | BDL      | 05/22/97      | WSD     | 0.33 |            |     |
| Isophorone                 | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2-Methylnaphthalene        | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Naphthalene                | mg/kg | BDL      | 05/22/97      | WSD     | 0.33 |            |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Phenanthrene               | mg/kg | BDL      | 05/22/97      | WSD     | 0.33 |            |     |
| Pyrene                     | mg/kg | BDL      | 05/22/97      | WSD     | 1.00 |            |     |
| Pyridine                   | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |

## Analytical Method(s):

SW846 8270

SAMPLES ARE EXTRACTED IN METHYLENE CHLORIDE/ACETONE AND  
FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

05/30/97  
page 18 of 32

Purchase Order Number: 40163  
Project Number: 40163

LIMS-BAT #: LIMS-29639  
Job Number: 29639  
Sample Matrix: SOIL

Sampled: 05/16/97  
R.O.W.  
ROW/TP01/0-2'

|                                  | Units | 97809020 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                            | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/22/97      | WSD     | 1.33 |            |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Pentachlorophenol                | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Phenol                           | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |

Sampled: 05/16/97  
R.O.W.  
ROW/TP06/3-4'

|                                  | Units | 97809022 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                            | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/22/97      | WSD     | 0.67 |            |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/22/97      | WSD     | 1.33 |            |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

05/30/97  
 page 19 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP06/3-4'

|                       | Units | 97809022 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------|-------|----------|---------------|---------|------|------------|-----|
| Pentachlorophenol     | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| Phenol                | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4,5-Trichlorophenol | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |
| 2,4,6-Trichlorophenol | mg/kg | ND       | 05/22/97      | WSD     | 0.33 |            |     |

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP07/2-3'

|                                  | Units | 97809023 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------------|-------|----------|---------------|---------|------|------------|-----|
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/22/97      | WSD     | 20.0 |            |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/22/97      | WSD     | 40.0 |            |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| Pentachlorophenol                | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| Phenol                           | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/22/97      | WSD     | 10.0 |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97  
 page 20 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP09/6-8'

|                                  | Units | 97809024 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/22/97         | WSD     | 6.67 | -----         | --- |
| 2-Chlorophenol                   | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/22/97         | WSD     | 13.3 | -----         | --- |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2-Nitrophenol                    | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 4-Nitrophenol                    | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| Pentachlorophenol                | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| Phenol                           | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP10/4-6'

|                                  | Units | 97809026 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/22/97         | WSD     | 6.67 | -----         | --- |
| 2-Chlorophenol                   | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/22/97         | WSD     | 13.3 | -----         | --- |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 2-Nitrophenol                    | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |
| 4-Nitrophenol                    | mg/kg | ND       | 05/22/97         | WSD     | 3.33 | -----         | --- |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97

page 21 of 32

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29639

Job Number: 29639

Sample Matrix: SOIL

Sampled: 05/16/97

R.O.W.

ROW/TP10/4-6'

|                       | Units | 97809026 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                 | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Pentachlorophenol     | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| Phenol                | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 2,4,5-Trichlorophenol | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |
| 2,4,6-Trichlorophenol | mg/kg | ND       | 05/22/97         | WSD     | 3.33 |               |     |

Sampled: 05/16/97

R.O.W.

ROW/TP11/3-4'

|                                  | Units | 97809028 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/22/97         | WSD     | 0.67 |               |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/22/97         | WSD     | 1.33 |               |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Pentachlorophenol                | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| Phenol                           | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/22/97         | WSD     | 0.33 |               |     |

Analytical Method(s):

SW846 8270

SAMPLES ARE EXTRACTED IN METHYLENE CHLORIDE/ACETONE AND

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.



05/30/97

page 22 of 32

FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

05/30/97  
 page 23 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP03/0-2'

|                 | Units | 97B09021 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------|-------|----------|---------------|---------|------|------------|-----|
| Cyanide - Total | mg/kg | BDL      | 05/30/97      | TAM     | 0.98 |            |     |

Analytical Method(s):

MODIFIED SW846 9012

 DISTILLATION FOLLOWED BY REACTION WITH CHLORAMINE-T/PYRIDINE-BARBITURIC  
 ACID AND PHOSPHATE BUFFER. ANALYSIS BY AUTOMATED FLOW INJECTION  
 SPECTROPHOTOMETRY.

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97  
 page 24 of 32

 Purchase Order Number: 40163  
 Project Number: 40163

 LIMS-BAT #: LIMS-29639  
 Job Number: 29639  
 Sample Matrix: SOIL

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP01/0-2'

|           | Units | 97809020 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|-------|---------------|-----|
| -----     | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Antimony  | mg/kg | ND       | 05/22/97         | KLF     | 2.48  |               |     |
| Arsenic   | mg/kg | ND       | 05/22/97         | KLF     | 4.95  |               |     |
| Beryllium | mg/kg | 0.33     | 05/22/97         | KLF     | 0.10  |               |     |
| Cadmium   | mg/kg | 2.54     | 05/22/97         | KLF     | 0.05  |               |     |
| Chromium  | mg/kg | 36.6     | 05/22/97         | KLF     | 0.35  |               |     |
| Copper    | mg/kg | 180      | 05/22/97         | KLF     | 0.10  |               |     |
| Lead      | mg/kg | 163      | 05/22/97         | KLF     | 2.48  | 1000          | P   |
| Mercury   | mg/kg | 0.082    | 05/23/97         | APP     | 0.020 |               |     |
| Nickel    | mg/kg | 14.4     | 05/22/97         | KLF     | 0.25  |               |     |
| Selenium  | mg/kg | ND       | 05/22/97         | KLF     | 4.95  |               |     |
| Silver    | mg/kg | 34.3     | 05/22/97         | KLF     | 0.50  |               |     |
| Thallium  | mg/kg | ND       | 05/22/97         | KLF     | 9.90  |               |     |
| Zinc      | mg/kg | 905      | 05/22/97         | KLF     | 0.50  |               |     |

 Sampled: 05/16/97  
 R.O.W.  
 ROW/TP06/3-4'

|           | Units | 97809022 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|-------|---------------|-----|
| -----     | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Antimony  | mg/kg | 6.23     | 05/22/97         | KLF     | 2.48  |               |     |
| Arsenic   | mg/kg | 36.1     | 05/22/97         | KLF     | 4.95  |               |     |
| Beryllium | mg/kg | 0.25     | 05/22/97         | KLF     | 0.10  |               |     |
| Cadmium   | mg/kg | 17.1     | 05/22/97         | KLF     | 0.05  |               |     |
| Chromium  | mg/kg | 272      | 05/22/97         | KLF     | 0.35  |               |     |
| Copper    | mg/kg | 1420     | 05/22/97         | KLF     | 0.10  |               |     |
| Lead      | mg/kg | 9130     | 05/22/97         | KLF     | 2.48  | 1000          | F   |
| Mercury   | mg/kg | ND       | 05/23/97         | APP     | 0.020 |               |     |
| Nickel    | mg/kg | 434      | 05/22/97         | KLF     | 0.25  |               |     |
| Selenium  | mg/kg | 5.77     | 05/22/97         | KLF     | 4.95  |               |     |
| Silver    | mg/kg | 1.93     | 05/22/97         | KLF     | 0.50  |               |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

05/30/97  
page 25 of 32

Purchase Order Number: 40163  
Project Number: 40163

LIMS-BAT #: LIMS-29639  
Job Number: 29639  
Sample Matrix: SOIL

Sampled: 05/16/97  
R.O.W.  
ROW/TP06/3-4'

|          | Units | 97809022 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|-------|----------|---------------|---------|------|------------|-----|
| Thallium | mg/kg | ND       | 05/22/97      | KLF     | 9.90 |            |     |
| Zinc     | mg/kg | 1400     | 05/22/97      | KLF     | 0.50 |            |     |

Sampled: 05/16/97  
R.O.W.  
ROW/TP07/2-3'

|           | Units | 97809023 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|-------|------------|-----|
| Antimony  | mg/kg | ND       | 05/22/97      | KLF     | 24.8  |            |     |
| Arsenic   | mg/kg | 28.9     | 05/22/97      | KLF     | 4.95  |            |     |
| Beryllium | mg/kg | 0.25     | 05/22/97      | KLF     | 0.10  |            |     |
| Cadmium   | mg/kg | 7.90     | 05/22/97      | KLF     | 0.05  |            |     |
| Chromium  | mg/kg | 188      | 05/22/97      | KLF     | 0.35  |            |     |
| Copper    | mg/kg | 29500    | 05/22/97      | KLF     | 0.10  |            |     |
| Lead      | mg/kg | 1240     | 05/22/97      | KLF     | 2.48  | 1000       | F   |
| Mercury   | mg/kg | 0.059    | 05/23/97      | APP     | 0.020 |            |     |
| Nickel    | mg/kg | 179      | 05/22/97      | KLF     | 0.25  |            |     |
| Selenium  | mg/kg | 15.2     | 05/22/97      | KLF     | 4.95  |            |     |
| Silver    | mg/kg | ND       | 05/22/97      | KLF     | 4.95  |            |     |
| Thallium  | mg/kg | ND       | 05/22/97      | KLF     | 9.90  |            |     |
| Zinc      | mg/kg | 17800    | 05/22/97      | KLF     | 0.50  |            |     |

Sampled: 05/16/97  
R.O.W.  
ROW/TP10/4-6'

|          | Units | 97809026 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|-------|----------|---------------|---------|------|------------|-----|
| Antimony | mg/kg | ND       | 05/22/97      | KLF     | 2.50 |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

05/30/97  
page 26 of 32

Purchase Order Number: 40163  
Project Number: 40163

LIMS-BAT #: LIMS-29639  
Job Number: 29639  
Sample Matrix: SOIL

Sampled: 05/16/97  
R.O.W.  
ROW/TP10/4-6'

|           | Units | 97809026 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|-------|------------|-----|
| -----     | ----- | -----    | -----         | -----   | ---   | -----      | --- |
| Arsenic   | mg/kg | ND       | 05/22/97      | KLF     | 5.00  |            |     |
| Beryllium | mg/kg | 0.44     | 05/22/97      | KLF     | 0.10  |            |     |
| Cadmium   | mg/kg | 0.14     | 05/22/97      | KLF     | 0.05  |            |     |
| Chromium  | mg/kg | 14.1     | 05/22/97      | KLF     | 0.35  |            |     |
| Copper    | mg/kg | 24.4     | 05/22/97      | KLF     | 0.10  |            |     |
| Lead      | mg/kg | 7.44     | 05/22/97      | KLF     | 2.50  | 1000       | P   |
| Mercury   | mg/kg | ND       | 05/23/97      | APP     | 0.020 |            |     |
| Nickel    | mg/kg | 38.3     | 05/22/97      | KLF     | 0.25  |            |     |
| Selenium  | mg/kg | ND       | 05/22/97      | KLF     | 5.00  |            |     |
| Silver    | mg/kg | ND       | 05/22/97      | KLF     | 0.50  |            |     |
| Thallium  | mg/kg | ND       | 05/22/97      | KLF     | 10.0  |            |     |
| Zinc      | mg/kg | 237      | 05/22/97      | KLF     | 0.50  |            |     |

## Analytical Method(s):

Antimony  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Arsenic  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Beryllium  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

05/30/97

page 27 of 32

## INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Cadmium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Chromium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Copper

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Lead

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Mercury

SW846 3050/7471

SAMPLES ARE DIGESTED WITH ACIDS AND THEN ANALYZED BY  
COLD VAPOR (FLAMELESS) ATOMIC ABSORPTION SPECTROPHOTOMETRY

Nickel

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



05/30/97

page 28 of 32

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Selenium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Silver

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Thallium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Zinc

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

05/30/97

page 29 of 32

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29639

Job Number: 29639

Sample Matrix: SOIL

Sampled: 05/16/97

TEST PST AT UST-2

UST 2-6'

|       | Units | 97809018 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-------|-------|----------|------------------|---------|------|---------------|-----|
| ----- | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| LEAD  | MG/KG | 3.50     | 05/22/97         | APP     | 2.50 | 1000          | P   |

Analytical Method(s):

SW846 3050/7420

SAMPLES ARE DIGESTED IN NITRIC ACID AND ANALYZED BY FLAME ATOMIC  
ABSORPTION SPECTROPHOTOMETRY.MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



05/30/97

page 30 of 32

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29639

Job Number: 29639

Sample Matrix: SOIL

Sampled: 05/16/97

R.O.W.

ROW/TP07/2-3'

|                              | Units | 97809023 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 38200    | 05/28/97      | RCL     | 19.8 |            |     |

Sampled: 05/16/97

R.O.W.

ROW/TP09/6-8'

|                              | Units | 97809024 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 3000     | 05/27/97      | AC      | 20.0 |            |     |

Sampled: 05/16/97

R.O.W.

ROW/TP10/4-6'

|                              | Units | 97809026 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 7450     | 05/28/97      | RCL     | 20.0 |            |     |

Sampled: 05/16/97

R.O.W.

ROW/TP11/3-4'

|                              | Units | 97809028 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 35.2     | 05/27/97      | AC      | 19.6 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

05/30/97

page 31 of 32

Purchase Order Number: 40163

Project Number: 40163

LIMS-BAT #: LIMS-29639

Job Number: 29639

Sample Matrix: SOIL

Sampled: 05/16/97

TEST PST AT UST-2

UST 2-6'

|                              | Units | 97B09018 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                        | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Total Petroleum Hydrocarbons | mg/kg | 9380     | 05/28/97         | RCL     | 20.0 |               |     |

Analytical Method(s):

MODIFIED EPA 418.1

INFRA-RED DETERMINATION FOLLOWING EXTRACTION OF HYDROCARBONS INTO  
1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE (FREON 113)MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

The following notes were attached to the reported analysis:

Sample: 97B09023

ELEVATED DETECTION LIMITS DUE TO SAMPLE MATRIX INTERFERENCE.

Sample: 97B09024

ELEVATED DETECTION LIMITS DUE TO SAMPLE MATRIX INTERFERENCE.

Sample: 97B09026

ELEVATED DETECTION LIMITS DUE TO SAMPLE MATRIX INTERFERENCE.

Sample: 97B09023

Analysis: Antimony

ELEVATED METHOD DETECTION LIMIT DUE TO MATRIX INTERFERENCES.

Sample: 97B09023

Analysis: Silver

ELEVATED METHOD DETECTION LIMIT DUE TO MATRIX INTERFERENCES.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike DuplicatesBATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 1 of 14

QC Batch Number: CYANIDE-0295

| Sample Id    | Analysis        | QC Analysis         | Values | Units | Limits |
|--------------|-----------------|---------------------|--------|-------|--------|
| -----        | -----           | -----               | -----  | ----- | -----  |
| STDADD-05829 | Cyanide - Total | Standard Measured   | 3.190  | mg/l  |        |
|              |                 | Standard Amt Added  | 4.160  | mg/l  |        |
|              |                 | Standard % Recovery | 76.683 | %     |        |

## QC SUMMARY REPORT

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 2 of 14

QC Batch Number: FLM/AA-1164

| Sample Id     | Analysis | QC Analysis          | Values | Units         | Limits |
|---------------|----------|----------------------|--------|---------------|--------|
| -----         | -----    | -----                | -----  | -----         | -----  |
| LFBLANK-03935 | LEAD     | Lab Fort Blank Amt.  | 99.42  | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. Found  | 105.39 | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. % Rec. | 106.00 | %             |        |
|               | LEAD     | Lab Fort Blank Amt.  | 99.42  | MG/KG         |        |
|               |          | Lab Fort Blk. Found  | 105.39 | MG/KG         |        |
|               |          | Lab Fort Blk. % Rec. | 106.00 | %             |        |
| LFBLANK-03936 | LEAD     | Lab Fort Blank Amt.  | 99.60  | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. Found  | 102.59 | mg/kg dry wt. |        |
|               |          | Lab Fort Blk. % Rec. | 103.00 | %             |        |
|               | LEAD     | Lab Fort Blank Amt.  | 99.60  | MG/KG         |        |
|               |          | Lab Fort Blk. Found  | 102.59 | MG/KG         |        |
|               |          | Lab Fort Blk. % Rec. | 103.00 | %             |        |

## QC SUMMARY REPORT

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 3 of 14

QC Batch Number: GC/PID-1632

| Sample Id   | Analysis             | QC Analysis         | Values | Units | Limits     |
|-------------|----------------------|---------------------|--------|-------|------------|
| -----       | -----                | -----               | -----  | ----- | -----      |
| 97809019    | 1-Cl-2-Fluorobenzene | Sur. Recovery (PID) | 102.3  | %     | 70.2-130.0 |
| BLANK-07911 | Benzene              | Blank               | <1.0   | ug/kg |            |
|             | 1,4-Dichlorobenzene  | Blank               | <2.5   | ug/kg |            |
|             | Ethyl Benzene        | Blank               | <2.5   | ug/kg |            |
|             | Toluene              | Blank               | <2.5   | ug/kg |            |
|             | o-Xylene             | Blank               | <2.5   | ug/kg |            |
|             | p&m-Xylene           | Blank               | <5.0   | ug/kg |            |
|             | 1,2-Dichlorobenzene  | Blank               | <2.5   | ug/kg |            |
|             | 1,3-Dichlorobenzene  | Blank               | <2.5   | ug/kg |            |
|             | Methyl tert-Butyl Et | Blank               | <2.5   | ug/kg |            |
|             | Chlorobenzene        | Blank               | <2.5   | ug/kg |            |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 4 of 14

QC Batch Number: GCMS/SEMI-0735

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits     |
|-----------|----------------------|----------------------|--------|-------|------------|
| -----     | -----                | -----                | -----  | ----- | -----      |
| 97809020  | Phenol - D6 mg/kg re | Surrogate Recovery   | 49.2   | %     | 24.0-113.0 |
|           | Nitrobenzene - D5 mg | Surrogate Recovery   | 20.8   | %     | 23.0-120.0 |
|           | 2-Fluorobipheny mg/k | Surrogate Recovery   | 24.9   | %     | 25.0-121.0 |
|           | 2,4,6-Tribromophenol | Surrogate Recovery   | 48.8   | %     | 19.0-122.0 |
|           | Terphenyl - D14 mg/k | Surrogate Recovery   | 32.5   | %     | 18.0-137.0 |
|           | 2-Fluorophenol mg/kg | Surrogate Recovery   | 38.4   | %     | 30.0-115.0 |
| 97809022  | Phenol - D6 mg/kg re | Surrogate Recovery   | 75.3   | %     | 24.0-113.0 |
|           | Nitrobenzene - D5 mg | Surrogate Recovery   | 60.5   | %     | 23.0-120.0 |
|           | 2-Fluorobipheny mg/k | Surrogate Recovery   | 71.9   | %     | 25.0-121.0 |
|           | 2,4,6-Tribromophenol | Surrogate Recovery   | 95.9   | %     | 19.0-122.0 |
|           | Terphenyl - D14 mg/k | Surrogate Recovery   | 83.2   | %     | 18.0-137.0 |
|           | 2-Fluorophenol mg/kg | Surrogate Recovery   | 69.8   | %     | 30.0-115.0 |
| 97809023  | Phenol - D6 mg/kg re | Surrogate Recovery   | 31.4   | %     | 24.0-113.0 |
|           | Nitrobenzene - D5 mg | Surrogate Recovery   | 30.1   | %     | 23.0-120.0 |
|           | 2-Fluorobipheny mg/k | Surrogate Recovery   | 39.2   | %     | 25.0-121.0 |
|           | 2,4,6-Tribromophenol | Surrogate Recovery   | 27.8   | %     | 19.0-122.0 |
|           | Terphenyl - D14 mg/k | Surrogate Recovery   | 45.5   | %     | 18.0-137.0 |
|           | 2-Fluorophenol mg/kg | Surrogate Recovery   | 32.6   | %     | 30.0-115.0 |
| 97809024  | Phenol - D6 mg/kg re | Surrogate Recovery   | 108.5  | %     | 24.0-113.0 |
|           | Nitrobenzene - D5 mg | Surrogate Recovery   | 74.0   | %     | 23.0-120.0 |
|           | 2-Fluorobipheny mg/k | Surrogate Recovery   | 95.0   | %     | 25.0-121.0 |
|           | 2,4,6-Tribromophenol | Surrogate Recovery   | 86.0   | %     | 19.0-122.0 |
|           | Terphenyl - D14 mg/k | Surrogate Recovery   | 106.0  | %     | 18.0-137.0 |
|           | 2-Fluorophenol mg/kg | Surrogate Recovery   | 109.5  | %     | 30.0-115.0 |
| 97809026  | Phenol - D6 mg/kg re | Surrogate Recovery   | 68.0   | %     | 24.0-113.0 |
|           | Nitrobenzene - D5 mg | Surrogate Recovery   | 85.0   | %     | 23.0-120.0 |
|           | 2-Fluorobipheny mg/k | Surrogate Recovery   | 84.0   | %     | 25.0-121.0 |
|           | 2,4,6-Tribromophenol | Surrogate Recovery   | 85.0   | %     | 19.0-122.0 |
|           | Terphenyl - D14 mg/k | Surrogate Recovery   | 88.0   | %     | 18.0-137.0 |
|           | 2-Fluorophenol mg/kg | Surrogate Recovery   | 85.0   | %     | 30.0-115.0 |
| 97809028  | 1,4-Dichlorobenzene  | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |            |
|           |                      | MS Amt Measured      | 2.40   | mg/kg |            |
|           |                      | Matrix Spike % Rec.  | 71.46  | %     |            |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |            |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |            |
|           |                      | MSD Amt Measured     | 2.40   | mg/kg |            |
|           |                      | MSD % Recovery       | 71.46  | %     |            |
|           |                      | MSD Range            | 0.00   | units |            |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 5 of 14

QC Batch Number: GCMS/SEMI-0735

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits |
|-----------|----------------------|----------------------|--------|-------|--------|
| -----     | -----                | -----                | -----  | ----- | -----  |
|           | Acenaphthene         | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |        |
|           |                      | MS Amt Measured      | 2.57   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 77.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |        |
|           |                      | MSD Amt Measured     | 2.80   | mg/kg |        |
|           |                      | MSD % Recovery       | 84.00  | %     |        |
|           |                      | MSD Range            | 7.00   | units |        |
|           | 2,4-Dinitrotoluene   | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |        |
|           |                      | MS Amt Measured      | 2.47   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 74.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |        |
|           |                      | MSD Amt Measured     | 2.80   | mg/kg |        |
|           |                      | MSD % Recovery       | 84.00  | %     |        |
|           |                      | MSD Range            | 10.00  | units |        |
|           | N-Nitrosodimethylami | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |        |
|           |                      | MS Amt Measured      | 3.03   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 91.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |        |
|           |                      | MSD Amt Measured     | 3.17   | mg/kg |        |
|           |                      | MSD % Recovery       | 95.00  | %     |        |
|           |                      | MSD Range            | 4.00   | units |        |
|           | Pyrene               | Sample Amount        | <1.00  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |        |
|           |                      | MS Amt Measured      | 2.33   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 66.60  | %     |        |
|           |                      | Duplicate Sample Amt | <1.00  | mg/kg |        |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |        |
|           |                      | MSD Amt Measured     | 2.30   | mg/kg |        |
|           |                      | MSD % Recovery       | 65.60  | %     |        |
|           |                      | MSD Range            | 1.00   | units |        |
|           | 1,2,4-Trichlorobenze | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |        |
|           |                      | MS Amt Measured      | 2.57   | mg/kg |        |



## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 6 of 14

QC Batch Number: GCMS/SEMI-0735

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits |
|-----------|----------------------|----------------------|--------|-------|--------|
| -----     | -----                | -----                | -----  | ----- | -----  |
|           |                      | Matrix Spike % Rec.  | 77.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |        |
|           |                      | MSD Amt Measured     | 2.63   | mg/kg |        |
|           |                      | MSD % Recovery       | 79.00  | %     |        |
|           |                      | MSD Range            | 2.00   | units |        |
|           | 4-Chloro-3-methylphe | Sample Amount        | <0.67  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 6.67   | mg/kg |        |
|           |                      | MS Amt Measured      | 5.17   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 77.50  | %     |        |
|           |                      | Duplicate Sample Amt | <0.67  | mg/kg |        |
|           |                      | MSD Amount Added     | 6.67   | mg/kg |        |
|           |                      | MSD Amt Measured     | 5.93   | mg/kg |        |
|           |                      | MSD % Recovery       | 89.00  | %     |        |
|           |                      | MSD Range            | 11.50  | units |        |
|           | 2-Chlorophenol       | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 6.67   | mg/kg |        |
|           |                      | MS Amt Measured      | 4.53   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 68.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 6.67   | mg/kg |        |
|           |                      | MSD Amt Measured     | 4.57   | mg/kg |        |
|           |                      | MSD % Recovery       | 68.50  | %     |        |
|           |                      | MSD Range            | 0.50   | units |        |
|           | 4-Nitrophenol        | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 6.67   | mg/kg |        |
|           |                      | MS Amt Measured      | 5.63   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 84.50  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 6.67   | mg/kg |        |
|           |                      | MSD Amt Measured     | 6.97   | mg/kg |        |
|           |                      | MSD % Recovery       | 104.50 | %     |        |
|           |                      | MSD Range            | 20.00  | units |        |
|           | Phenol               | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 6.67   | mg/kg |        |
|           |                      | MS Amt Measured      | 4.80   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 72.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 6.67   | mg/kg |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 7 of 14

QC Batch Number: GCMS/SEMI-0735

| Sample Id   | Analysis               | QC Analysis          | Values | Units | Limits     |
|-------------|------------------------|----------------------|--------|-------|------------|
| -----       | -----                  | -----                | -----  | ----- | -----      |
|             |                        | MSD Amt Measured     | 5.30   | mg/kg |            |
|             |                        | MSD % Recovery       | 79.50  | %     |            |
|             |                        | MSD Range            | 7.50   | units |            |
|             | Pentachlorophenol      | Sample Amount        | <0.33  | mg/kg |            |
|             |                        | Matrix Spk Amt Added | 6.67   | mg/kg |            |
|             |                        | MS Amt Measured      | 4.77   | mg/kg |            |
|             |                        | Matrix Spike % Rec.  | 71.50  | %     |            |
|             |                        | Duplicate Sample Amt | <0.33  | mg/kg |            |
|             |                        | MSD Amount Added     | 6.67   | mg/kg |            |
|             |                        | MSD Amt Measured     | 5.70   | mg/kg |            |
|             |                        | MSD % Recovery       | 85.50  | %     |            |
|             |                        | MSD Range            | 14.00  | units |            |
|             | Phenol - D6 mg/kg re   | Surrogate Recovery   | 62.3   | %     | 24.0-113.0 |
|             | Nitrobenzene - D5 mg   | Surrogate Recovery   | 53.1   | %     | 23.0-120.0 |
|             | 2-Fluorobipheny mg/k   | Surrogate Recovery   | 57.1   | %     | 25.0-121.0 |
|             | 2,4,6-Tribromophenol   | Surrogate Recovery   | 64.8   | %     | 19.0-122.0 |
|             | Terphenyl - D14 mg/k   | Surrogate Recovery   | 56.3   | %     | 18.0-137.0 |
|             | 2-Fluorophenol mg/kg   | Surrogate Recovery   | 58.2   | %     | 30.0-115.0 |
| BLANK-07928 | 1,4-Dichlorobenzene    | Blank                | <0.33  | mg/kg |            |
|             | Naphthalene            | Blank                | <0.33  | mg/kg |            |
|             | 1,2-Dichlorobenzene    | Blank                | <0.33  | mg/kg |            |
|             | 1,3-Dichlorobenzene    | Blank                | <0.33  | mg/kg |            |
|             | Acenaphthene           | Blank                | <0.33  | mg/kg |            |
|             | Acenaphthylene         | Blank                | <0.33  | mg/kg |            |
|             | Aniline                | Blank                | <0.33  | mg/kg |            |
|             | Anthracene             | Blank                | <0.33  | mg/kg |            |
|             | Benzidene              | Blank                | <2.33  | mg/kg |            |
|             | Benzo(a)anthracene     | Blank                | <0.33  | mg/kg |            |
|             | Benzo(a)pyrene         | Blank                | <0.67  | mg/kg |            |
|             | Benzo(b)fluoranthene   | Blank                | <0.33  | mg/kg |            |
|             | Benzo(g,h,i)perylene   | Blank                | <1.00  | mg/kg |            |
|             | Benzoic Acid           | Blank                | <1.00  | mg/kg |            |
|             | Benzyl Alcohol         | Blank                | <0.67  | mg/kg |            |
|             | Bis(2-chloroethyl)et   | Blank                | <0.33  | mg/kg |            |
|             | Bis(2-chloroethoxy)m   | Blank                | <0.33  | mg/kg |            |
|             | Bis(2-chloroisopropyl) | Blank                | <0.33  | mg/kg |            |
|             | Bis(2-ethylhexyl)pht   | Blank                | <0.33  | mg/kg |            |
|             | 4-Bromophenylphenyle   | Blank                | <0.33  | mg/kg |            |
|             | Butylbenzylphthalate   | Blank                | <0.67  | mg/kg |            |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 8 of 14

QC Batch Number: GCHS/SEMI-0735

| Sample Id | Analysis              | QC Analysis | Values | Units | Limits |
|-----------|-----------------------|-------------|--------|-------|--------|
| -----     | -----                 | -----       | -----  | ----- | -----  |
|           | 4-Chloroaniline       | Blank       | <0.67  | mg/kg |        |
|           | 2-Chloronaphthalene   | Blank       | <0.33  | mg/kg |        |
|           | 4-Chlorophenylphenyl  | Blank       | <0.33  | mg/kg |        |
|           | Chrysene              | Blank       | <0.67  | mg/kg |        |
|           | Dibenz(a,h)anthracene | Blank       | <0.67  | mg/kg |        |
|           | Dibenzofuran          | Blank       | <0.33  | mg/kg |        |
|           | 3,3'-Dichlorobenzidi  | Blank       | <0.67  | mg/kg |        |
|           | Diethylphthalate      | Blank       | <0.33  | mg/kg |        |
|           | Dimethylphthalate     | Blank       | <0.67  | mg/kg |        |
|           | Di-n-butylphthalate   | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dinitrotoluene    | Blank       | <0.33  | mg/kg |        |
|           | 2,6-Dinitrotoluene    | Blank       | <0.33  | mg/kg |        |
|           | 1,2-Diphenylhydrazin  | Blank       | <0.33  | mg/kg |        |
|           | Di-n-octylphthalate   | Blank       | <0.67  | mg/kg |        |
|           | Fluoranthene          | Blank       | <0.33  | mg/kg |        |
|           | Fluorene              | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorobenzene     | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorobutadiene   | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorocyclopenta  | Blank       | <0.33  | mg/kg |        |
|           | Hexachloroethane      | Blank       | <0.33  | mg/kg |        |
|           | Indeno(1,2,3-cd)pyre  | Blank       | <0.33  | mg/kg |        |
|           | Isophorone            | Blank       | <0.33  | mg/kg |        |
|           | 2-Methylnaphthalene   | Blank       | <0.33  | mg/kg |        |
|           | 2-Nitroaniline        | Blank       | <0.33  | mg/kg |        |
|           | 3-Nitroaniline        | Blank       | <0.33  | mg/kg |        |
|           | Nitrobenzene          | Blank       | <0.33  | mg/kg |        |
|           | N-Nitrosodimethylami  | Blank       | <0.33  | mg/kg |        |
|           | N-Nitroso-di-n-propy  | Blank       | <0.33  | mg/kg |        |
|           | N-Nitrosodiphenylami  | Blank       | <0.33  | mg/kg |        |
|           | Phenanthrene          | Blank       | <0.33  | mg/kg |        |
|           | Pyrene                | Blank       | <1.00  | mg/kg |        |
|           | 1,2,4-Trichlorobenze  | Blank       | <0.33  | mg/kg |        |
|           | 4-Chloro-3-methylphe  | Blank       | <0.67  | mg/kg |        |
|           | 2-Chlorophenol        | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dichlorophenol    | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dimethylphenol    | Blank       | <1.33  | mg/kg |        |
|           | 4,6-Dinitro-2-methyl  | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dinitrophenol     | Blank       | <0.33  | mg/kg |        |
|           | 2-Methylphenol (o-cr  | Blank       | <0.33  | mg/kg |        |

**QC SUMMARY REPORT**

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 11 of 14

QC Batch Number: GCMS/VOL-1293

| Sample Id | Analysis             | QC Analysis | Values | Units | Limits |
|-----------|----------------------|-------------|--------|-------|--------|
| -----     | -----                | -----       | -----  | ----- | -----  |
|           | 2-Chloroethylvinylet | Blank       | <0.048 | mg/kg |        |
|           | Bromoform            | Blank       | <0.006 | mg/kg |        |
|           | 1,1,2,2-Tetrachloroe | Blank       | <0.007 | mg/kg |        |
|           | Dibromomethane       | Blank       | <0.006 | mg/kg |        |
|           | 1,2-Dichloropropane  | Blank       | <0.003 | mg/kg |        |
|           | 1,2,3-Trichloropropa | Blank       | <0.006 | mg/kg |        |
|           | Dichlorodifluorometh | Blank       | <0.005 | mg/kg |        |
|           | Iodomethane          | Blank       | <0.004 | mg/kg |        |
|           | Acrolein             | Blank       | <0.100 | mg/kg |        |
|           | Acrylonitrile        | Blank       | <0.038 | mg/kg |        |
|           | Carbon Disulfide     | Blank       | <0.002 | mg/kg |        |
|           | Vinyl Acetate        | Blank       | <0.082 | mg/kg |        |
|           | 2-Hexanone           | Blank       | <0.048 | mg/kg |        |
|           | t-1,4-Dichloro-2-But | Blank       | <0.010 | mg/kg |        |
|           | Ethyl Methacrylate   | Blank       | <0.004 | mg/kg |        |
|           | c-1,4-Dichloro-2-But | Blank       | <0.012 | mg/kg |        |
|           | Bromodichloromethane | Blank       | <0.002 | mg/kg |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 12 of 14

QC Batch Number: ICP-1808

| Sample Id     | Analysis  | QC Analysis          | Values | Units | Limits |
|---------------|-----------|----------------------|--------|-------|--------|
| -----         | -----     | -----                | -----  | ----- | -----  |
| LFBLANK-03948 | Silver    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 68.20  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 68.20  | %     |        |
|               | Arsenic   | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 82.90  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 82.90  | %     |        |
|               | Barium    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 93.34  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 93.34  | %     |        |
|               | Beryllium | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.65  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.65  | %     |        |
|               | Cadmium   | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 83.45  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 83.45  | %     |        |
|               | Chromium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.75  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.75  | %     |        |
|               | Copper    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 88.00  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 88.00  | %     |        |
|               | Nickel    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.48  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.48  | %     |        |
|               | Lead      | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 86.70  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 86.70  | %     |        |
|               | Antimony  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 76.65  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 76.65  | %     |        |
|               | Selenium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 83.15  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 83.15  | %     |        |
|               | Thallium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 83.75  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 83.75  | %     |        |
|               | Zinc      | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 81.66  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 81.66  | %     |        |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 13 of 14

QC Batch Number: ICP-1808

| Sample Id     | Analysis  | QC Analysis          | Values | Units | Limits |
|---------------|-----------|----------------------|--------|-------|--------|
| -----         | -----     | -----                | -----  | ----- | -----  |
| LFBLANK-03949 | Silver    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 72.90  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 72.90  | %     |        |
|               | Arsenic   | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 83.80  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 83.80  | %     |        |
|               | Barium    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 92.18  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 92.18  | %     |        |
|               | Beryllium | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.25  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.25  | %     |        |
|               | Cadmium   | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 84.35  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 84.35  | %     |        |
|               | Chromium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.80  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.80  | %     |        |
|               | Copper    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 88.04  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 88.04  | %     |        |
|               | Nickel    | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 88.28  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 88.28  | %     |        |
|               | Lead      | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 87.10  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 87.10  | %     |        |
|               | Antimony  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 75.20  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 75.20  | %     |        |
|               | Selenium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 86.15  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 86.15  | %     |        |
|               | Thallium  | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 84.80  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 84.80  | %     |        |
|               | Zinc      | Lab Fort Blank Amt.  | 100.00 | mg/kg |        |
|               |           | Lab Fort Blk. Found  | 82.62  | mg/kg |        |
|               |           | Lab Fort Blk. % Rec. | 82.62  | %     |        |



**con-test®**  
ANALYTICAL LABORATORY

39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332  
QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29639

Page 14 of 14

NOTES:

QC Batch No.: GCMS/SEMI-0735  
Sample ID: 97B09020  
Analysis: Nitrobenzene - D5  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CON-TEST CONTROL LIMITS, BUT WITHIN  
METHOD REQUIREMENTS.

QC Batch No.: GCMS/SEMI-0735  
Sample ID: 97B09020  
Analysis: 2-Fluorobiphenyl  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CON-TEST CONTROL LIMITS, BUT WITHIN  
METHOD REQUIREMENTS.



(413) 525-2332  
FAX (413) 525-6405

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

Client Name: Vannic Blonger Bio-Station, Inc.  
Attn: Marc Richardson  
Address: 101 Walnut St.  
Waterbury, MA 02272  
Site Location: Walden, CT  
Sampled By: Marc Richardson  
Call Results: Yes ☐ No ☒  
Fax Results: Yes ☒ No ☐

Telephone: 617-924-1770  
Batch #: 115-29639  
Project #: 40163  
Client P.O. #: 40163  
Fax #: 617-923-2336

| Field Sample I.D. | Sample Description | Lab #         | DATE SAMPLED    |                | Composite | Grab | MATRIX      |              |           |      |     |       | Preservative (Use Code) | Container (Use Code) | TH 48 | VOC 82 | Total Lead | 13 Heavy Metals | Succ 82 | Total Organics | VOC 82 |
|-------------------|--------------------|---------------|-----------------|----------------|-----------|------|-------------|--------------|-----------|------|-----|-------|-------------------------|----------------------|-------|--------|------------|-----------------|---------|----------------|--------|
|                   |                    |               | Start Date/Time | Stop Date/Time |           |      | WASTE WATER | GROUND WATER | DKG WATER | Soil | Air | Other |                         |                      |       |        |            |                 |         |                |        |
| 2-G1              | Test Post 05T-2    | 97B09018-9020 |                 | 5/16           |           | X    |             |              |           | X    |     |       |                         | 2-G                  | X     |        | X          |                 |         |                |        |
| TP10-21           | R.O.W              | 9020          |                 | 5/16           | X         |      |             |              |           | X    |     |       |                         | G                    |       |        | X          |                 |         |                |        |
| TP3/121           |                    | 9021          |                 | 5/16           | X         | *    |             |              |           | X    |     |       |                         | G                    |       |        | X          |                 |         |                |        |
| TP6/3-A           |                    | 9022          |                 | 5/16           | X         |      |             |              |           | X    |     |       |                         | G                    |       |        | X          |                 |         |                |        |
| TP7/2-3           |                    | 9023          |                 | 5/16           | X         |      |             |              |           | X    |     |       |                         | G                    |       | X      | X          |                 |         |                |        |
| TP9/6-E           |                    | 9024-9025     |                 | 5/16           | X         |      |             |              |           | X    |     |       |                         | 2-G                  | X     |        | X          |                 |         |                | X      |
| TP10/4-E          |                    | 9026-9027     |                 | 5/16           | X         |      |             |              |           | X    |     |       |                         | 2-G                  | X     |        | X          |                 |         |                | X      |
| TP11/3-A          |                    | 9028          |                 | 5/16           | X         |      |             |              |           | X    |     |       |                         | G                    | X     |        | X          |                 |         |                | X      |

| CONTAINER CODE                                                                            |                   | PRESERVATIVE CODE:                                                                                             |                                                              |
|-------------------------------------------------------------------------------------------|-------------------|----------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------|
| P: PLASTIC (___ Size) V = 40 ml vial G = Glass (___ size) A = 1000 ml Amber 0 = Other ___ |                   | I = ICED N = HNO <sub>3</sub> H = HCl S = NaOH T = Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub> O = OTHER ___ |                                                              |
| Relinquished by: (Signature)<br><u>[Signature]</u>                                        | Date Time<br>1547 | Received by: (Signature)<br><u>W.R. W. Thompson</u>                                                            | Turnaround Requested: ___ 24-Hour ___ 48-Hour ___ Normal ___ |
| Relinquished by: (Signature)<br><u>W.R. W. Thompson</u>                                   | Date Time<br>1720 | Received by: (Signature)<br><u>Edward Danson</u>                                                               | Other ___ Date Required                                      |
| Relinquished by: (Signature)                                                              | Date Time         | Received by: (Signature)                                                                                       | Remarks/Comments:                                            |
| *MATRIX OTHER                                                                             |                   |                                                                                                                |                                                              |





**con-test®**  
ANALYTICAL LABORATORY

39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.

REPORT DATE: 06/12/97

01 WALNUT STREET

WATER TOWN, MA 02272

ATTN: MARC RICHARDS

PURCHASE ORDER NUMBER: 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29688

JOB NUMBER: 29688

The results of analyses performed on the following samples submitted to the CON-TEST Analytical Laboratory are found in this report

PROJECT LOCATION: MIDDLETOWN, CT

| FIELD SAMPLE # | LAB ID   | MATRIX | SAMPLE DESCRIPTION | TEST             |
|----------------|----------|--------|--------------------|------------------|
| 1-01/10-12'    | 97809235 | SOIL   | SOIL BORING        | 8240 - solid (a) |
| 8-01/10-12'    | 97809235 | SOIL   | SOIL BORING        | 8240 - solid (b) |
| 8-01/10-12'    | 97809235 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 1-02/10-12'    | 97809236 | SOIL   | SOIL BORING        | 8240 - solid (a) |
| 3-02/10-12'    | 97809236 | SOIL   | SOIL BORING        | 8240 - solid (b) |
| 8-02/10-12'    | 97809236 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 3-03/10-12'    | 97809237 | SOIL   | SOIL BORING        | 8240 - solid (a) |
| 1-03/10-12'    | 97809237 | SOIL   | SOIL BORING        | 8240 - solid (b) |
| 8-03/10-12'    | 97809237 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-04/0-2'      | 97809238 | SOIL   | SOIL BORING        | 8240 - solid (a) |
| 8-04/0-2'      | 97809238 | SOIL   | SOIL BORING        | 8240 - solid (b) |
| 8-04/0-2'      | 97809238 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-04/08-10'    | 97809239 | SOIL   | SOIL BORING        | 8240 - solid (a) |
| 8-04/08-10'    | 97809239 | SOIL   | SOIL BORING        | 8240 - solid (b) |
| 8-04/08-10'    | 97809239 | SOIL   | SOIL BORING        | 8270-soil bn-2   |
| 8-04/08-10'    | 97809239 | SOIL   | SOIL BORING        | 8270-soil bn1    |
| 8-04/08-10'    | 97809239 | SOIL   | SOIL BORING        | 8270-soil-acid   |
| 8-04/08-10'    | 97809239 | SOIL   | SOIL BORING        | metals(13pp)socp |
| 8-04/08-10'    | 97809239 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-05/06-08'    | 97809240 | SOIL   | SOIL BORING        | 8240 - solid (a) |
| 8-05/06-08'    | 97809240 | SOIL   | SOIL BORING        | 8240 - solid (b) |
| 8-05/06-08'    | 97809240 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-07/10-11'    | 97809241 | SOIL   | SOIL BORING        | 8240 - solid (a) |
| 8-07/10-11'    | 97809241 | SOIL   | SOIL BORING        | 8240 - solid (b) |
| 8-07/10-11'    | 97809241 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-08/08-10'    | 97809242 | SOIL   | SOIL BORING        | 8240 - solid (a) |
| 8-08/08-10'    | 97809242 | SOIL   | SOIL BORING        | 8240 - solid (b) |
| 8-08/08-10'    | 97809242 | SOIL   | SOIL BORING        | 8270-soil bn-2   |
| 8-08/08-10'    | 97809242 | SOIL   | SOIL BORING        | 8270-soil bn1    |
| 8-08/08-10'    | 97809242 | SOIL   | SOIL BORING        | 8270-soil-acid   |
| 8-08/08-10'    | 97809242 | SOIL   | SOIL BORING        | metals(13pp)socp |
| 8-08/08-10'    | 97809242 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-09/09-11'    | 97809243 | SOIL   | SOIL BORING        | 8270-soil bn-2   |
| 8-09/09-11'    | 97809243 | SOIL   | SOIL BORING        | 8270-soil bn1    |
| 8-09/09-11'    | 97809243 | SOIL   | SOIL BORING        | 8270-soil-acid   |
| 8-09/09-11'    | 97809243 | SOIL   | SOIL BORING        | metals(13pp)socp |
| 8-09/09-11'    | 97809243 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-10/06-07'    | 97809244 | SOIL   | SOIL BORING        | 8270-soil bn-2   |
| 8-10/06-07'    | 97809244 | SOIL   | SOIL BORING        | 8270-soil bn1    |



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.

REPORT DATE: 06/12/97

101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

PURCHASE ORDER NUMBER: 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29688  
JOB NUMBER: 29688

| FIELD SAMPLE # | LAB ID   | MATRIX | SAMPLE DESCRIPTION | TEST             |
|----------------|----------|--------|--------------------|------------------|
| 8-10/06-07'    | 97809244 | SOIL   | SOIL BORING        | 8270-soil-acid   |
| 8-10/06-07'    | 97809244 | SOIL   | SOIL BORING        | metals(13pp)socp |
| 8-10/06-07'    | 97809244 | SOIL   | SOIL BORING        | pcb - soil       |
| 8-10/06-07'    | 97809244 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-11/04-06'    | 97809245 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-12/04-06'    | 97809246 | SOIL   | SOIL BORING        | tph (mg/kg)      |
| 8-13/06-08'    | 97809247 | SOIL   | SOIL BORING        | tph (mg/kg)      |

The CON-TEST Environmental Laboratory operates under the following certifications and accreditations:

|                             |                              |
|-----------------------------|------------------------------|
| AIHA 308                    | AIHA ELLAP (LEAD) 6838       |
| MASSACHUSETTS MA100         | MAINE (POTABLE/NON-POTABLE)  |
| CONNECTICUT PH-0567         | VERMONT DOH (LEAD) No. 15036 |
| NEW YORK ELAP 10899         | RHODE ISLAND (LIC. No. 112)  |
| OHIO (ENVIRO. LEAD) # 10005 |                              |
| NEW HAMPSHIRE 2516          |                              |

I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document.

*Edward Denson* 6/12/97

SIGNATURE

DATE

Tod Kopyscinski  
Director of Operations

Edward Denson  
Technical Director



MARC RICHARDS  
VANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272

39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332  
06/12/97

page 1 of 38

Purchase Order Number: 40163

Project Location: MIDDLETOWN, CT  
Date Received: 05/20/97

LIMS-BAT #: LIMS-29688  
Job Number: 29688  
Sample Matrix: SOIL

Sampled: 05/20/97  
SOIL BORING  
B-01/10-12'

|                         | Units | 97B09235 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-------------------------|-------|----------|---------------|---------|-------|------------|-----|
| Acetone                 | mg/kg | ND       | 05/29/97      | WSD     | 0.080 |            |     |
| Acrolein                | mg/kg | ND       | 05/29/97      | WSD     | 0.100 |            |     |
| Acrylonitrile           | mg/kg | ND       | 05/29/97      | WSD     | 0.038 |            |     |
| Benzene                 | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| Bromodichloromethane    | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Bromomethane            | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| Bromoform               | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/29/97      | WSD     | 0.060 |            |     |
| Carbon Disulfide        | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Chlorobenzene           | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Chloroethane            | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/29/97      | WSD     | 0.048 |            |     |
| Chloroform              | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| Chloromethane           | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| Dibromomethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97      | WSD     | 0.012 |            |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97      | WSD     | 0.010 |            |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/29/97      | WSD     | 0.005 |            |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Ethyl Benzene           | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

8-01/10-12'

|                                | Units | 97809235 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| 2-Hexanone                     | mg/kg | ND       | 05/29/97         | WSD     | 0.048 |               |     |
| Iodomethane                    | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Methylene Chloride             | mg/kg | ND       | 05/29/97         | WSD     | 0.015 |               |     |
| 4-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/29/97         | WSD     | 0.044 |               |     |
| Styrene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.007 |               |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Toluene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Trichloroethylene              | mg/kg | 0.058    | 05/29/97         | WSD     | 0.005 |               |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/29/97         | WSD     | 0.082 |               |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| m-Xylene                       | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| o&p-Xylene                     | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |

MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-02/10-12'

|                         | Units | 97809236 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                   | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Acetone                 | mg/kg | ND       | 05/29/97         | WSD     | 0.080 |               |     |
| Acrolein                | mg/kg | ND       | 05/29/97         | WSD     | 0.100 |               |     |
| Acrylonitrile           | mg/kg | ND       | 05/29/97         | WSD     | 0.038 |               |     |
| Benzene                 | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| Bromodichloromethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Bromomethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Bromoform               | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/29/97         | WSD     | 0.060 |               |     |
| Carbon Disulfide        | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Chlorobenzene           | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Chloroethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/29/97         | WSD     | 0.048 |               |     |
| Chloroform              | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Chloromethane           | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Dibromomethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 0.012 |               |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 0.010 |               |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/29/97         | WSD     | 0.005 |               |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Ethyl Benzene           | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or

regulatory level for comparison with data to

determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-03/10-12'

|                                | Units | 97809237 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| 2-Hexanone                     | mg/kg | ND       | 05/29/97         | WSD     | 0.048 |               |     |
| Iodomethane                    | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Methylene Chloride             | mg/kg | ND       | 05/29/97         | WSD     | 0.015 |               |     |
| 4-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/29/97         | WSD     | 0.044 |               |     |
| Styrene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.007 |               |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Toluene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Trichloroethylene              | mg/kg | 0.029    | 05/29/97         | WSD     | 0.005 |               |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/29/97         | WSD     | 0.082 |               |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| m-Xylene                       | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| o&p-Xylene                     | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

 LIMS-BAT #: LIMS-29688  
 Job Number: 29688  
 Sample Matrix: SOIL

 Sampled: 05/20/97  
 SOIL BORING  
 B-04/0-2'

|                         | Units | 97809238 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                   | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Acetone                 | mg/kg | ND       | 05/29/97         | WSD     | 6.44  |               |     |
| Acrolein                | mg/kg | ND       | 05/29/97         | WSD     | 8.00  |               |     |
| Acrylonitrile           | mg/kg | ND       | 05/29/97         | WSD     | 3.04  |               |     |
| Benzene                 | mg/kg | ND       | 05/29/97         | WSD     | 0.240 |               |     |
| Bromodichloromethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.160 |               |     |
| Bromomethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.480 |               |     |
| Bromoform               | mg/kg | ND       | 05/29/97         | WSD     | 0.480 |               |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/29/97         | WSD     | 4.80  |               |     |
| Carbon Disulfide        | mg/kg | ND       | 05/29/97         | WSD     | 0.200 |               |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/29/97         | WSD     | 0.200 |               |     |
| Chlorobenzene           | mg/kg | ND       | 05/29/97         | WSD     | 0.240 |               |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.200 |               |     |
| Chloroethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/29/97         | WSD     | 3.84  |               |     |
| Chloroform              | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |
| Chloromethane           | mg/kg | ND       | 05/29/97         | WSD     | 0.480 |               |     |
| Dibromomethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.440 |               |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.240 |               |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 0.960 |               |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 0.840 |               |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/29/97         | WSD     | 0.400 |               |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.280 |               |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.360 |               |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/29/97         | WSD     | 0.240 |               |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/29/97         | WSD     | 0.240 |               |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/29/97         | WSD     | 0.200 |               |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/29/97         | WSD     | 0.160 |               |     |
| Ethyl Benzene           | mg/kg | BDL      | 05/29/97         | WSD     | 0.240 |               |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-04/0-2'

|                                | Units | 97809238 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| 2-Hexanone                     | mg/kg | ND       | 05/29/97         | WSD     | 3.88  |               |     |
| Iodomethane                    | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |
| Methylene Chloride             | mg/kg | ND       | 05/29/97         | WSD     | 1.20  |               |     |
| 4-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/29/97         | WSD     | 3.52  |               |     |
| Styrene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.280 |               |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.560 |               |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/29/97         | WSD     | 0.160 |               |     |
| Toluene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.280 |               |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.360 |               |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.280 |               |     |
| Trichloroethylene              | mg/kg | ND       | 05/29/97         | WSD     | 0.400 |               |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/29/97         | WSD     | 0.280 |               |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/29/97         | WSD     | 0.520 |               |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/29/97         | WSD     | 6.56  |               |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/29/97         | WSD     | 0.120 |               |     |
| m-Xylene                       | mg/kg | BDL      | 05/29/97         | WSD     | 0.520 |               |     |
| o&p-Xylene                     | mg/kg | 0.840    | 05/29/97         | WSD     | 0.200 |               |     |

MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: 40163

 LIMS-BAT #: LIMS-29688  
 Job Number: 29688  
 Sample Matrix: SOIL

 Sampled: 05/20/97  
 SOIL BORING  
 B-04/08-10'

|                         | Units | 97809239 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                   | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Acetone                 | mg/kg | ND       | 05/29/97         | WSD     | 0.080 |               |     |
| Acrolein                | mg/kg | ND       | 05/29/97         | WSD     | 0.100 |               |     |
| Acrylonitrile           | mg/kg | ND       | 05/29/97         | WSD     | 0.038 |               |     |
| Benzene                 | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| Bromodichloromethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Bromomethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Bromoform               | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/29/97         | WSD     | 0.060 |               |     |
| Carbon Disulfide        | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Chlorobenzene           | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Chloroethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/29/97         | WSD     | 0.048 |               |     |
| Chloroform              | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Chloromethane           | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Dibromomethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 0.012 |               |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 0.010 |               |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/29/97         | WSD     | 0.005 |               |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Ethyl Benzene           | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

8-04/08-10'

|                                | Units | 97809239 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| 2-Hexanone                     | mg/kg | ND       | 05/29/97         | WSD     | 0.048 |               |     |
| Iodomethane                    | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Methylene Chloride             | mg/kg | ND       | 05/29/97         | WSD     | 0.015 |               |     |
| 4-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/29/97         | WSD     | 0.044 |               |     |
| Styrene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.007 |               |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Toluene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Trichloroethylene              | mg/kg | ND       | 05/29/97         | WSD     | 0.005 |               |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/29/97         | WSD     | 0.082 |               |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| m-Xylene                       | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| o&p-Xylene                     | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-05/06-08'

|                         | Units | 97809240 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-------------------------|-------|----------|---------------|---------|-------|------------|-----|
| Acetone                 | mg/kg | ND       | 05/29/97      | WSD     | 6.44  |            |     |
| Acrolein                | mg/kg | ND       | 05/29/97      | WSD     | 8.00  |            |     |
| Acrylonitrile           | mg/kg | ND       | 05/29/97      | WSD     | 3.04  |            |     |
| Benzene                 | mg/kg | ND       | 05/29/97      | WSD     | 0.240 |            |     |
| Bromodichloromethane    | mg/kg | ND       | 05/29/97      | WSD     | 0.160 |            |     |
| Bromomethane            | mg/kg | ND       | 05/29/97      | WSD     | 0.480 |            |     |
| Bromoform               | mg/kg | ND       | 05/29/97      | WSD     | 0.480 |            |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/29/97      | WSD     | 4.80  |            |     |
| Carbon Disulfide        | mg/kg | ND       | 05/29/97      | WSD     | 0.200 |            |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/29/97      | WSD     | 0.200 |            |     |
| Chlorobenzene           | mg/kg | ND       | 05/29/97      | WSD     | 0.240 |            |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/29/97      | WSD     | 0.200 |            |     |
| Chloroethane            | mg/kg | ND       | 05/29/97      | WSD     | 0.320 |            |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/29/97      | WSD     | 3.84  |            |     |
| Chloroform              | mg/kg | ND       | 05/29/97      | WSD     | 0.320 |            |     |
| Chloromethane           | mg/kg | ND       | 05/29/97      | WSD     | 0.480 |            |     |
| Dibromomethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.440 |            |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.320 |            |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.240 |            |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.320 |            |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97      | WSD     | 0.960 |            |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97      | WSD     | 0.840 |            |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/29/97      | WSD     | 0.400 |            |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.280 |            |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.360 |            |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/29/97      | WSD     | 0.240 |            |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/29/97      | WSD     | 0.320 |            |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/29/97      | WSD     | 0.240 |            |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/29/97      | WSD     | 0.200 |            |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/29/97      | WSD     | 0.160 |            |     |
| Ethyl Benzene           | mg/kg | ND       | 05/29/97      | WSD     | 0.240 |            |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/29/97      | WSD     | 0.320 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or

regulatory level for comparison with data to

determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

8-05/06-08'

|                                | Units | 97809240 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| 2-Hexanone                     | mg/kg | ND       | 05/29/97         | WSD     | 3.88  |               |     |
| Iodomethane                    | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/29/97         | WSD     | 0.320 |               |     |
| Methylene Chloride             | mg/kg | ND       | 05/29/97         | WSD     | 1.20  |               |     |
| 4-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/29/97         | WSD     | 3.52  |               |     |
| Styrene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.280 |               |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.560 |               |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/29/97         | WSD     | 0.160 |               |     |
| Toluene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.280 |               |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.360 |               |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.280 |               |     |
| Trichloroethylene              | mg/kg | ND       | 05/29/97         | WSD     | 0.400 |               |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/29/97         | WSD     | 0.280 |               |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/29/97         | WSD     | 0.520 |               |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/29/97         | WSD     | 6.56  |               |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/29/97         | WSD     | 0.120 |               |     |
| m-Xylene                       | mg/kg | BDL      | 05/29/97         | WSD     | 0.520 |               |     |
| o&p-Xylene                     | mg/kg | ND       | 05/29/97         | WSD     | 0.200 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

 LIMS-BAT #: LIMS-29688  
 Job Number: 29688  
 Sample Matrix: SOIL

 Sampled: 05/20/97  
 SOIL BORING  
 8-07/10-11'

|                         | Units | 97809241 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                   | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Acetone                 | mg/kg | ND       | 05/29/97         | WSD     | 0.080 |               |     |
| Acrolein                | mg/kg | ND       | 05/29/97         | WSD     | 0.100 |               |     |
| Acrylonitrile           | mg/kg | ND       | 05/29/97         | WSD     | 0.038 |               |     |
| Benzene                 | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| Bromodichloromethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Bromomethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Bromoform               | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/29/97         | WSD     | 0.060 |               |     |
| Carbon Disulfide        | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Chlorobenzene           | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Chloroethane            | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/29/97         | WSD     | 0.048 |               |     |
| Chloroform              | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Chloromethane           | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Dibromomethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 0.012 |               |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97         | WSD     | 0.010 |               |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/29/97         | WSD     | 0.005 |               |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Ethyl Benzene           | mg/kg | ND       | 05/29/97         | WSD     | 0.003 |               |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-07/10-11'

|                                | Units | 97B09241 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| 2-Hexanone                     | mg/kg | ND       | 05/29/97         | WSD     | 0.048 |               |     |
| Iodomethane                    | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Methylene Chloride             | mg/kg | ND       | 05/29/97         | WSD     | 0.015 |               |     |
| 4-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/29/97         | WSD     | 0.044 |               |     |
| Styrene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/29/97         | WSD     | 0.007 |               |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| Toluene                        | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| Trichloroethylene              | mg/kg | ND       | 05/29/97         | WSD     | 0.005 |               |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/29/97         | WSD     | 0.004 |               |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/29/97         | WSD     | 0.082 |               |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |
| m-Xylene                       | mg/kg | ND       | 05/29/97         | WSD     | 0.006 |               |     |
| o&p-Xylene                     | mg/kg | ND       | 05/29/97         | WSD     | 0.002 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-08/08-10'

|                         | Units | 97B09242 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-------------------------|-------|----------|---------------|---------|-------|------------|-----|
| -----                   | ----- | -----    | -----         | -----   | ---   | -----      | --- |
| Acetone                 | mg/kg | ND       | 05/29/97      | WSD     | 0.080 |            |     |
| Acrolein                | mg/kg | ND       | 05/29/97      | WSD     | 0.100 |            |     |
| Acrylonitrile           | mg/kg | ND       | 05/29/97      | WSD     | 0.038 |            |     |
| Benzene                 | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| Bromodichloromethane    | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Bromomethane            | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| Bromoform               | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/29/97      | WSD     | 0.060 |            |     |
| Carbon Disulfide        | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Chlorobenzene           | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Chloroethane            | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/29/97      | WSD     | 0.048 |            |     |
| Chloroform              | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| Chloromethane           | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| Dibromomethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97      | WSD     | 0.012 |            |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/29/97      | WSD     | 0.010 |            |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/29/97      | WSD     | 0.005 |            |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Ethyl Benzene           | mg/kg | ND       | 05/29/97      | WSD     | 0.003 |            |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

 LIMS-BAT #: LIMS-29688  
 Job Number: 29688  
 Sample Matrix: SOIL

 Sampled: 05/20/97  
 SOIL BORING  
 8-08/08-10'

|                                | Units | 97B09242 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|--------------------------------|-------|----------|---------------|---------|-------|------------|-----|
| -----                          | ----- | -----    | -----         | -----   | ---   | -----      | --- |
| 2-Hexanone                     | mg/kg | ND       | 05/29/97      | WSD     | 0.048 |            |     |
| Iodomethane                    | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| Methylene Chloride             | mg/kg | ND       | 05/29/97      | WSD     | 0.015 |            |     |
| 4-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/29/97      | WSD     | 0.044 |            |     |
| Styrene                        | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/29/97      | WSD     | 0.007 |            |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| Toluene                        | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| Trichloroethylene              | mg/kg | ND       | 05/29/97      | WSD     | 0.005 |            |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/29/97      | WSD     | 0.004 |            |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/29/97      | WSD     | 0.082 |            |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |
| m-Xylene                       | mg/kg | ND       | 05/29/97      | WSD     | 0.006 |            |     |
| o&p-Xylene                     | mg/kg | ND       | 05/29/97      | WSD     | 0.002 |            |     |

Analytical Method(s):

SW846 8240

SAMPLES ARE CONCENTRATED BY PURGE AND TRAP, FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-04/08-10'

|                             | Units | 97B09239 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                       | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Acenaphthene                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Acenaphthylene              | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Aniline                     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Anthracene                  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Benzo(a)anthracene          | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Benzo(a)pyrene              | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Benzo(b)fluoranthene        | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/27/97      | WSD     | 1.00 |            |     |
| Benzo(k)fluoranthene        | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Butylbenzylphthalate        | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Chrysene                    | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Dibenzofuran                | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Diethylphthalate            | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Dimethylphthalate           | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Di-n-butylphthalate         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Di-n-octylphthalate         | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-04/08-10'

|                            | Units | 97B09239 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                      | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Fluoranthene               | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Fluorene                   | mg/kg | 0.43     | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Isophorone                 | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2-Methylnaphthalene        | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Naphthalene                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Phenanthrene               | mg/kg | 1.69     | 05/27/97      | WSD     | 0.33 |            |     |
| Pyrene                     | mg/kg | ND       | 05/27/97      | WSD     | 1.00 |            |     |
| Pyridine                   | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |

MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688  
Job Number: 29688  
Sample Matrix: SOIL

Sampled: 05/20/97  
SOIL BORING  
8-08/08-10'

|                             | Units | 97B09242 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                       | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Acenaphthene                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Acenaphthylene              | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Aniline                     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Anthracene                  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Benzidene                   | mg/kg | ND       | 05/27/97      | WSD     | 2.33 |            |     |
| Benzoic Acid                | mg/kg | ND       | 05/27/97      | WSD     | 1.00 |            |     |
| Benzo(a)anthracene          | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Benzo(a)pyrene              | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Benzo(b)fluoranthene        | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/27/97      | WSD     | 1.00 |            |     |
| Benzo(k)fluoranthene        | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Butylbenzylphthalate        | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Chrysene                    | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Dibenzofuran                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Diethylphthalate            | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Dimethylphthalate           | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Di-n-butylphthalate         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Di-n-octylphthalate         | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-08/08-10'

|                            | Units | 97809242 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                      | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Fluoranthene               | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Fluorene                   | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Isophorone                 | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2-Methylnaphthalene        | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Naphthalene                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Phenanthrene               | mg/kg | 1.27     | 05/27/97      | WSD     | 0.33 |            |     |
| Pyrene                     | mg/kg | ND       | 05/27/97      | WSD     | 1.00 |            |     |
| Pyridine                   | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

8-09/09-11'

|                             | Units | 97809243 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                       | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acenaphthene                | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Acenaphthylene              | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Aniline                     | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Anthracene                  | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Benzo(a)anthracene          | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Benzo(b)fluoranthene        | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Benzo(k)fluoranthene        | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Butylbenzylphthalate        | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Chrysene                    | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Dibenzofuran                | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Diethylphthalate            | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Dimethylphthalate           | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Di-n-butylphthalate         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Di-n-octylphthalate         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or

regulatory level for comparison with data to

determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-09/09-11'

|                            | Units | 97809243 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Fluoranthene               | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Fluorene                   | mg/kg | BDL      | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Isophorone                 | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Methylnaphthalene        | mg/kg | 10.7     | 05/27/97      | WSD     | 10.0 |            |     |
| Naphthalene                | mg/kg | BDL      | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Phenanthrene               | mg/kg | BDL      | 05/27/97      | WSD     | 10.0 |            |     |
| Pyrene                     | mg/kg | BDL      | 05/27/97      | WSD     | 30.0 |            |     |
| Pyridine                   | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-10/06-07'

|                             | Units | 97B09244 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| Acenaphthene                | mg/kg | 528      | 05/27/97      | WSD     | 10.0 |            |     |
| Acenaphthylene              | mg/kg | 556      | 05/27/97      | WSD     | 10.0 |            |     |
| Aniline                     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Anthracene                  | mg/kg | 1500     | 05/27/97      | WSD     | 10.0 |            |     |
| Benzidene                   | mg/kg | BDL      | 05/27/97      | WSD     | 70.0 |            |     |
| Benzoic Acid                | mg/kg | ND       | 05/27/97      | WSD     | 30.0 |            |     |
| Benzo(a)anthracene          | mg/kg | 1560     | 05/27/97      | WSD     | 10.0 |            |     |
| Benzo(a)pyrene              | mg/kg | 1380     | 05/27/97      | WSD     | 20.0 |            |     |
| Benzo(b)fluoranthene        | mg/kg | 1200     | 05/27/97      | WSD     | 10.0 |            |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/27/97      | WSD     | 30.0 |            |     |
| Benzo(k)fluoranthene        | mg/kg | 830      | 05/27/97      | WSD     | 20.0 |            |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/27/97      | WSD     | 20.0 |            |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | BDL      | 05/27/97      | WSD     | 10.0 |            |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Butylbenzylphthalate        | mg/kg | BDL      | 05/27/97      | WSD     | 20.0 |            |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 20.0 |            |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Chrysene                    | mg/kg | 1590     | 05/27/97      | WSD     | 20.0 |            |     |
| Dibenzofuran                | mg/kg | 1000     | 05/27/97      | WSD     | 10.0 |            |     |
| Dibenz(a,h)anthracene       | mg/kg | 184      | 05/27/97      | WSD     | 20.0 |            |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/27/97      | WSD     | 20.0 |            |     |
| Diethylphthalate            | mg/kg | BDL      | 05/27/97      | WSD     | 10.0 |            |     |
| Dimethylphthalate           | mg/kg | BDL      | 05/27/97      | WSD     | 20.0 |            |     |
| Di-n-butylphthalate         | mg/kg | 11.2     | 05/27/97      | WSD     | 10.0 |            |     |
| Di-n-octylphthalate         | mg/kg | ND       | 05/27/97      | WSD     | 20.0 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/12/97

page 24 of 38

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-10/06-07'

|                            | Units | 97809244 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Fluoranthene               | mg/kg | 4680     | 05/27/97      | WSD     | 10.0 |            |     |
| Fluorene                   | mg/kg | 1640     | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | 684      | 05/27/97      | WSD     | 10.0 |            |     |
| Isophorone                 | mg/kg | BDL      | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Methylnaphthalene        | mg/kg | 1000     | 05/27/97      | WSD     | 10.0 |            |     |
| Naphthalene                | mg/kg | 3700     | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Nitroaniline             | mg/kg | BDL      | 05/27/97      | WSD     | 10.0 |            |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Phenanthrene               | mg/kg | 6540     | 05/27/97      | WSD     | 10.0 |            |     |
| Pyrene                     | mg/kg | 3440     | 05/27/97      | WSD     | 30.0 |            |     |
| Pyridine                   | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |

Analytical Method(s):

SW846 8270

SAMPLES ARE EXTRACTED IN METHYLENE CHLORIDE/ACETONE AND  
FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-04/08-10'

|                                  | Units | 97809239 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/27/97         | WSD     | 0.67 |               |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/27/97         | WSD     | 1.33 |               |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Pentachlorophenol                | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Phenol                           | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |

Sampled: 05/20/97

SOIL BORING

B-08/08-10'

|                                  | Units | 97809242 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/27/97         | WSD     | 0.67 |               |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/27/97         | WSD     | 1.33 |               |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

 LIHS-BAT #: LIHS-29688  
 Job Number: 29688  
 Sample Matrix: SOIL

 Sampled: 05/20/97  
 SOIL BORING  
 B-08/08-10'

|                       | Units | 97B09242 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------|-------|----------|---------------|---------|------|------------|-----|
| Pentachlorophenol     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Phenol                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2,4,5-Trichlorophenol | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2,4,6-Trichlorophenol | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |

 Sampled: 05/20/97  
 SOIL BORING  
 B-09/09-11'

|                                  | Units | 97B09243 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------------|-------|----------|---------------|---------|------|------------|-----|
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/27/97      | WSD     | 20.0 |            |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/27/97      | WSD     | 40.0 |            |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Pentachlorophenol                | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Phenol                           | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688  
Job Number: 29688  
Sample Matrix: SOIL

Sampled: 05/20/97  
SOIL BORING  
B-10/06-07'

|                                  | Units | 97809244 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                            | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/27/97      | WSD     | 20.0 |            |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4-Dimethylphenol               | mg/kg | 210      | 05/27/97      | WSD     | 40.0 |            |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Methylphenol (o-cresol)        | mg/kg | 122      | 05/27/97      | WSD     | 10.0 |            |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | 92.0     | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Pentachlorophenol                | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Phenol                           | mg/kg | 68.7     | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |

## Analytical Method(s):

SW846 8270

SAMPLES ARE EXTRACTED IN METHYLENE CHLORIDE/ACETONE AND  
FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-04/08-10'

|           | Units | 97B09239 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|-------|------------|-----|
| Antimony  | mg/kg | ND       | 05/28/97      | KLF     | 2.50  |            |     |
| Arsenic   | mg/kg | 5.07     | 05/28/97      | KLF     | 5.00  |            |     |
| Beryllium | mg/kg | 0.53     | 05/28/97      | KLF     | 0.10  |            |     |
| Cadmium   | mg/kg | 0.06     | 05/28/97      | KLF     | 0.05  |            |     |
| Chromium  | mg/kg | 14.8     | 05/28/97      | KLF     | 0.35  |            |     |
| Copper    | mg/kg | 14.8     | 05/28/97      | KLF     | 0.10  |            |     |
| Lead      | mg/kg | 7.84     | 05/28/97      | KLF     | 2.50  | 1000       | P   |
| Mercury   | mg/kg | ND       | 05/28/97      | APP     | 0.020 |            |     |
| Nickel    | mg/kg | 12.4     | 05/28/97      | KLF     | 0.25  |            |     |
| Selenium  | mg/kg | ND       | 05/28/97      | KLF     | 5.00  |            |     |
| Silver    | mg/kg | ND       | 05/28/97      | KLF     | 0.50  |            |     |
| Thallium  | mg/kg | ND       | 05/28/97      | KLF     | 10.0  |            |     |
| Zinc      | mg/kg | 39.7     | 05/28/97      | KLF     | 0.50  |            |     |

Sampled: 05/20/97

SOIL BORING

B-08/08-10'

|           | Units | 97B09242 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|-------|------------|-----|
| Antimony  | mg/kg | ND       | 05/28/97      | KLF     | 2.48  |            |     |
| Arsenic   | mg/kg | ND       | 05/28/97      | KLF     | 4.95  |            |     |
| Beryllium | mg/kg | 0.55     | 05/28/97      | KLF     | 0.10  |            |     |
| Cadmium   | mg/kg | 0.07     | 05/28/97      | KLF     | 0.05  |            |     |
| Chromium  | mg/kg | 13.9     | 05/28/97      | KLF     | 0.35  |            |     |
| Copper    | mg/kg | 13.4     | 05/28/97      | KLF     | 0.10  |            |     |
| Lead      | mg/kg | 8.54     | 05/28/97      | KLF     | 2.48  | 1000       | P   |
| Mercury   | mg/kg | ND       | 05/28/97      | APP     | 0.183 |            |     |
| Nickel    | mg/kg | 10.9     | 05/28/97      | KLF     | 0.25  |            |     |
| Selenium  | mg/kg | 5.50     | 05/28/97      | KLF     | 4.95  |            |     |
| Silver    | mg/kg | ND       | 05/28/97      | KLF     | 0.50  |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-08/08-10'

|          | Units | 97809242 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------|-------|----------|------------------|---------|------|---------------|-----|
| Thallium | mg/kg | ND       | 05/28/97         | KLF     | 9.90 |               |     |
| Zinc     | mg/kg | 26.5     | 05/28/97         | KLF     | 0.50 |               |     |

Sampled: 05/20/97

SOIL BORING

B-09/09-11'

|           | Units | 97809243 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|-------|---------------|-----|
| Antimony  | mg/kg | ND       | 05/28/97         | KLF     | 2.50  |               |     |
| Arsenic   | mg/kg | 42.9     | 05/28/97         | KLF     | 5.00  |               |     |
| Beryllium | mg/kg | 0.15     | 05/28/97         | KLF     | 0.10  |               |     |
| Cadmium   | mg/kg | 0.26     | 05/28/97         | KLF     | 0.05  |               |     |
| Chromium  | mg/kg | 4.42     | 05/28/97         | KLF     | 0.35  |               |     |
| Copper    | mg/kg | 75.8     | 05/28/97         | KLF     | 0.10  |               |     |
| Lead      | mg/kg | 44.4     | 05/28/97         | KLF     | 2.50  | 1000          | P   |
| Mercury   | mg/kg | 0.044    | 05/28/97         | APP     | 0.020 |               |     |
| Nickel    | mg/kg | 11.6     | 05/28/97         | KLF     | 0.25  |               |     |
| Selenium  | mg/kg | 8.80     | 05/28/97         | KLF     | 5.00  |               |     |
| Silver    | mg/kg | ND       | 05/28/97         | KLF     | 0.50  |               |     |
| Thallium  | mg/kg | ND       | 05/28/97         | KLF     | 10.0  |               |     |
| Zinc      | mg/kg | 21.2     | 05/28/97         | KLF     | 0.50  |               |     |

Sampled: 05/20/97

SOIL BORING

B-10/06-07'

|          | Units | 97809244 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------|-------|----------|------------------|---------|------|---------------|-----|
| Antimony | mg/kg | ND       | 05/28/97         | KLF     | 2.50 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/12/97

page 30 of 38

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-10/06-07'

|           | Units | 97809244 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|-------|---------------|-----|
| -----     | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Arsenic   | mg/kg | 11.7     | 05/28/97         | KLF     | 5.00  |               |     |
| Beryllium | mg/kg | ND       | 05/28/97         | KLF     | 0.10  |               |     |
| Cadmium   | mg/kg | 2.82     | 05/28/97         | KLF     | 0.05  |               |     |
| Chromium  | mg/kg | 18.2     | 05/28/97         | KLF     | 0.35  |               |     |
| Copper    | mg/kg | 69.4     | 05/28/97         | KLF     | 0.10  |               |     |
| Lead      | mg/kg | 296      | 05/28/97         | KLF     | 2.50  | 1000          | P   |
| Mercury   | mg/kg | ND       | 05/28/97         | APP     | 0.186 |               |     |
| Nickel    | mg/kg | 39.8     | 05/28/97         | KLF     | 0.25  |               |     |
| Selenium  | mg/kg | ND       | 05/28/97         | KLF     | 5.00  |               |     |
| Silver    | mg/kg | ND       | 05/28/97         | KLF     | 0.50  |               |     |
| Thallium  | mg/kg | ND       | 05/28/97         | KLF     | 10.0  |               |     |
| Zinc      | mg/kg | 1300     | 05/28/97         | KLF     | 0.50  |               |     |

## Analytical Method(s):

Antimony  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Arsenic  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Beryllium  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Cadmium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Chromium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Copper

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Lead

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Mercury

SW846 3050/7471

SAMPLES ARE DIGESTED WITH ACIDS AND THEN ANALYZED BY  
COLD VAPOR (FLAMELESS) ATOMIC ABSORPTION SPECTROPHOTOMETRY

Nickel

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Selenium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Silver

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Thallium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Zinc

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: 40163

 LIMS-BAT #: LIMS-29688  
 Job Number: 29688  
 Sample Matrix: SOIL

 Sampled: 05/20/97  
 SOIL BORING  
 B-10/06-07'

|               | Units | 97809244 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| PCB 1221      | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| PCB 1232      | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| PCB 1242/1016 | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| PCB 1248      | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| PCB 1254      | mg/kg | 0.746    | 05/23/97         | JB      |       |               |     |
| PCB 1260      | mg/kg | ND       | 05/23/97         | JB      |       |               |     |
| Total PCB     | mg/kg | 0.746    | 05/23/97         | JB      | 0.497 |               |     |

## Analytical Method(s):

SW846 8080

 SAMPLES ARE EXTRACTED INTO HEXANE AND ANALYZED BY GAS CHROMATOGRAPHY  
 WITH ELECTRON CAPTURE DETECTION.

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-01/10-12'

|                              | Units | 97809235 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 37.7     | 05/29/97      | AMC     | 19.8 |            |     |

Sampled: 05/20/97

SOIL BORING

B-02/10-12'

|                              | Units | 97809236 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | BDL      | 05/29/97      | AMC     | 19.6 |            |     |

Sampled: 05/20/97

SOIL BORING

B-03/10-12'

|                              | Units | 97809237 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 47.6     | 05/29/97      | AMC     | 19.8 |            |     |

Sampled: 05/20/97

SOIL BORING

B-04/0-2'

|                              | Units | 97809238 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 12300    | 05/29/97      | AMC     | 19.7 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-04/08-10'

|                              | Units | 97809239 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 4870     | 05/29/97      | AMC     | 19.6 |            |     |

Sampled: 05/20/97

SOIL BORING

B-05/06-08'

|                              | Units | 97809240 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 4490     | 05/29/97      | AMC     | 19.8 |            |     |

Sampled: 05/20/97

SOIL BORING

B-07/10-11'

|                              | Units | 97809241 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 46.2     | 05/29/97      | AMC     | 20.3 |            |     |

Sampled: 05/20/97

SOIL BORING

B-08/08-10'

|                              | Units | 97809242 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| Total Petroleum Hydrocarbons | mg/kg | 4920     | 05/29/97      | AMC     | 19.6 |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688

Job Number: 29688

Sample Matrix: SOIL

Sampled: 05/20/97

SOIL BORING

B-09/09-11'

|                              | Units | 97809243 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 62500    | 05/29/97      | AMC     | 19.6 |            |     |

Sampled: 05/20/97

SOIL BORING

B-10/06-07'

|                              | Units | 97809244 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 10400    | 05/29/97      | AMC     | 20.3 |            |     |

Sampled: 05/20/97

SOIL BORING

B-11/04-06'

|                              | Units | 97809245 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 34.2     | 05/29/97      | AMC     | 19.5 |            |     |

Sampled: 05/20/97

SOIL BORING

B-12/04-06'

|                              | Units | 97809246 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 25.8     | 05/29/97      | AMC     | 19.8 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29688  
Job Number: 29688  
Sample Matrix: SOIL

Sampled: 05/20/97  
SOIL BORING  
B-13/06-08'

|                              | Units | 97809247 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| .....                        | ..... | .....    | .....            | .....   | ---  | -----         | --- |
| Total Petroleum Hydrocarbons | mg/kg | 33.5     | 05/29/97         | AMC     | 19.7 |               |     |

Analytical Method(s):

MODIFIED EPA 418.1

INFRA-RED DETERMINATION FOLLOWING EXTRACTION OF HYDROCARBONS INTO  
1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE (FREON 113)

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

The following notes were attached to the reported analysis:

Sample: 97809242

Analysis: Mercury

ELEVATED METHOD DETECTION LIMIT DUE TO MATRIX INTERFERENCES.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

## QC SUMMARY REPORT

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 1 of 19

QC Batch Number: GC/ECD-1287

| Sample Id   | Analysis            | QC Analysis | Values | Units | Limits |
|-------------|---------------------|-------------|--------|-------|--------|
| -----       | -----               | -----       | -----  | ----- | -----  |
| BLANK-07902 | PCB 1232            | Blank       | 0.000  | mg/kg |        |
|             | PCB 1242/1016       | Blank       | 0.000  | mg/kg |        |
|             | PCB 1254            | Blank       | 0.000  | mg/kg |        |
|             | PCB 1260            | Blank       | 0.000  | mg/kg |        |
|             | PCB 1248            | Blank       | 0.000  | mg/kg |        |
|             | PCB 1221            | Blank       | 0.000  | mg/kg |        |
|             | Total PCB           | Blank       | <0.025 | mg/kg |        |
|             | Dibutylchloredate ( | Blank       | 106.5  | %     |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 2 of 19

QC Batch Number: GCMS/SEMI-0738

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits     |
|-----------|----------------------|----------------------|--------|-------|------------|
| -----     | -----                | -----                | -----  | ----- | -----      |
| 97B09239  | Phenol - D6 mg/kg re | Surrogate Recovery   | 118.8  | %     | 24.0-113.0 |
|           | Nitrobenzene - D5 mg | Surrogate Recovery   | 120.2  | %     | 23.0-120.0 |
|           | 2-Fluorobipheny mg/k | Surrogate Recovery   | 97.3   | %     | 25.0-121.0 |
|           | 2,4,6-Tribromophenol | Surrogate Recovery   | 106.6  | %     | 19.0-122.0 |
|           | Terphenyl - D14 mg/k | Surrogate Recovery   | 105.7  | %     | 18.0-137.0 |
|           | 2-Fluorophenol mg/kg | Surrogate Recovery   | 113.8  | %     | 30.0-115.0 |
| 97B09242  | 1,4-Dichlorobenzene  | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Duplicate Value      | <0.33  | mg/kg |            |
|           |                      | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |            |
|           |                      | MS Amt Measured      | 2.50   | mg/kg |            |
|           |                      | Matrix Spike % Rec.  | 75.00  | %     |            |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |            |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |            |
|           |                      | MSD Amt Measured     | 2.90   | mg/kg |            |
|           |                      | MSD % Recovery       | 87.00  | %     |            |
|           |                      | MSD Range            | 12.00  | units |            |
|           | Naphthalene          | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Duplicate Value      | <0.33  | mg/kg |            |
|           | 1,2-Dichlorobenzene  | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Duplicate Value      | <0.33  | mg/kg |            |
|           | 1,3-Dichlorobenzene  | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Duplicate Value      | <0.33  | mg/kg |            |
|           | Acenaphthene         | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Duplicate Value      | <0.33  | mg/kg |            |
|           |                      | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |            |
|           |                      | MS Amt Measured      | 3.17   | mg/kg |            |
|           |                      | Matrix Spike % Rec.  | 95.00  | %     |            |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |            |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |            |
|           |                      | MSD Amt Measured     | 3.67   | mg/kg |            |
|           |                      | MSD % Recovery       | 110.00 | %     |            |
|           |                      | MSD Range            | 15.00  | units |            |
|           | Acenaphthylene       | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Duplicate Value      | <0.33  | mg/kg |            |
|           | Aniline              | Sample Amount        | <0.33  | mg/kg |            |
|           |                      | Duplicate Value      | <0.33  | mg/kg |            |
|           | Anthracene           | Sample Amount        | <0.33  | mg/kg |            |



## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 3 of 19

QC Batch Number: GCMS/SEMI-0738

| Sample Id | Analysis               | QC Analysis     | Values | Units | Limits |
|-----------|------------------------|-----------------|--------|-------|--------|
| -----     | -----                  | -----           | -----  | ----- | -----  |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | Benzidene              | Sample Amount   | <2.33  | mg/kg |        |
|           |                        | Duplicate Value | <2.33  | mg/kg |        |
|           | Benzo(a)anthracene     | Sample Amount   | <0.33  | mg/kg |        |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | Benzo(a)pyrene         | Sample Amount   | <0.67  | mg/kg |        |
|           |                        | Duplicate Value | <0.67  | mg/kg |        |
|           | Benzo(b)fluoranthene   | Sample Amount   | <0.33  | mg/kg |        |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | Benzo(g,h,i)perylene   | Sample Amount   | <1.00  | mg/kg |        |
|           |                        | Duplicate Value | <1.00  | mg/kg |        |
|           | Benzoic Acid           | Sample Amount   | <1.00  | mg/kg |        |
|           |                        | Duplicate Value | <1.00  | mg/kg |        |
|           | Benzyl Alcohol         | Sample Amount   | <0.67  | mg/kg |        |
|           |                        | Duplicate Value | <0.67  | mg/kg |        |
|           | Bis(2-chloroethyl)et   | Sample Amount   | <0.33  | mg/kg |        |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | Bis(2-chloroethoxy)m   | Sample Amount   | <0.33  | mg/kg |        |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | Bis(2-chloroisopropyl) | Sample Amount   | <0.33  | mg/kg |        |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | Bis(2-ethylhexyl)pht   | Sample Amount   | <0.33  | mg/kg |        |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | 4-Bromophenylphenyle   | Sample Amount   | <0.33  | mg/kg |        |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | Butylbenzylphthalate   | Sample Amount   | <0.67  | mg/kg |        |
|           |                        | Duplicate Value | <0.67  | mg/kg |        |
|           | 4-Chloroaniline        | Sample Amount   | <0.67  | mg/kg |        |
|           |                        | Duplicate Value | <0.67  | mg/kg |        |
|           | 2-Chloronaphthalene    | Sample Amount   | <0.33  | mg/kg |        |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | 4-Chlorophenylphenyl   | Sample Amount   | <0.33  | mg/kg |        |
|           |                        | Duplicate Value | <0.33  | mg/kg |        |
|           | Chrysene               | Sample Amount   | <0.67  | mg/kg |        |
|           |                        | Duplicate Value | <0.67  | mg/kg |        |
|           |                        | Duplicate RPD   | 31.37  | %     |        |
|           | Dibenz(a,h)anthracen   | Sample Amount   | <0.67  | mg/kg |        |
|           |                        | Duplicate Value | <0.67  | mg/kg |        |
|           | Dibenzofuran           | Sample Amount   | <0.33  | mg/kg |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 4 of 19

QC Batch Number: GCMS/SEMI-0738

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits |
|-----------|----------------------|----------------------|--------|-------|--------|
| -----     | -----                | -----                | -----  | ----- | -----  |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 3,3'-Dichlorobenzidi | Sample Amount        | <0.67  | mg/kg |        |
|           |                      | Duplicate Value      | <0.67  | mg/kg |        |
|           | Diethylphthalate     | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Dimethylphthalate    | Sample Amount        | <0.67  | mg/kg |        |
|           |                      | Duplicate Value      | <0.67  | mg/kg |        |
|           | Di-n-butylphthalate  | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 2,4-Dinitrotoluene   | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           |                      | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |        |
|           |                      | MS Amt Measured      | 2.57   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 77.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |        |
|           |                      | MSD Amt Measured     | 2.33   | mg/kg |        |
|           |                      | MSD % Recovery       | 70.00  | %     |        |
|           |                      | MSD Range            | 7.00   | units |        |
|           | 2,6-Dinitrotoluene   | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 1,2-Diphenylhydrazin | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Di-n-octylphthalate  | Sample Amount        | <0.67  | mg/kg |        |
|           |                      | Duplicate Value      | <0.67  | mg/kg |        |
|           | Fluoranthene         | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Fluorene             | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Hexachlorobenzene    | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Hexachlorobutadiene  | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Hexachlorocyclopenta | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Hexachloroethane     | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Indeno(1,2,3-cd)pyre | Sample Amount        | <0.33  | mg/kg |        |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 5 of 19

QC Batch Number: GCMS/SEMI-0738

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits |
|-----------|----------------------|----------------------|--------|-------|--------|
| -----     | -----                | -----                | -----  | ----- | -----  |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Isophorone           | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 2-Methylnaphthalene  | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 2-Nitroaniline       | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 3-Nitroaniline       | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Nitrobenzene         | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | N-Nitrosodimethylami | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | N-Nitroso-di-n-propy | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           |                      | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |        |
|           |                      | MS Amt Measured      | 3.43   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 103.00 | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |        |
|           |                      | MSD Amt Measured     | 4.13   | mg/kg |        |
|           |                      | MSD % Recovery       | 124.00 | %     |        |
|           |                      | MSD Range            | 21.00  | units |        |
|           | N-Nitrosodiphenylami | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Phenanthrene         | Sample Amount        | 1.27   | mg/kg |        |
|           |                      | Duplicate Value      | 0.60   | mg/kg |        |
|           |                      | Duplicate RPD        | 71.54  | %     |        |
|           | Pyrene               | Sample Amount        | <1.00  | mg/kg |        |
|           |                      | Duplicate Value      | <1.00  | mg/kg |        |
|           |                      | Sample Amount        | <1.00  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |        |
|           |                      | MS Amt Measured      | 3.23   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 97.00  | %     |        |
|           |                      | Duplicate Sample Amt | <1.00  | mg/kg |        |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |        |
|           |                      | MSD Amt Measured     | 3.77   | mg/kg |        |
|           |                      | MSD % Recovery       | 113.00 | %     |        |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 6 of 19

QC Batch Number: GCMS/SEMI-0738

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits |
|-----------|----------------------|----------------------|--------|-------|--------|
| -----     | -----                | -----                | -----  | ----- | -----  |
|           |                      | MSD Range            | 16.00  | units |        |
|           | 1,2,4-Trichlorobenze | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           |                      | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 3.33   | mg/kg |        |
|           |                      | MS Amt Measured      | 3.03   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 91.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 3.33   | mg/kg |        |
|           |                      | MSD Amt Measured     | 3.30   | mg/kg |        |
|           |                      | MSD % Recovery       | 99.00  | %     |        |
|           |                      | MSD Range            | 8.00   | units |        |
|           | 4-Chloro-3-methylphe | Sample Amount        | <0.67  | mg/kg |        |
|           |                      | Duplicate Value      | <0.67  | mg/kg |        |
|           |                      | Sample Amount        | <0.67  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 6.67   | mg/kg |        |
|           |                      | MS Amt Measured      | 2.07   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 31.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.67  | mg/kg |        |
|           |                      | MSD Amount Added     | 6.67   | mg/kg |        |
|           |                      | MSD Amt Measured     | 6.63   | mg/kg |        |
|           |                      | MSD % Recovery       | 99.50  | %     |        |
|           |                      | MSD Range            | 68.50  | units |        |
|           | 2-Chlorophenol       | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           |                      | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 6.67   | mg/kg |        |
|           |                      | MS Amt Measured      | 5.20   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 78.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 6.67   | mg/kg |        |
|           |                      | MSD Amt Measured     | 6.00   | mg/kg |        |
|           |                      | MSD % Recovery       | 90.00  | %     |        |
|           |                      | MSD Range            | 12.00  | units |        |
|           | 2,4-Dichlorophenol   | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 2,4-Dimethylphenol   | Sample Amount        | <1.33  | mg/kg |        |
|           |                      | Duplicate Value      | <1.33  | mg/kg |        |
|           | 4,6-Dinitro-2-methyl | Sample Amount        | <0.33  | mg/kg |        |

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 7 of 19

QC Batch Number: GCMS/SEMI-0738

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits |
|-----------|----------------------|----------------------|--------|-------|--------|
| -----     | -----                | -----                | -----  | ----- | -----  |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 2,4-Dinitrophenol    | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 2-Methylphenol (o-cr | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 3- & 4-Methylphenol  | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 2-Nitrophenol        | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 4-Nitrophenol        | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           |                      | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 6.67   | mg/kg |        |
|           |                      | MS Amt Measured      | 1.23   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 18.50  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 6.67   | mg/kg |        |
|           |                      | MSD Amt Measured     | 5.57   | mg/kg |        |
|           |                      | MSD % Recovery       | 83.50  | %     |        |
|           |                      | MSD Range            | 65.00  | units |        |
|           | Phenol               | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           |                      | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 6.67   | mg/kg |        |
|           |                      | MS Amt Measured      | 5.40   | mg/kg |        |
|           |                      | Matrix Spike % Rec.  | 81.00  | %     |        |
|           |                      | Duplicate Sample Amt | <0.33  | mg/kg |        |
|           |                      | MSD Amount Added     | 6.67   | mg/kg |        |
|           |                      | MSD Amt Measured     | 6.53   | mg/kg |        |
|           |                      | MSD % Recovery       | 98.00  | %     |        |
|           |                      | MSD Range            | 17.00  | units |        |
|           | 2,4,5-Trichloropheno | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | 2,4,6-Trichloropheno | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           | Pentachlorophenol    | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Duplicate Value      | <0.33  | mg/kg |        |
|           |                      | Sample Amount        | <0.33  | mg/kg |        |
|           |                      | Matrix Spk Amt Added | 6.67   | mg/kg |        |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 8 of 19

QC Batch Number: GCMS/SEMI-0738

| Sample Id   | Analysis             | QC Analysis          | Values | Units | Limits     |
|-------------|----------------------|----------------------|--------|-------|------------|
| -----       | -----                | -----                | -----  | ----- | -----      |
|             |                      | MS Amt Measured      | 5.13   | mg/kg |            |
|             |                      | Matrix Spike % Rec.  | 77.00  | %     |            |
|             |                      | Duplicate Sample Amt | <0.33  | mg/kg |            |
|             |                      | MSD Amount Added     | 6.67   | mg/kg |            |
|             |                      | MSD Amt Measured     | 5.93   | mg/kg |            |
|             |                      | MSD % Recovery       | 89.00  | %     |            |
|             |                      | MSD Range            | 12.00  | units |            |
|             | Pyridine             | Sample Amount        | <0.33  | mg/kg |            |
|             |                      | Duplicate Value      | <0.33  | mg/kg |            |
|             | Benzo(k)fluoranthene | Sample Amount        | <0.67  | mg/kg |            |
|             |                      | Duplicate Value      | <0.67  | mg/kg |            |
|             |                      | Duplicate RPD        | 75.69  | %     |            |
|             | 4-Nitroaniline       | Sample Amount        | <0.33  | mg/kg |            |
|             |                      | Duplicate Value      | <0.33  | mg/kg |            |
|             | Phenol - D6 mg/kg re | Surrogate Recovery   | 126.0  | %     | 24.0-113.0 |
|             | Nitrobenzene - D5 mg | Surrogate Recovery   | 114.9  | %     | 23.0-120.0 |
|             | 2-Fluorobipheny mg/k | Surrogate Recovery   | 122.8  | %     | 25.0-121.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery   | 29.8   | %     | 19.0-122.0 |
|             | Terphenyl - D14 mg/k | Surrogate Recovery   | 105.6  | %     | 18.0-137.0 |
|             | 2-Fluorophenol mg/kg | Surrogate Recovery   | 118.4  | %     | 30.0-115.0 |
| 97B09243    | Phenol - D6 mg/kg re | Surrogate Recovery   | 84.1   | %     | 24.0-113.0 |
|             | Nitrobenzene - D5 mg | Surrogate Recovery   | 70.6   | %     | 23.0-120.0 |
|             | 2-Fluorobipheny mg/k | Surrogate Recovery   | 86.8   | %     | 25.0-121.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery   | 80.0   | %     | 19.0-122.0 |
|             | Terphenyl - D14 mg/k | Surrogate Recovery   | 94.2   | %     | 18.0-137.0 |
|             | 2-Fluorophenol mg/kg | Surrogate Recovery   | 83.0   | %     | 30.0-115.0 |
| 97B09244    | Phenol - D6 mg/kg re | Surrogate Recovery   | 86.4   | %     | 24.0-113.0 |
|             | Nitrobenzene - D5 mg | Surrogate Recovery   | 115.8  | %     | 23.0-120.0 |
|             | 2-Fluorobipheny mg/k | Surrogate Recovery   | 77.6   | %     | 25.0-121.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery   | 68.2   | %     | 19.0-122.0 |
|             | Terphenyl - D14 mg/k | Surrogate Recovery   | 136.0  | %     | 18.0-137.0 |
|             | 2-Fluorophenol mg/kg | Surrogate Recovery   | 82.1   | %     | 30.0-115.0 |
| BLANK-07955 | 1,4-Dichlorobenzene  | Blank                | <0.33  | mg/kg |            |
|             | Naphthalene          | Blank                | <0.33  | mg/kg |            |
|             | 1,2-Dichlorobenzene  | Blank                | <0.33  | mg/kg |            |
|             | 1,3-Dichlorobenzene  | Blank                | <0.33  | mg/kg |            |
|             | Acenaphthene         | Blank                | <0.33  | mg/kg |            |
|             | Acenaphthylene       | Blank                | <0.33  | mg/kg |            |
|             | Aniline              | Blank                | <0.33  | mg/kg |            |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 9 of 19

QC Batch Number: GCMS/SEMI-0738

| Sample Id | Analysis               | QC Analysis | Values | Units | Limits |
|-----------|------------------------|-------------|--------|-------|--------|
| -----     | -----                  | -----       | -----  | ----- | -----  |
|           | Anthracene             | Blank       | <0.33  | mg/kg |        |
|           | Benzenzene             | Blank       | <2.33  | mg/kg |        |
|           | Benzo(a)anthracene     | Blank       | <0.33  | mg/kg |        |
|           | Benzo(a)pyrene         | Blank       | <0.67  | mg/kg |        |
|           | Benzo(b)fluoranthene   | Blank       | <0.33  | mg/kg |        |
|           | Benzo(g,h,i)perylene   | Blank       | <1.00  | mg/kg |        |
|           | Benzoic Acid           | Blank       | <1.00  | mg/kg |        |
|           | Benzyl Alcohol         | Blank       | <0.67  | mg/kg |        |
|           | Bis(2-chloroethyl)et   | Blank       | <0.33  | mg/kg |        |
|           | Bis(2-chloroethoxy)m   | Blank       | <0.33  | mg/kg |        |
|           | Bis(2-chloroisopropyl) | Blank       | <0.33  | mg/kg |        |
|           | Bis(2-ethylhexyl)pht   | Blank       | <0.33  | mg/kg |        |
|           | 4-Bromophenylphenyle   | Blank       | <0.33  | mg/kg |        |
|           | Butylbenzylphthalate   | Blank       | <0.67  | mg/kg |        |
|           | 4-Chloroaniline        | Blank       | <0.67  | mg/kg |        |
|           | 2-Chloronaphthalene    | Blank       | <0.33  | mg/kg |        |
|           | 4-Chlorophenylphenyl   | Blank       | <0.33  | mg/kg |        |
|           | Chrysene               | Blank       | <0.67  | mg/kg |        |
|           | Dibenz(a,h)anthracen   | Blank       | <0.67  | mg/kg |        |
|           | Dibenzofuran           | Blank       | <0.33  | mg/kg |        |
|           | 3,3'-Dichlorobenzidi   | Blank       | <0.67  | mg/kg |        |
|           | Diethylphthalate       | Blank       | <0.33  | mg/kg |        |
|           | Dimethylphthalate      | Blank       | <0.67  | mg/kg |        |
|           | Di-n-butylphthalate    | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dinitrotoluene     | Blank       | <0.33  | mg/kg |        |
|           | 2,6-Dinitrotoluene     | Blank       | <0.33  | mg/kg |        |
|           | 1,2-Diphenylhydrazin   | Blank       | <0.33  | mg/kg |        |
|           | Di-n-octylphthalate    | Blank       | <0.67  | mg/kg |        |
|           | Fluoranthene           | Blank       | <0.33  | mg/kg |        |
|           | Fluorene               | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorobenzene      | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorobutadiene    | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorocyclopenta   | Blank       | <0.33  | mg/kg |        |
|           | Hexachloroethane       | Blank       | <0.33  | mg/kg |        |
|           | Indeno(1,2,3-cd)pyre   | Blank       | <0.33  | mg/kg |        |
|           | Isophorone             | Blank       | <0.33  | mg/kg |        |
|           | 2-Methylnaphthalene    | Blank       | <0.33  | mg/kg |        |
|           | 2-Nitroaniline         | Blank       | <0.33  | mg/kg |        |
|           | 3-Nitroaniline         | Blank       | <0.33  | mg/kg |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 10 of 19

QC Batch Number: GCMS/SEMI-0738

| Sample Id | Analysis             | QC Analysis | Values | Units | Limits |
|-----------|----------------------|-------------|--------|-------|--------|
| -----     | -----                | -----       | -----  | ----- | -----  |
|           | Nitrobenzene         | Blank       | <0.33  | mg/kg |        |
|           | N-Nitrosodimethylami | Blank       | <0.33  | mg/kg |        |
|           | N-Nitroso-di-n-propy | Blank       | <0.33  | mg/kg |        |
|           | N-Nitrosodiphenylami | Blank       | <0.33  | mg/kg |        |
|           | Phenanthrene         | Blank       | <0.33  | mg/kg |        |
|           | Pyrene               | Blank       | <1.00  | mg/kg |        |
|           | 1,2,4-Trichlorobenze | Blank       | <0.33  | mg/kg |        |
|           | 4-Chloro-3-methylphe | Blank       | <0.67  | mg/kg |        |
|           | 2-Chlorophenol       | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dichlorophenol   | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dimethylphenol   | Blank       | <1.33  | mg/kg |        |
|           | 4,6-Dinitro-2-methyl | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dinitrophenol    | Blank       | <0.33  | mg/kg |        |
|           | 2-Methylphenol (o-cr | Blank       | <0.33  | mg/kg |        |
|           | 3- & 4-Methylphenol  | Blank       | <0.33  | mg/kg |        |
|           | 2-Nitrophenol        | Blank       | <0.33  | mg/kg |        |
|           | 4-Nitrophenol        | Blank       | <0.33  | mg/kg |        |
|           | Phenol               | Blank       | <0.33  | mg/kg |        |
|           | 2,4,5-Trichloropheno | Blank       | <0.33  | mg/kg |        |
|           | 2,4,6-Trichloropheno | Blank       | <0.33  | mg/kg |        |
|           | Pentachlorophenol    | Blank       | <0.33  | mg/kg |        |
|           | Pyridine             | Blank       | <0.33  | mg/kg |        |
|           | Benzo(k)fluoranthene | Blank       | <0.67  | mg/kg |        |
|           | 4-Nitroaniline       | Blank       | <0.33  | mg/kg |        |



SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 11 of 19

QC Batch Number: GCMS/VOL-1294

| Sample Id | Analysis             | QC Analysis          | Values  | Units | Limits         |
|-----------|----------------------|----------------------|---------|-------|----------------|
| -----     | -----                | -----                | -----   | ----- | -----          |
| 97809235  | d4-12-Dichloroethane | Surrogate Recovery   | 111.200 | %     | 56.000-128.000 |
|           | d8-Toluene (8240 dry | Surrogate Recovery   | 102.000 | %     | 65.000-113.000 |
|           | Bromofluorobenzene   | Surrogate Recovery   | 102.400 | %     | 62.000-137.000 |
| 97809236  | d4-12-Dichloroethane | Surrogate Recovery   | 106.800 | %     | 56.000-128.000 |
|           | d8-Toluene (8240 dry | Surrogate Recovery   | 104.400 | %     | 65.000-113.000 |
|           | Bromofluorobenzene   | Surrogate Recovery   | 109.600 | %     | 62.000-137.000 |
| 97809237  | d4-12-Dichloroethane | Surrogate Recovery   | 109.600 | %     | 56.000-128.000 |
|           | d8-Toluene (8240 dry | Surrogate Recovery   | 103.600 | %     | 65.000-113.000 |
|           | Bromofluorobenzene   | Surrogate Recovery   | 108.000 | %     | 62.000-137.000 |
| 97809238  | d4-12-Dichloroethane | Surrogate Recovery   | 104.400 | %     | 56.000-128.000 |
|           | d8-Toluene (8240 dry | Surrogate Recovery   | 98.800  | %     | 65.000-113.000 |
|           | Bromofluorobenzene   | Surrogate Recovery   | 106.400 | %     | 62.000-137.000 |
| 97809239  | d4-12-Dichloroethane | Surrogate Recovery   | 116.520 | %     | 56.000-128.000 |
|           | d8-Toluene (8240 dry | Surrogate Recovery   | 96.320  | %     | 65.000-113.000 |
|           | Bromofluorobenzene   | Surrogate Recovery   | 93.080  | %     | 62.000-137.000 |
| 97809240  | d4-12-Dichloroethane | Surrogate Recovery   | 105.200 | %     | 56.000-128.000 |
|           | d8-Toluene (8240 dry | Surrogate Recovery   | 103.600 | %     | 65.000-113.000 |
|           | Bromofluorobenzene   | Surrogate Recovery   | 114.000 | %     | 62.000-137.000 |
| 97809241  | d4-12-Dichloroethane | Surrogate Recovery   | 104.400 | %     | 56.000-128.000 |
|           | d8-Toluene (8240 dry | Surrogate Recovery   | 106.400 | %     | 65.000-113.000 |
|           | Bromofluorobenzene   | Surrogate Recovery   | 108.800 | %     | 62.000-137.000 |
| 97809242  | Benzene              | Sample Amount        | <0.003  | mg/kg |                |
|           |                      | Matrix Spk Amt Added | 0.125   | mg/kg |                |
|           |                      | MS Amt Measured      | 0.139   | mg/kg |                |
|           |                      | Matrix Spike % Rec.  | 111.520 | %     |                |
|           | Toluene              | Sample Amount        | <0.004  | mg/kg |                |
|           |                      | Matrix Spk Amt Added | 0.125   | mg/kg |                |
|           |                      | MS Amt Measured      | 0.112   | mg/kg |                |
|           |                      | Matrix Spike % Rec.  | 90.000  | %     |                |
|           | Trichloroethylene    | Sample Amount        | <0.005  | mg/kg |                |
|           |                      | Matrix Spk Amt Added | 0.125   | mg/kg |                |
|           |                      | MS Amt Measured      | 0.120   | mg/kg |                |
|           |                      | Matrix Spike % Rec.  | 96.000  | %     |                |
|           | 1,1-Dichloroethylene | Sample Amount        | <0.003  | mg/kg |                |
|           |                      | Matrix Spk Amt Added | 0.125   | mg/kg |                |
|           |                      | MS Amt Measured      | 0.128   | mg/kg |                |
|           |                      | Matrix Spike % Rec.  | 102.400 | %     |                |
|           | Chlorobenzene        | Sample Amount        | <0.003  | mg/kg |                |
|           |                      | Matrix Spk Amt Added | 0.125   | mg/kg |                |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 12 of 19

QC Batch Number: GCMS/VOL-1294

| Sample Id   | Analysis             | QC Analysis         | Values  | Units | Limits         |
|-------------|----------------------|---------------------|---------|-------|----------------|
| -----       | -----                | -----               | -----   | ----- | -----          |
|             |                      | MS Amt Measured     | 0.132   | mg/kg |                |
|             |                      | Matrix Spike % Rec. | 105.560 | %     |                |
|             | d4-12-Dichloroethane | Surrogate Recovery  | 119.200 | %     | 56.000-128.000 |
|             | d8-Toluene (8240 dry | Surrogate Recovery  | 94.920  | %     | 65.000-113.000 |
|             | Bromofluorobenzene   | Surrogate Recovery  | 92.320  | %     | 62.000-137.000 |
| BLANK-07956 | Acetone              | Blank               | <0.080  | mg/kg |                |
|             | Benzene              | Blank               | <0.003  | mg/kg |                |
|             | Carbon Tetrachloride | Blank               | <0.002  | mg/kg |                |
|             | Chloroform           | Blank               | <0.004  | mg/kg |                |
|             | 1,2-Dichloroethane   | Blank               | <0.004  | mg/kg |                |
|             | 1,4-Dichlorobenzene  | Blank               | <0.004  | mg/kg |                |
|             | Ethyl Benzene        | Blank               | <0.003  | mg/kg |                |
|             | 2-Butanone (MEK)     | Blank               | <0.060  | mg/kg |                |
|             | 4-Methyl-2-Pentanone | Blank               | <0.044  | mg/kg |                |
|             | Styrene              | Blank               | <0.004  | mg/kg |                |
|             | Tetrachloroethylene  | Blank               | <0.002  | mg/kg |                |
|             | Toluene              | Blank               | <0.004  | mg/kg |                |
|             | 1,1,1-Trichloroethan | Blank               | <0.004  | mg/kg |                |
|             | Trichloroethylene    | Blank               | <0.005  | mg/kg |                |
|             | Trichlorofluorometha | Blank               | <0.004  | mg/kg |                |
|             | o&p-Xylene           | Blank               | <0.002  | mg/kg |                |
|             | m-Xylene             | Blank               | <0.006  | mg/kg |                |
|             | 1,2-Dichlorobenzene  | Blank               | <0.004  | mg/kg |                |
|             | 1,3-Dichlorobenzene  | Blank               | <0.003  | mg/kg |                |
|             | 1,1-Dichloroethane   | Blank               | <0.004  | mg/kg |                |
|             | 1,1-Dichloroethylene | Blank               | <0.003  | mg/kg |                |
|             | Methyl tert-Butyl Et | Blank               | <0.004  | mg/kg |                |
|             | t-1,2-Dichloroethyle | Blank               | <0.004  | mg/kg |                |
|             | Vinyl Chloride       | Blank               | <0.002  | mg/kg |                |
|             | Methylene Chloride   | Blank               | <0.015  | mg/kg |                |
|             | Chlorobenzene        | Blank               | <0.003  | mg/kg |                |
|             | Chloromethane        | Blank               | <0.006  | mg/kg |                |
|             | Bromomethane         | Blank               | <0.006  | mg/kg |                |
|             | Chloroethane         | Blank               | <0.004  | mg/kg |                |
|             | cis-1,3-Dichloroprop | Blank               | <0.002  | mg/kg |                |
|             | t-1,3-Dichloropropen | Blank               | <0.002  | mg/kg |                |
|             | Chlorodibromomethane | Blank               | <0.002  | mg/kg |                |
|             | 1,1,2-Trichloroethan | Blank               | <0.004  | mg/kg |                |
|             | 2-Chloroethylvinylet | Blank               | <0.048  | mg/kg |                |

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 13 of 19

QC Batch Number: GCMS/VOL-1294

| Sample Id | Analysis             | QC Analysis | Values | Units | Limits |
|-----------|----------------------|-------------|--------|-------|--------|
| -----     | -----                | -----       | -----  | ----- | -----  |
|           | Bromoform            | Blank       | <0.006 | mg/kg |        |
|           | 1,1,2,2-Tetrachloroe | Blank       | <0.007 | mg/kg |        |
|           | Dibromomethane       | Blank       | <0.006 | mg/kg |        |
|           | 1,2-Dichloropropane  | Blank       | <0.003 | mg/kg |        |
|           | 1,2,3-Trichloropropa | Blank       | <0.006 | mg/kg |        |
|           | Dichlorodifluorometh | Blank       | <0.005 | mg/kg |        |
|           | Iodomethane          | Blank       | <0.004 | mg/kg |        |
|           | Acrolein             | Blank       | <0.100 | mg/kg |        |
|           | Acrylonitrile        | Blank       | <0.038 | mg/kg |        |
|           | Carbon Disulfide     | Blank       | <0.002 | mg/kg |        |
|           | Vinyl Acetate        | Blank       | <0.082 | mg/kg |        |
|           | 2-Hexanone           | Blank       | <0.048 | mg/kg |        |
|           | t-1,4-Dichloro-2-But | Blank       | <0.010 | mg/kg |        |
|           | Ethyl Methacrylate   | Blank       | <0.004 | mg/kg |        |
|           | c-1,4-Dichloro-2-But | Blank       | <0.012 | mg/kg |        |
|           | Bromodichloromethane | Blank       | <0.002 | mg/kg |        |

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike DuplicatesBATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 14 of 19

QC Batch Number: HG-0494

| Sample Id     | Analysis | QC Analysis          | Values  | Units | Limits |
|---------------|----------|----------------------|---------|-------|--------|
| -----         | -----    | -----                | -----   | ----- | -----  |
| LFBLANK-03956 | Mercury  | Lab Fort Blank Amt.  | 0.200   | mg/kg |        |
|               |          | Lab Fort Blk. Found  | 0.230   | mg/kg |        |
|               |          | Lab Fort Blk. % Rec. | 115.000 | %     |        |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 15 of 19

QC Batch Number: ICP-1817

| Sample Id | Analysis  | QC Analysis          | Values | Units | Limits |
|-----------|-----------|----------------------|--------|-------|--------|
| -----     | -----     | -----                | -----  | ----- | -----  |
| 97809239  | Silver    | Sample Amount        | <0.50  | mg/kg |        |
|           |           | Duplicate Value      | 0.00   | mg/kg |        |
|           |           | Sample Amount        | <0.50  | mg/kg |        |
|           |           | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           |           | MS Amt Measured      | 86.15  | mg/kg |        |
|           |           | Matrix Spike % Rec.  | 86.15  | %     |        |
|           | Arsenic   | Sample Amount        | 5.07   | mg/kg |        |
|           |           | Duplicate Value      | 0.00   | mg/kg |        |
|           |           | Duplicate RPD        | 200.00 | %     |        |
|           |           | Sample Amount        | 5.07   | mg/kg |        |
|           |           | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           |           | MS Amt Measured      | 88.30  | mg/kg |        |
|           |           | Matrix Spike % Rec.  | 83.23  | %     |        |
|           | Beryllium | Sample Amount        | 0.53   | mg/kg |        |
|           |           | Duplicate Value      | 0.56   | mg/kg |        |
|           |           | Duplicate RPD        | 5.50   | %     |        |
|           |           | Sample Amount        | 0.53   | mg/kg |        |
|           |           | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           |           | MS Amt Measured      | 97.20  | mg/kg |        |
|           |           | Matrix Spike % Rec.  | 96.67  | %     |        |
|           | Cadmium   | Sample Amount        | 0.06   | mg/kg |        |
|           |           | Duplicate Value      | 0.00   | mg/kg |        |
|           |           | Duplicate RPD        | 200.00 | %     |        |
|           |           | Sample Amount        | 0.06   | mg/kg |        |
|           |           | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           |           | MS Amt Measured      | 87.75  | mg/kg |        |
|           |           | Matrix Spike % Rec.  | 87.70  | %     |        |
|           | Chromium  | Sample Amount        | 14.78  | mg/kg |        |
|           |           | Duplicate Value      | 13.72  | mg/kg |        |
|           |           | Duplicate RPD        | 7.40   | %     |        |
|           |           | Sample Amount        | 14.78  | mg/kg |        |
|           |           | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           |           | MS Amt Measured      | 104.60 | mg/kg |        |
|           |           | Matrix Spike % Rec.  | 89.82  | %     |        |
|           | Copper    | Sample Amount        | 14.85  | mg/kg |        |
|           |           | Duplicate Value      | 14.60  | mg/kg |        |
|           |           | Duplicate RPD        | 1.70   | %     |        |
|           |           | Sample Amount        | 14.85  | mg/kg |        |
|           |           | Matrix Spk Amt Added | 100.00 | mg/kg |        |

**QC SUMMARY REPORT**

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 16 of 19

QC Batch Number: ICP-1817

| Sample Id | Analysis | QC Analysis          | Values | Units | Limits |
|-----------|----------|----------------------|--------|-------|--------|
| -----     | -----    | -----                | -----  | ----- | -----  |
|           | Nickel   | MS Amt Measured      | 102.40 | mg/kg |        |
|           |          | Matrix Spike % Rec.  | 87.55  | %     |        |
|           |          | Sample Amount        | 12.36  | mg/kg |        |
|           |          | Duplicate Value      | 12.12  | mg/kg |        |
|           |          | Duplicate RPD        | 1.96   | %     |        |
|           |          | Sample Amount        | 12.36  | mg/kg |        |
|           |          | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           | Lead     | MS Amt Measured      | 100.70 | mg/kg |        |
|           |          | Matrix Spike % Rec.  | 88.34  | %     |        |
|           |          | Sample Amount        | 7.84   | mg/kg |        |
|           |          | Duplicate Value      | 8.70   | mg/kg |        |
|           |          | Duplicate RPD        | 10.40  | %     |        |
|           |          | Sample Amount        | 7.84   | mg/kg |        |
|           |          | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           | Antimony | MS Amt Measured      | 94.30  | mg/kg |        |
|           |          | Matrix Spike % Rec.  | 86.46  | %     |        |
|           |          | Sample Amount        | <2.50  | mg/kg |        |
|           |          | Duplicate Value      | 0.00   | mg/kg |        |
|           |          | Sample Amount        | <2.50  | mg/kg |        |
|           |          | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           | Selenium | MS Amt Measured      | 59.80  | mg/kg |        |
|           |          | Matrix Spike % Rec.  | 59.80  | %     |        |
|           |          | Sample Amount        | <5.00  | mg/kg |        |
|           |          | Duplicate Value      | 6.43   | mg/kg |        |
|           |          | Duplicate RPD        | 200.00 | %     |        |
|           |          | Sample Amount        | <5.00  | mg/kg |        |
|           |          | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           | Thallium | MS Amt Measured      | 93.70  | mg/kg |        |
|           |          | Matrix Spike % Rec.  | 93.70  | %     |        |
|           |          | Sample Amount        | <10.00 | mg/kg |        |
|           |          | Duplicate Value      | 0.00   | mg/kg |        |
|           |          | Sample Amount        | <10.00 | mg/kg |        |
|           |          | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           | Zinc     | MS Amt Measured      | 85.65  | mg/kg |        |
|           |          | Matrix Spike % Rec.  | 85.65  | %     |        |
|           |          | Sample Amount        | 39.74  | mg/kg |        |
|           |          | Duplicate Value      | 36.26  | mg/kg |        |
|           |          | Duplicate RPD        | 9.18   | %     |        |
|           |          | Sample Amount        | 39.74  | mg/kg |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 17 of 19

QC Batch Number: ICP-1817

| Sample Id | Analysis | QC Analysis          | Values | Units | Limits |
|-----------|----------|----------------------|--------|-------|--------|
| -----     | -----    | -----                | -----  | ----- | -----  |
|           |          | Matrix Spk Amt Added | 100.00 | mg/kg |        |
|           |          | MS Amt Measured      | 126.30 | mg/kg |        |
|           |          | Matrix Spike % Rec.  | 86.56  | %     |        |

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 18 of 19

QC Batch Number: TPH-0760

| Sample Id    | Analysis             | QC Analysis          | Values  | Units | Limits          |
|--------------|----------------------|----------------------|---------|-------|-----------------|
| -----        | -----                | -----                | -----   | ----- | -----           |
| 97809242     | Total Petroleum Hydr | Sample Amount        | 4916.83 | mg/kg |                 |
|              |                      | Duplicate Value      | 3710.63 | mg/kg |                 |
|              |                      | Duplicate RPD        | 27.96   | %     |                 |
|              |                      | Sample Amount        | 4916.83 | mg/kg |                 |
|              |                      | Matrix Spk Amt Added | 2006.00 | mg/kg |                 |
|              |                      | MS Amt Measured      | 6534.65 | mg/kg |                 |
|              |                      | Matrix Spike % Rec.  | 80.65   | %     | 50.20-124.00    |
| BLANK-07961  | Total Petroleum Hydr | Blank                | <20.00  | mg/kg |                 |
| STDADD-05824 | Total Petroleum Hydr | Standard Measured    | 1777.91 | mg/kg | 1485.00-2475.00 |
|              |                      | Standard Amt Added   | 1960.00 | mg/kg |                 |
|              |                      | Standard % Recovery  | 90.71   | %     |                 |



SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike DuplicatesBATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 05/30/97

Lims Bat #: LIMS-29688

Page 19 of 19

## NOTES:

QC Batch No.: GCMS/SEMI-0738  
Sample ID: 97809239  
Analysis: Phenol - D6  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CONTROL LIMITS DUE TO SAMPLE MATRIX  
INTERFERENCE.

QC Batch No.: GCMS/SEMI-0738  
Sample ID: 97809239  
Analysis: Nitrobenzene - D5  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CONTROL LIMITS DUE TO SAMPLE MATRIX  
INTERFERENCE.

QC Batch No.: GCMS/SEMI-0738  
Sample ID: 97809242  
Analysis: Phenol - D6  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CONTROL LIMITS DUE TO SAMPLE MATRIX  
INTERFERENCE.

QC Batch No.: GCMS/SEMI-0738  
Sample ID: 97809242  
Analysis: 2-Fluorobiphenyl  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CONTROL LIMITS DUE TO SAMPLE MATRIX  
INTERFERENCE.

QC Batch No.: GCMS/SEMI-0738  
Sample ID: 97809242  
Analysis: 2-Fluorophenol  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CONTROL LIMITS DUE TO SAMPLE MATRIX  
INTERFERENCE.



(413) 525-2332  
FAX (413) 525-6405

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

Client Name: Venese Hagen-Brooklyn, Inc.  
Attn: Marc Richards  
Address: 101 Walnut St.  
Woburn, MA 02272  
Site Location: Michelle-Lynn, CT  
Sampled By: Marc Richards  
Call Results: Yes ☐ No ☒  
Fax Results: Yes ☒ No ☐

Telephone: 617-924-1770  
Batch #: 29688  
Project #: 4063  
Client P.O. #: 4063  
Fax #: 617-923-2336

| Field Sample I.D. | Sample Description | Lab #    | DATE SAMPLED    |                | Composite | Grab | MATRIX      |              |           |      |     |       | Preservative (Use Code) | Container (Use Code) | Vcc 8 | TPH 4 | SVC 8 | 13 Residual |
|-------------------|--------------------|----------|-----------------|----------------|-----------|------|-------------|--------------|-----------|------|-----|-------|-------------------------|----------------------|-------|-------|-------|-------------|
|                   |                    |          | Start Date/Time | Stop Date/Time |           |      | WASTE WATER | GROUND WATER | DKG WATER | Soil | Air | Other |                         |                      |       |       |       |             |
| B-1/10-12         | Soil Boring        | 97B09235 | 5/20            |                | X         |      |             |              |           | S    |     |       | 2G                      | X                    | X     | X     |       |             |
| B-2/10-12         |                    | 09236    |                 |                | X         |      |             |              |           | S    |     |       | 2G                      | X                    | X     | X     |       |             |
| B-3/10-12         |                    | 09237    |                 |                | X         |      |             |              |           | S    |     |       | 2G                      | X                    | X     | X     |       |             |
| B-4/10-12         |                    | 09238    |                 |                | X         |      |             |              |           | S    |     |       | G                       | X                    | X     | X     |       |             |
| B-4/10-10         |                    | 09239    |                 |                | X         |      |             |              |           | S    |     |       | 2G                      | X                    | X     | X     | X     |             |
| B-5/10-11         |                    | 09240    |                 |                | X         |      |             |              |           | S    |     |       | 2G                      | X                    | X     | X     |       |             |
| B-7/10-11         |                    | 09241    |                 |                | X         |      |             |              |           | S    |     |       | 2G                      | X                    | X     | X     |       |             |
| B-8/10-10         |                    | 09242    |                 |                | X         |      |             |              |           | S    |     |       | 2G                      | X                    | X     | X     | X     |             |

### CONTAINER CODE

P: PLASTIC (\_\_\_ Size) V = 40 ml vial G = Glass (\_\_\_ size) A = 1000 ml Amber O = Other

Relinquished by: (Signature) Marc Richards Date Time 5:20-97

Relinquished by: (Signature) Michelle-Lynn Date Time 5:20-97

Relinquished by: (Signature) Chris Wilson Date Time 5:20-97

Relinquished by: (Signature) Chris Wilson Date Time 5:20-97

### PRESERVATIVE CODE:

I = ICED N = HNO<sub>3</sub> H = HCl S = NaOH T = Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub> O = OTHER

Turnaround Requested: \_\_\_ 24-Hour \_\_\_ 48-Hour \_\_\_ Normal

Other: \_\_\_ Date Required: \_\_\_

Remarks/Comments:

\*MATRIX OTHER

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

|                                                                                   |  |                                |  |                   |  |
|-----------------------------------------------------------------------------------|--|--------------------------------|--|-------------------|--|
| Client Name: <u>Versar Hanger Breston</u>                                         |  | Telephone: <u>617-924-1770</u> |  | Analysis Required |  |
| Attn: <u>Steve Richards</u>                                                       |  | Batch #: <u>29688</u>          |  |                   |  |
| Address: <u>101 Walnut St</u>                                                     |  | Project #: <u>40163</u>        |  |                   |  |
| Site Location: <u>Waterbury, CT</u>                                               |  | Client P.O. #: <u>40163</u>    |  |                   |  |
| Sampled By: <u>Steve Richards</u>                                                 |  | Fax #: <u>617-923-2336</u>     |  |                   |  |
| Call Results: Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |  |                                |  |                   |  |
| Fax Results: Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>  |  |                                |  |                   |  |

| Field Sample I.D. | Sample Description | Lab #    | DATE SAMPLED    |                | Composite | Grab | MATRIX      |              |           |      |     | Preservative (Use Code) | Container (Use Code) | TPH 418.1 | Succ 8270 | 13 Fract Palmit Methyl | PCB 8280 |
|-------------------|--------------------|----------|-----------------|----------------|-----------|------|-------------|--------------|-----------|------|-----|-------------------------|----------------------|-----------|-----------|------------------------|----------|
|                   |                    |          | Start Date/Time | Stop Date/Time |           |      | WASTE WATER | GROUND WATER | DKG WATER | Soil | Air |                         |                      |           |           |                        |          |
| B-9/9-11          | Soil Boring        | 97B09243 |                 | 5/20           | X         |      |             |              |           |      |     |                         |                      | X         |           |                        |          |
| B-10/6-71         |                    | 09244    |                 |                | X         |      |             |              |           |      |     |                         |                      | X         |           |                        |          |
| B-11/A-61         |                    | 09245    |                 |                | X         |      |             |              |           |      |     |                         |                      | X         |           |                        |          |
| B-12/A-61         |                    | 09246    |                 |                | X         |      |             |              |           |      |     |                         |                      | X         |           |                        |          |
| B-13/6-81         |                    | 09247    |                 | 6              | X         |      |             |              |           |      |     |                         |                      | X         |           |                        |          |

|                                                                                       |                                                                                                            |                                                          |  |
|---------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|--|
| CONTAINER CODE                                                                        |                                                                                                            | PRESERVATIVE CODE:                                       |  |
| P: PLASTIC (___ Size) V = 40 ml vial G = Glass (___ size) A = 1000 ml Amber O = Other | I = ICED N = HNO <sub>3</sub> H = HCl S = NaOH T = Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub> O = OTHER |                                                          |  |
| Relinquished by: (Signature) <u>Steve Richards</u>                                    | Date Time <u>5:20-97</u>                                                                                   | Turnaround Requested: ___ 24-Hour ___ 48-Hour ___ Normal |  |
| Relinquished by: (Signature) <u>Steve Richards</u>                                    | Date Time <u>5:20-97</u>                                                                                   | Remarks/Comments: <u>13 Fract Palmit Methyl</u>          |  |
| Relinquished by: (Signature) <u>Steve Richards</u>                                    | Date Time <u>5:20-97</u>                                                                                   | Date Required: ___                                       |  |



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

REPORT DATE: 06/02/97

PURCHASE ORDER NUMBER: 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29711

JOB NUMBER: 29711

The results of analyses performed on the following samples submitted to the CON-TEST Analytical Laboratory are found in this report

PROJECT LOCATION: MIDDLETOWN, CT

| FIELD SAMPLE # | LAB ID   | MATRIX | SAMPLE DESCRIPTION | TEST             |
|----------------|----------|--------|--------------------|------------------|
| B-15/07'-08'   | 97809377 | SOIL   | SOOL BORING        | 8240 - solid (a) |
| B-15/07'-08'   | 97809377 | SOIL   | SOOL BORING        | 8240 - solid (b) |
| B-15/07'-08'   | 97809377 | SOIL   | SOOL BORING        | tph (mg/kg)      |
| B-16/05'-06'   | 97809378 | SOIL   | SOOL BORING        | 8270-soil bn-2   |
| B-16/05'-06'   | 97809378 | SOIL   | SOOL BORING        | 8270-soil bn1    |
| B-16/05'-06'   | 97809378 | SOIL   | SOOL BORING        | 8270-soil-acid   |
| B-16/05'-06'   | 97809378 | SOIL   | SOOL BORING        | tph (mg/kg)      |
| B-18/05'-07'   | 97809379 | SOIL   | SOOL BORING        | 8240 - solid (a) |
| B-18/05'-07'   | 97809379 | SOIL   | SOOL BORING        | 8240 - solid (b) |
| B-18/05'-07'   | 97809379 | SOIL   | SOOL BORING        | 8270-soil bn-2   |
| B-18/05'-07'   | 97809379 | SOIL   | SOOL BORING        | 8270-soil bn1    |
| B-18/05'-07'   | 97809379 | SOIL   | SOOL BORING        | 8270-soil-acid   |
| B-18/05'-07'   | 97809379 | SOIL   | SOOL BORING        | metals(13pp)socp |
| B-18/05'-07'   | 97809379 | SOIL   | SOOL BORING        | tph (mg/kg)      |
| SUR-01         | 97809375 | SOIL   | HAND AUGER         | 8270-soil bn-2   |
| SUR-01         | 97809375 | SOIL   | HAND AUGER         | 8270-soil bn1    |
| SUR-01         | 97809375 | SOIL   | HAND AUGER         | 8270-soil-acid   |
| SUR-01         | 97809375 | SOIL   | HAND AUGER         | metals(13pp)socp |
| SUR-01         | 97809375 | SOIL   | HAND AUGER         | pcb - soil       |
| SUR-01         | 97809375 | SOIL   | HAND AUGER         | tph (mg/kg)      |
| SUR-02         | 97809376 | SOIL   | HAND AUGER         | 8270-soil bn-2   |
| SUR-02         | 97809376 | SOIL   | HAND AUGER         | 8270-soil bn1    |
| SUR-02         | 97809376 | SOIL   | HAND AUGER         | 8270-soil-acid   |
| SUR-02         | 97809376 | SOIL   | HAND AUGER         | metals(13pp)socp |
| SUR-02         | 97809376 | SOIL   | HAND AUGER         | pcb - soil       |
| SUR-02         | 97809376 | SOIL   | HAND AUGER         | tph (mg/kg)      |



39 Spruce Street • 2nd Floor • East longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.

REPORT DATE: 06/02/97

101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

PURCHASE ORDER NUMBER: 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29711  
JOB NUMBER: 29711

| FIELD SAMPLE # | LAB ID | MATRIX | SAMPLE DESCRIPTION | TEST |
|----------------|--------|--------|--------------------|------|
|----------------|--------|--------|--------------------|------|

The CON-TEST Environmental Laboratory operates under the following certifications and accreditations:

|                             |                              |
|-----------------------------|------------------------------|
| AIHA 308                    | AIHA ELLAP (LEAD) 6838       |
| MASSACHUSETTS MA100         | MAINE (POTABLE/NON-POTABLE)  |
| CONNECTICUT PH-0567         | VERMONT DOH (LEAD) No. 15036 |
| NEW YORK ELAP 10899         | RHODE ISLAND (LIC. No. 112)  |
| OHIO (ENVIRO. LEAD) # 10005 |                              |
| NEW HAMPSHIRE 2516          |                              |

I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document.

*Edward Denson* 6/3/97

SIGNATURE

DATE

Tod Kopyscinski  
Director of Operations

Edward Denson  
Technical Director

MARC RICHARDS

VANASSE HANGEN BRUSTLIN, INC.

101 WALNUT STREET

WATERTOWN, MA 02272

Purchase Order Number: 40163

06/02/97

page 1 of 24

Project Location: MIDDLETOWN, CT

Date Received: 05/21/97

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOIL BORING

B-15/07'-08'

|                         | Units | 97809377 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-------------------------|-------|----------|---------------|---------|-------|------------|-----|
| -----                   | ----- | -----    | -----         | -----   | ---   | -----      | --- |
| Acetone                 | mg/kg | ND       | 05/30/97      | WSD     | 0.080 |            |     |
| Acrolein                | mg/kg | ND       | 05/30/97      | WSD     | 0.100 |            |     |
| Acrylonitrile           | mg/kg | ND       | 05/30/97      | WSD     | 0.038 |            |     |
| Benzene                 | mg/kg | ND       | 05/30/97      | WSD     | 0.003 |            |     |
| Bromodichloromethane    | mg/kg | ND       | 05/30/97      | WSD     | 0.002 |            |     |
| Bromomethane            | mg/kg | ND       | 05/30/97      | WSD     | 0.006 |            |     |
| Bromoform               | mg/kg | ND       | 05/30/97      | WSD     | 0.006 |            |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/30/97      | WSD     | 0.060 |            |     |
| Carbon Disulfide        | mg/kg | ND       | 05/30/97      | WSD     | 0.002 |            |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/30/97      | WSD     | 0.002 |            |     |
| Chlorobenzene           | mg/kg | ND       | 05/30/97      | WSD     | 0.003 |            |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/30/97      | WSD     | 0.002 |            |     |
| Chloroethane            | mg/kg | ND       | 05/30/97      | WSD     | 0.004 |            |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/30/97      | WSD     | 0.048 |            |     |
| Chloroform              | mg/kg | ND       | 05/30/97      | WSD     | 0.004 |            |     |
| Chloromethane           | mg/kg | ND       | 05/30/97      | WSD     | 0.006 |            |     |
| Dibromomethane          | mg/kg | ND       | 05/30/97      | WSD     | 0.006 |            |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/30/97      | WSD     | 0.004 |            |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/30/97      | WSD     | 0.003 |            |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/30/97      | WSD     | 0.004 |            |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/30/97      | WSD     | 0.012 |            |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/30/97      | WSD     | 0.010 |            |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/30/97      | WSD     | 0.005 |            |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/30/97      | WSD     | 0.004 |            |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/30/97      | WSD     | 0.004 |            |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/30/97      | WSD     | 0.003 |            |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/30/97      | WSD     | 0.004 |            |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/30/97      | WSD     | 0.003 |            |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/30/97      | WSD     | 0.002 |            |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/30/97      | WSD     | 0.002 |            |     |
| Ethyl Benzene           | mg/kg | ND       | 05/30/97      | WSD     | 0.003 |            |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/30/97      | WSD     | 0.004 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BD = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOOL BORING

B-15/07'-08'

|                                | Units | 97809377 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| -Hexanone                      | mg/kg | ND       | 05/30/97         | WSD     | 0.048 |               |     |
| odomethane                     | mg/kg | ND       | 05/30/97         | WSD     | 0.004 |               |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/30/97         | WSD     | 0.004 |               |     |
| Methylene Chloride             | mg/kg | ND       | 05/30/97         | WSD     | 0.015 |               |     |
| -Methyl-2-Pentanone (MIBK)     | mg/kg | ND       | 05/30/97         | WSD     | 0.044 |               |     |
| Styrene                        | mg/kg | ND       | 05/30/97         | WSD     | 0.004 |               |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/30/97         | WSD     | 0.007 |               |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/30/97         | WSD     | 0.002 |               |     |
| Toluene                        | mg/kg | ND       | 05/30/97         | WSD     | 0.004 |               |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/30/97         | WSD     | 0.004 |               |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/30/97         | WSD     | 0.004 |               |     |
| Trichloroethylene              | mg/kg | ND       | 05/30/97         | WSD     | 0.005 |               |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/30/97         | WSD     | 0.004 |               |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/30/97         | WSD     | 0.006 |               |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/30/97         | WSD     | 0.082 |               |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/30/97         | WSD     | 0.002 |               |     |
| m-Xylene                       | mg/kg | ND       | 05/30/97         | WSD     | 0.006 |               |     |
| o&p-Xylene                     | mg/kg | ND       | 05/30/97         | WSD     | 0.002 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOOL BORING

B-18/05'-07'

|                         | Units | 97809379 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-------------------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----                   | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Acetone                 | mg/kg | ND       | 05/30/97         | WSD     | 6.44  |               |     |
| Acrolein                | mg/kg | ND       | 05/30/97         | WSD     | 8.00  |               |     |
| Acrylonitrile           | mg/kg | ND       | 05/30/97         | WSD     | 3.04  |               |     |
| Benzene                 | mg/kg | ND       | 05/30/97         | WSD     | 0.240 |               |     |
| Bromodichloromethane    | mg/kg | ND       | 05/30/97         | WSD     | 0.160 |               |     |
| Bromomethane            | mg/kg | ND       | 05/30/97         | WSD     | 0.480 |               |     |
| Bromoform               | mg/kg | ND       | 05/30/97         | WSD     | 0.480 |               |     |
| 2-Butanone (MEK)        | mg/kg | ND       | 05/30/97         | WSD     | 4.80  |               |     |
| Carbon Disulfide        | mg/kg | ND       | 05/30/97         | WSD     | 0.200 |               |     |
| Carbon Tetrachloride    | mg/kg | ND       | 05/30/97         | WSD     | 0.200 |               |     |
| Chlorobenzene           | mg/kg | ND       | 05/30/97         | WSD     | 0.240 |               |     |
| Chlorodibromomethane    | mg/kg | ND       | 05/30/97         | WSD     | 0.200 |               |     |
| Chloroethane            | mg/kg | ND       | 05/30/97         | WSD     | 0.320 |               |     |
| 2-Chloroethylvinylether | mg/kg | ND       | 05/30/97         | WSD     | 3.84  |               |     |
| Chloroform              | mg/kg | ND       | 05/30/97         | WSD     | 0.320 |               |     |
| Chloromethane           | mg/kg | ND       | 05/30/97         | WSD     | 0.480 |               |     |
| Dibromomethane          | mg/kg | ND       | 05/30/97         | WSD     | 0.440 |               |     |
| 1,2-Dichlorobenzene     | mg/kg | ND       | 05/30/97         | WSD     | 0.320 |               |     |
| 1,3-Dichlorobenzene     | mg/kg | ND       | 05/30/97         | WSD     | 0.240 |               |     |
| 1,4-Dichlorobenzene     | mg/kg | ND       | 05/30/97         | WSD     | 0.320 |               |     |
| c-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/30/97         | WSD     | 0.960 |               |     |
| t-1,4-Dichloro-2-Butene | mg/kg | ND       | 05/30/97         | WSD     | 0.840 |               |     |
| Dichlorodifluoromethane | mg/kg | ND       | 05/30/97         | WSD     | 0.400 |               |     |
| 1,1-Dichloroethane      | mg/kg | ND       | 05/30/97         | WSD     | 0.280 |               |     |
| 1,2-Dichloroethane      | mg/kg | ND       | 05/30/97         | WSD     | 0.360 |               |     |
| 1,1-Dichloroethylene    | mg/kg | ND       | 05/30/97         | WSD     | 0.240 |               |     |
| t-1,2-Dichloroethylene  | mg/kg | ND       | 05/30/97         | WSD     | 0.320 |               |     |
| 1,2-Dichloropropane     | mg/kg | ND       | 05/30/97         | WSD     | 0.240 |               |     |
| cis-1,3-Dichloropropene | mg/kg | ND       | 05/30/97         | WSD     | 0.200 |               |     |
| t-1,3-Dichloropropene   | mg/kg | ND       | 05/30/97         | WSD     | 0.160 |               |     |
| Ethyl Benzene           | mg/kg | ND       | 05/30/97         | WSD     | 0.240 |               |     |
| Ethyl Methacrylate      | mg/kg | ND       | 05/30/97         | WSD     | 0.320 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or

regulatory level for comparison with data to

determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOOL BORING

B-18/05'-07'

|                                | Units | 97B09379 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|--------------------------------|-------|----------|---------------|---------|-------|------------|-----|
| -----                          | ----- | -----    | -----         | -----   | ---   | -----      | --- |
| n-Hexanone                     | mg/kg | ND       | 05/30/97      | WSD     | 3.88  |            |     |
| Iodomethane                    | mg/kg | ND       | 05/30/97      | WSD     | 0.320 |            |     |
| Methyl tert-Butyl Ether (MTBE) | mg/kg | ND       | 05/30/97      | WSD     | 0.320 |            |     |
| Methylene Chloride             | mg/kg | BDL      | 05/30/97      | WSD     | 1.20  |            |     |
| n-Methyl-2-Pentanone (MIBK)    | mg/kg | ND       | 05/30/97      | WSD     | 3.52  |            |     |
| Styrene                        | mg/kg | ND       | 05/30/97      | WSD     | 0.280 |            |     |
| 1,1,2,2-Tetrachloroethane      | mg/kg | ND       | 05/30/97      | WSD     | 0.560 |            |     |
| Tetrachloroethylene            | mg/kg | ND       | 05/30/97      | WSD     | 0.160 |            |     |
| Toluene                        | mg/kg | ND       | 05/30/97      | WSD     | 0.280 |            |     |
| 1,1,1-Trichloroethane          | mg/kg | ND       | 05/30/97      | WSD     | 0.360 |            |     |
| 1,1,2-Trichloroethane          | mg/kg | ND       | 05/30/97      | WSD     | 0.280 |            |     |
| Trichloroethylene              | mg/kg | ND       | 05/30/97      | WSD     | 0.400 |            |     |
| Trichlorofluoromethane         | mg/kg | ND       | 05/30/97      | WSD     | 0.280 |            |     |
| 1,2,3-Trichloropropane         | mg/kg | ND       | 05/30/97      | WSD     | 0.520 |            |     |
| Vinyl Acetate                  | mg/kg | ND       | 05/30/97      | WSD     | 6.56  |            |     |
| Vinyl Chloride                 | mg/kg | ND       | 05/30/97      | WSD     | 0.120 |            |     |
| m-Xylene                       | mg/kg | ND       | 05/30/97      | WSD     | 0.520 |            |     |
| o&p-Xylene                     | mg/kg | ND       | 05/30/97      | WSD     | 0.200 |            |     |

Analytical Method(s):

SW846 8240

SAMPLES ARE CONCENTRATED BY PURGE AND TRAP, FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOIL BORING

B-16/05'-06'

|                             | Units | 97B09378 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                       | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Acenaphthene                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Acenaphthylene              | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Aniline                     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Anthracene                  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Benidene                    | mg/kg | ND       | 05/27/97      | WSD     | 2.33 |            |     |
| Benzoic Acid                | mg/kg | ND       | 05/27/97      | WSD     | 1.00 |            |     |
| Benzo(a)anthracene          | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Benzo(a)pyrene              | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Benzo(b)fluoranthene        | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/27/97      | WSD     | 1.00 |            |     |
| Benzo(k)fluoranthene        | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Butylbenzylphthalate        | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Chrysene                    | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Dibenzofuran                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Diethylphthalate            | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Dimethylphthalate           | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Di-n-butylphthalate         | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Di-n-octylphthalate         | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOOL BORING

B-16/05'-06'

|                            | Units | 97809378 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                      | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Fluoranthene               | mg/kg | BDL      | 05/27/97         | WSD     | 0.33 |               |     |
| Fluorene                   | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Hexachloroethane           | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Isophorone                 | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Methylnaphthalene        | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Naphthalene                | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Nitrobenzene               | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Phenanthrene               | mg/kg | BDL      | 05/27/97         | WSD     | 0.33 |               |     |
| Pyrene                     | mg/kg | BDL      | 05/27/97         | WSD     | 1.00 |               |     |
| Pyridine                   | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOOL BORING

B-18/05'-07'

|                             | Units | 97B09379 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                       | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Acenaphthene                | mg/kg | 0.64     | 05/27/97      | WSD     | 0.33 |            |     |
| Acenaphthylene              | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Aniline                     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Anthracene                  | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Benzenidene                 | mg/kg | ND       | 05/27/97      | WSD     | 2.33 |            |     |
| Benzoic Acid                | mg/kg | ND       | 05/27/97      | WSD     | 1.00 |            |     |
| Benzo(a)anthracene          | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Benzo(a)pyrene              | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Benzo(b)fluoranthene        | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/27/97      | WSD     | 1.00 |            |     |
| Benzo(k)fluoranthene        | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroethyl)ether     | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Butylbenzylphthalate        | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Chrysene                    | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Dibenzofuran                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/27/97      | WSD     | 0.67 |            |     |
| Diethylphthalate            | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Dimethylphthalate           | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |
| Di-n-butylphthalate         | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Di-n-octylphthalate         | mg/kg | BDL      | 05/27/97      | WSD     | 0.67 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

 LIMS-BAT #: LIMS-29711  
 Job Number: 29711  
 Sample Matrix: SOIL

 Sampled: 05/21/97  
 SOOL BORING  
 B-18/05'-07'

|                            | Units | 97809379 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                      | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Fluoranthene               | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Fluorene                   | mg/kg | 2.11     | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Isophorone                 | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2-Methylnaphthalene        | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Naphthalene                | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 3-Nitroaniline             | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Phenanthrene               | mg/kg | 2.17     | 05/27/97      | WSD     | 0.33 |            |     |
| Pyrene                     | mg/kg | BDL      | 05/27/97      | WSD     | 1.00 |            |     |
| Pyridine                   | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

HAND AUGER

SUR-01

|                             | Units | 97809375 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| Acenaphthene                | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Acenaphthylene              | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Aniline                     | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Anthracene                  | mg/kg | BDL      | 05/27/97         | WSD     | 10.0 |               |     |
| Benzidene                   | mg/kg | ND       | 05/27/97         | WSD     | 70.0 |               |     |
| Benzoic Acid                | mg/kg | ND       | 05/27/97         | WSD     | 30.0 |               |     |
| Benzo(a)anthracene          | mg/kg | BDL      | 05/27/97         | WSD     | 10.0 |               |     |
| Benzo(a)pyrene              | mg/kg | BDL      | 05/27/97         | WSD     | 20.0 |               |     |
| Benzo(b)fluoranthene        | mg/kg | 10.4     | 05/27/97         | WSD     | 10.0 |               |     |
| Benzo(g,h,i)perylene        | mg/kg | ND       | 05/27/97         | WSD     | 30.0 |               |     |
| Benzo(k)fluoranthene        | mg/kg | BDL      | 05/27/97         | WSD     | 20.0 |               |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/27/97         | WSD     | 20.0 |               |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | BDL      | 05/27/97         | WSD     | 10.0 |               |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Butylbenzylphthalate        | mg/kg | ND       | 05/27/97         | WSD     | 20.0 |               |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/27/97         | WSD     | 20.0 |               |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Chrysene                    | mg/kg | BDL      | 05/27/97         | WSD     | 20.0 |               |     |
| Dibenzofuran                | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Dibenz(a,h)anthracene       | mg/kg | ND       | 05/27/97         | WSD     | 20.0 |               |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/27/97         | WSD     | 20.0 |               |     |
| Diethylphthalate            | mg/kg | ND       | 05/27/97         | WSD     | 10.0 |               |     |
| Dimethylphthalate           | mg/kg | ND       | 05/27/97         | WSD     | 20.0 |               |     |
| Di-n-butylphthalate         | mg/kg | BDL      | 05/27/97         | WSD     | 10.0 |               |     |
| Di-n-octylphthalate         | mg/kg | ND       | 05/27/97         | WSD     | 20.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

HAND AUGER

SUR-01

|                            | Units | 97B09375 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Fluoranthene               | mg/kg | 13.5     | 05/27/97      | WSD     | 10.0 |            |     |
| Fluorene                   | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Isophorone                 | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Methylnaphthalene        | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Naphthalene                | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| Phenanthrene               | mg/kg | BDL      | 05/27/97      | WSD     | 10.0 |            |     |
| Pyrene                     | mg/kg | BDL      | 05/27/97      | WSD     | 30.0 |            |     |
| Pyridine                   | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/27/97      | WSD     | 10.0 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/02/97

page 11 of 24

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

HAND AUGER

SUR-02

|                             | Units | 97B09376 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                       | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acenaphthene                | mg/kg | BDL      | 05/27/97         | WSD     | 0.33 |               |     |
| Acenaphthylene              | mg/kg | 1.36     | 05/27/97         | WSD     | 0.33 |               |     |
| Aniline                     | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Anthracene                  | mg/kg | 2.18     | 05/27/97         | WSD     | 0.33 |               |     |
| Benidene                    | mg/kg | BDL      | 05/27/97         | WSD     | 2.33 |               |     |
| Benzoic Acid                | mg/kg | ND       | 05/27/97         | WSD     | 1.00 |               |     |
| Benzo(a)anthracene          | mg/kg | 11.7     | 05/27/97         | WSD     | 0.33 |               |     |
| Benzo(a)pyrene              | mg/kg | 14.3     | 05/27/97         | WSD     | 0.67 |               |     |
| Benzo(b)fluoranthene        | mg/kg | 15.0     | 05/27/97         | WSD     | 0.33 |               |     |
| Benzo(g,h,i)perylene        | mg/kg | 6.67     | 05/27/97         | WSD     | 1.00 |               |     |
| Benzo(k)fluoranthene        | mg/kg | 13.1     | 05/27/97         | WSD     | 0.67 |               |     |
| Benzyl Alcohol              | mg/kg | ND       | 05/27/97         | WSD     | 0.67 |               |     |
| Bis(2-chloroethoxy)methane  | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Bis(2-chloroethyl)ether     | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Bis(2-chloroisopropyl)ether | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Bis(2-ethylhexyl)phthalate  | mg/kg | BDL      | 05/27/97         | WSD     | 0.33 |               |     |
| 4-Bromophenylphenylether    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Butylbenzylphthalate        | mg/kg | BDL      | 05/27/97         | WSD     | 0.67 |               |     |
| 4-Chloroaniline             | mg/kg | ND       | 05/27/97         | WSD     | 0.67 |               |     |
| 2-Chloronaphthalene         | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 4-Chlorophenylphenylether   | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Chrysene                    | mg/kg | 14.7     | 05/27/97         | WSD     | 0.67 |               |     |
| Dibenzofuran                | mg/kg | 0.37     | 05/27/97         | WSD     | 0.33 |               |     |
| Dibenz(a,h)anthracene       | mg/kg | 1.83     | 05/27/97         | WSD     | 0.67 |               |     |
| 1,2-Dichlorobenzene         | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 1,3-Dichlorobenzene         | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 1,4-Dichlorobenzene         | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 3,3'-Dichlorobenzidine      | mg/kg | ND       | 05/27/97         | WSD     | 0.67 |               |     |
| Diethylphthalate            | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Dimethylphthalate           | mg/kg | ND       | 05/27/97         | WSD     | 0.67 |               |     |
| Di-n-butylphthalate         | mg/kg | BDL      | 05/27/97         | WSD     | 0.33 |               |     |
| Di-n-octylphthalate         | mg/kg | ND       | 05/27/97         | WSD     | 0.67 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.



06/02/97

page 12 of 24

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

HAND AUGER

SUR-02

|                            | Units | 97809376 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                      | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| 2,4-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2,6-Dinitrotoluene         | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,2-Diphenylhydrazine      | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Fluoranthene               | mg/kg | 21.3     | 05/27/97      | WSD     | 0.33 |            |     |
| Fluorene                   | mg/kg | 0.56     | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorobenzene          | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorobutadiene        | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachlorocyclopentadiene  | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Hexachloroethane           | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Indeno(1,2,3-cd)pyrene     | mg/kg | 10.0     | 05/27/97      | WSD     | 0.33 |            |     |
| Isophorone                 | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 2-Methylnaphthalene        | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| Naphthalene                | mg/kg | BDL      | 05/27/97      | WSD     | 0.33 |            |     |
| 2-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 3-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 4-Nitroaniline             | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Nitrobenzene               | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitrosodimethylamine     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitrosodiphenylamine     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| N-Nitroso-di-n-propylamine | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| Phenanthrene               | mg/kg | 9.57     | 05/27/97      | WSD     | 0.33 |            |     |
| Pyrene                     | mg/kg | 25.1     | 05/27/97      | WSD     | 1.00 |            |     |
| Pyridine                   | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |
| 1,2,4-Trichlorobenzene     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 |            |     |

Analytical Method(s):

SW846 8270

 SAMPLES ARE EXTRACTED IN METHYLENE CHLORIDE/ACETONE AND  
 FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/02/97

page 13 of 24

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOOL BORING

B-16/05'-06'

|                                  | Units | 97809378 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/27/97         | WSD     | 0.67 |               |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/27/97         | WSD     | 1.33 |               |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Pentachlorophenol                | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Phenol                           | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |

Sampled: 05/21/97

SOOL BORING

B-18/05'-07'

|                                  | Units | 97809379 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | mg/kg | BDL      | 05/27/97         | WSD     | 0.67 |               |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/27/97         | WSD     | 1.33 |               |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |

MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/02/97

page 14 of 24

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOOL BORING

B-18/05'-07'

|                       | Units | 97809379 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------|-------|----------|---------------|---------|------|------------|-----|
| Pentachlorophenol     | mg/kg | ND       | 05/27/97      | WSD     | 0.33 | -----      | --- |
| Phenol                | mg/kg | ND       | 05/27/97      | WSD     | 0.33 | -----      | --- |
| 2,4,5-Trichlorophenol | mg/kg | ND       | 05/27/97      | WSD     | 0.33 | -----      | --- |
| 2,4,6-Trichlorophenol | mg/kg | ND       | 05/27/97      | WSD     | 0.33 | -----      | --- |

Sampled: 05/21/97

HAND AUGER

SUR-01

|                                  | Units | 97809375 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------------|-------|----------|---------------|---------|------|------------|-----|
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/27/97      | WSD     | 20.0 | -----      | --- |
| 2-Chlorophenol                   | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/27/97      | WSD     | 40.0 | -----      | --- |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| 2-Nitrophenol                    | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| 4-Nitrophenol                    | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| Pentachlorophenol                | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| Phenol                           | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/27/97      | WSD     | 10.0 | -----      | --- |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/02/97  
 page 15 of 24

Purchase Order Number: 40163

 LIMS-BAT #: LIMS-29711  
 Job Number: 29711  
 Sample Matrix: SOIL

 Sampled: 05/21/97  
 HAND AUGER  
 SUR-02

|                                  | Units | 97809376 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | mg/kg | ND       | 05/27/97         | WSD     | 0.67 |               |     |
| 2-Chlorophenol                   | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dichlorophenol               | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dimethylphenol               | mg/kg | ND       | 05/27/97         | WSD     | 1.33 |               |     |
| 4,6-Dinitro-2-methylphenol       | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4-Dinitrophenol                | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Methylphenol (o-cresol)        | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 4-Nitrophenol                    | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Pentachlorophenol                | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| Phenol                           | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4,5-Trichlorophenol            | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |
| 2,4,6-Trichlorophenol            | mg/kg | ND       | 05/27/97         | WSD     | 0.33 |               |     |

## Analytical Method(s):

SW846 8270

 SAMPLES ARE EXTRACTED IN METHYLENE CHLORIDE/ACETONE AND  
 FOLLOWED BY GC/MS TARGET COMPOUND ANALYSIS.

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/02/97

page 16 of 24

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

SOOL BORING

B-18/05'-07'

|           | Units | 97809379 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|-------|---------------|-----|
| -----     | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Antimony  | mg/kg | ND       | 05/28/97         | KLF     | 2.50  |               |     |
| Arsenic   | mg/kg | ND       | 05/28/97         | KLF     | 5.00  |               |     |
| Beryllium | mg/kg | 0.42     | 05/28/97         | KLF     | 0.10  |               |     |
| Cadmium   | mg/kg | 0.06     | 05/28/97         | KLF     | 0.05  |               |     |
| Chromium  | mg/kg | 10.9     | 05/28/97         | KLF     | 0.35  |               |     |
| Copper    | mg/kg | 13.0     | 05/28/97         | KLF     | 0.10  |               |     |
| Lead      | mg/kg | 7.51     | 05/28/97         | KLF     | 2.50  | 1000          | P   |
| Mercury   | mg/kg | ND       | 05/28/97         | APP     | 0.020 |               |     |
| Nickel    | mg/kg | 12.5     | 05/28/97         | KLF     | 0.25  |               |     |
| Selenium  | mg/kg | 6.07     | 05/28/97         | KLF     | 5.00  |               |     |
| Silver    | mg/kg | ND       | 05/28/97         | KLF     | 0.50  |               |     |
| Thallium  | mg/kg | ND       | 05/28/97         | KLF     | 10.0  |               |     |
| Zinc      | mg/kg | 27.5     | 05/28/97         | KLF     | 0.50  |               |     |

Sampled: 05/21/97

HAND AUGER

SUR-01

|           | Units | 97809375 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|-------|---------------|-----|
| -----     | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| Antimony  | mg/kg | ND       | 05/28/97         | KLF     | 2.50  |               |     |
| Arsenic   | mg/kg | 10.4     | 05/28/97         | KLF     | 5.00  |               |     |
| Beryllium | mg/kg | 0.36     | 05/28/97         | KLF     | 0.10  |               |     |
| Cadmium   | mg/kg | 0.98     | 05/28/97         | KLF     | 0.05  |               |     |
| Chromium  | mg/kg | 45.8     | 05/28/97         | KLF     | 0.35  |               |     |
| Copper    | mg/kg | 2400     | 05/28/97         | KLF     | 0.10  |               |     |
| Lead      | mg/kg | 266      | 05/28/97         | KLF     | 2.50  | 1000          | P   |
| Mercury   | mg/kg | 0.073    | 05/28/97         | APP     | 0.020 |               |     |
| Nickel    | mg/kg | 37.0     | 05/28/97         | KLF     | 0.25  |               |     |
| Selenium  | mg/kg | 9.34     | 05/28/97         | KLF     | 5.00  |               |     |
| Silver    | mg/kg | ND       | 05/28/97         | KLF     | 0.50  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/02/97  
page 17 of 24

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711  
Job Number: 29711  
Sample Matrix: SOIL

Sampled: 05/21/97  
HAND AUGER  
SUR-01

|          | Units | 97B09375 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|-------|----------|---------------|---------|------|------------|-----|
| Thallium | mg/kg | ND       | 05/28/97      | KLF     | 10.0 |            |     |
| Zinc     | mg/kg | 944      | 05/28/97      | KLF     | 0.50 |            |     |

Sampled: 05/21/97  
HAND AUGER  
SUR-02

|           | Units | 97B09376 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|-------|------------|-----|
| Antimony  | mg/kg | ND       | 05/28/97      | KLF     | 12.5  |            |     |
| Arsenic   | mg/kg | 18.0     | 05/28/97      | KLF     | 5.00  |            |     |
| Beryllium | mg/kg | 0.47     | 05/28/97      | KLF     | 0.10  |            |     |
| Cadmium   | mg/kg | 0.45     | 05/28/97      | KLF     | 0.05  |            |     |
| Chromium  | mg/kg | 118      | 05/28/97      | KLF     | 0.35  |            |     |
| Copper    | mg/kg | 506      | 05/28/97      | KLF     | 0.10  |            |     |
| Lead      | mg/kg | 132      | 05/28/97      | KLF     | 2.50  | 1000       | P   |
| Mercury   | mg/kg | 0.270    | 05/28/97      | APP     | 0.020 |            |     |
| Nickel    | mg/kg | 84.2     | 05/28/97      | KLF     | 0.25  |            |     |
| Selenium  | mg/kg | 15.3     | 05/28/97      | KLF     | 5.00  |            |     |
| Silver    | mg/kg | ND       | 05/28/97      | KLF     | 2.5   |            |     |
| Thallium  | mg/kg | ND       | 05/28/97      | KLF     | 10.0  |            |     |
| Zinc      | mg/kg | 127      | 05/28/97      | KLF     | 0.50  |            |     |

## Analytical Method(s):

Antimony  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/02/97

page 18 of 24

Arsenic  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Beryllium  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Cadmium  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Chromium  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Copper  
SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Lead  
SW846 3050/6010

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/02/97

page 19 of 24

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Mercury

SW846 3050/7471

SAMPLES ARE DIGESTED WITH ACIDS AND THEN ANALYZED BY  
COLD VAPOR (FLAMELESS) ATOMIC ABSORPTION SPECTROPHOTOMETRY

Nickel

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Selenium

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Silver

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Thallium

SW846 3050/6010

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.





**con-test®**  
ANALYTICAL LABORATORY

39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332

06/02/97

page 20 of 24

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

Zinc

SW846 3050/6010

SAMPLES ARE DIGESTED WITH NITRIC ACID AND THEN ANALYZED BY  
INDUCTIVELY COUPLED PLASMA EMISSION SPECTROSCOPY.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/02/97

page 21 of 24

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711

Job Number: 29711

Sample Matrix: SOIL

Sampled: 05/21/97

HAND AUGER

SUR-01

|               | Units | 97809375 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| PCB 1221      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1232      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1242/1016 | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1248      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1254      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1260      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| Total PCB     | mg/kg | ND       | 05/28/97         | JB      | 0.500 |               |     |

Sampled: 05/21/97

HAND AUGER

SUR-02

|               | Units | 97809376 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|-------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---   | -----         | --- |
| PCB 1221      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1232      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1242/1016 | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1248      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1254      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| PCB 1260      | mg/kg | ND       | 05/28/97         | JB      |       |               |     |
| Total PCB     | mg/kg | ND       | 05/28/97         | JB      | 0.500 |               |     |

Analytical Method(s):

SW846 8080

SAMPLES ARE EXTRACTED INTO HEXANE AND ANALYZED BY GAS CHROMATOGRAPHY  
WITH ELECTRON CAPTURE DETECTION.

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/02/97  
page 22 of 24

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711  
Job Number: 29711  
Sample Matrix: SOIL

Sampled: 05/21/97  
SOOL BORING  
B-15/07'-08'

|                              | Units | 97B09377 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | BDL      | 05/27/97      | AC      | 20.1 |            |     |

Sampled: 05/21/97  
SOOL BORING  
B-16/05'-06'

|                              | Units | 97B09378 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 29.0     | 05/27/97      | AC      | 20.0 |            |     |

Sampled: 05/21/97  
SOOL BORING  
B-18/05'-07'

|                              | Units | 97B09379 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 5200     | 05/27/97      | AC      | 19.7 |            |     |

Sampled: 05/21/97  
HAND AUGER  
SUR-01

|                              | Units | 97B09375 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 1330     | 05/27/97      | AC      | 20.2 |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/02/97  
page 23 of 24

Purchase Order Number: 40163

LIMS-BAT #: LIMS-29711  
Job Number: 29711  
Sample Matrix: SOILSampled: 05/21/97  
HAND AUGER  
SUR-02

|                              | Units | 97B09376 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/kg | 147      | 05/27/97      | AC      | 19.3 |            |     |

Analytical Method(s):

MODIFIED EPA 418.1

INFRA-RED DETERMINATION FOLLOWING EXTRACTION OF HYDROCARBONS INTO  
1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE (FREON 113)MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/02/97

page 24 of 24

The following notes were attached to the reported analysis:

Sample: 97809379

Analysis: Acetone

ELEVATED LIMITS OF DETECTION DUE TO SAMPLE MATRIX.

Sample: 97809375

ELEVATED LIMITS OF DETECTION DUE TO SAMPLE MATRIX INTERFERENCES.

Sample: 97809376

Analysis: Antimony

ELEVATED METHOD DETECTION LIMIT DUE TO MATRIX INTERFERENCES.

Sample: 97809376

Analysis: Silver

ELEVATED METHOD DETECTION LIMIT DUE TO MATRIX INTERFERENCES.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/02/97

Lims Bat #: LIMS-29711

Page 1 of 8

QC Batch Number: GC/ECD-1291

| Sample Id   | Analysis              | QC Analysis          | Values | Units | Limits |
|-------------|-----------------------|----------------------|--------|-------|--------|
| -----       | -----                 | -----                | -----  | ----- | -----  |
| 97809375    | PCB 1232              | Sample Amount        | 0.000  | mg/kg |        |
|             |                       | Duplicate Value      | 0.000  | mg/kg |        |
|             | PCB 1242/1016         | Sample Amount        | 0.000  | mg/kg |        |
|             |                       | Duplicate Value      | 0.000  | mg/kg |        |
|             | PCB 1254              | Sample Amount        | 0.000  | mg/kg |        |
|             |                       | Duplicate Value      | 0.000  | mg/kg |        |
|             | PCB 1260              | Sample Amount        | 0.000  | mg/kg |        |
|             |                       | Duplicate Value      | 0.000  | mg/kg |        |
|             | PCB 1248              | Sample Amount        | 0.000  | mg/kg |        |
|             |                       | Duplicate Value      | 0.000  | mg/kg |        |
|             | PCB 1221              | Sample Amount        | 0.000  | mg/kg |        |
|             |                       | Duplicate Value      | 0.000  | mg/kg |        |
|             | Total PCB             | Sample Amount        | <0.500 | mg/kg |        |
|             |                       | Duplicate Value      | <0.500 | mg/kg |        |
| 97809376    | Dibutylchloroendate ( | Sample Amount        | 72.0   | %     |        |
|             |                       | Duplicate Value      | 82.0   | %     |        |
|             |                       | Duplicate RPD        | 13.0   | %     |        |
|             | PCB 1242/1016         | Sample Amount        | 0.000  | mg/kg |        |
|             |                       | Matrix Spk Amt Added | 24.600 | mg/kg |        |
|             |                       | MS Amt Measured      | 19.987 | mg/kg |        |
|             | Total PCB             | Matrix Spike % Rec.  | 81.248 | %     |        |
|             |                       | Sample Amount        | <0.500 | mg/kg |        |
|             |                       | Matrix Spk Amt Added | 24.600 | mg/kg |        |
|             |                       | MS Amt Measured      | 19.987 | mg/kg |        |
| BLANK-07941 | PCB 1242/1016         | Matrix Spike % Rec.  | 81.248 | %     |        |
|             |                       | Sample Amount        | 0.000  | mg/kg |        |
|             |                       | Matrix Spk Amt Added | 24.600 | mg/kg |        |
|             | PCB 1232              | MS Amt Measured      | 19.987 | mg/kg |        |
|             |                       | Matrix Spike % Rec.  | 81.248 | %     |        |
|             |                       | Sample Amount        | 0.000  | mg/kg |        |
|             | PCB 1254              | Blank                | 0.000  | mg/kg |        |
|             |                       | Blank                | 0.000  | mg/kg |        |
|             |                       | Blank                | 0.000  | mg/kg |        |
|             | PCB 1260              | Blank                | 0.000  | mg/kg |        |
|             |                       | Blank                | 0.000  | mg/kg |        |
|             |                       | Blank                | 0.000  | mg/kg |        |
|             | PCB 1248              | Blank                | 0.000  | mg/kg |        |
|             |                       | Blank                | 0.000  | mg/kg |        |
|             |                       | Blank                | 0.000  | mg/kg |        |
|             | PCB 1221              | Blank                | 0.000  | mg/kg |        |
|             |                       | Blank                | 0.000  | mg/kg |        |
|             |                       | Blank                | 0.000  | mg/kg |        |
|             | Total PCB             | Blank                | <0.025 | mg/kg |        |
|             |                       | Blank                | <0.025 | mg/kg |        |
|             |                       | Blank                | <0.025 | mg/kg |        |
|             | Dibutylchloroendate ( | Blank                | 106.5  | %     |        |
|             |                       | Blank                | 106.5  | %     |        |
|             |                       | Blank                | 106.5  | %     |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/02/97

Lims Bat #: LIMS-29711

Page 2 of 8

QC Batch Number: GCHS/SEMI-0741

| Sample Id   | Analysis             | QC Analysis        | Values | Units | Limits     |
|-------------|----------------------|--------------------|--------|-------|------------|
| -----       | -----                | -----              | -----  | ----- | -----      |
| 97809375    | Phenol - D6 mg/kg re | Surrogate Recovery | 86.4   | %     | 24.0-113.0 |
|             | Nitrobenzene - D5 mg | Surrogate Recovery | 76.7   | %     | 23.0-120.0 |
|             | 2-Fluorobipheny mg/k | Surrogate Recovery | 86.0   | %     | 25.0-121.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 79.8   | %     | 19.0-122.0 |
|             | Terphenyl - D14 mg/k | Surrogate Recovery | 105.8  | %     | 18.0-137.0 |
|             | 2-Fluorophenol mg/kg | Surrogate Recovery | 85.2   | %     | 30.0-115.0 |
| 97809376    | Phenol - D6 mg/kg re | Surrogate Recovery | 102.2  | %     | 24.0-113.0 |
|             | Nitrobenzene - D5 mg | Surrogate Recovery | 98.2   | %     | 23.0-120.0 |
|             | 2-Fluorobipheny mg/k | Surrogate Recovery | 104.6  | %     | 25.0-121.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 90.2   | %     | 19.0-122.0 |
|             | Terphenyl - D14 mg/k | Surrogate Recovery | 101.6  | %     | 18.0-137.0 |
|             | 2-Fluorophenol mg/kg | Surrogate Recovery | 103.3  | %     | 30.0-115.0 |
| 97809378    | Phenol - D6 mg/kg re | Surrogate Recovery | 87.9   | %     | 24.0-113.0 |
|             | Nitrobenzene - D5 mg | Surrogate Recovery | 75.7   | %     | 23.0-120.0 |
|             | 2-Fluorobipheny mg/k | Surrogate Recovery | 79.9   | %     | 25.0-121.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 80.5   | %     | 19.0-122.0 |
|             | Terphenyl - D14 mg/k | Surrogate Recovery | 89.9   | %     | 18.0-137.0 |
|             | 2-Fluorophenol mg/kg | Surrogate Recovery | 83.0   | %     | 30.0-115.0 |
| 97809379    | Phenol - D6 mg/kg re | Surrogate Recovery | 105.9  | %     | 24.0-113.0 |
|             | Nitrobenzene - D5 mg | Surrogate Recovery | 118.8  | %     | 23.0-120.0 |
|             | 2-Fluorobipheny mg/k | Surrogate Recovery | 103.5  | %     | 25.0-121.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 87.7   | %     | 19.0-122.0 |
|             | Terphenyl - D14 mg/k | Surrogate Recovery | 90.7   | %     | 18.0-137.0 |
|             | 2-Fluorophenol mg/kg | Surrogate Recovery | 101.0  | %     | 30.0-115.0 |
| BLANK-08012 | 1,4-Dichlorobenzene  | Blank              | <0.33  | mg/kg |            |
|             | Naphthalene          | Blank              | <0.33  | mg/kg |            |
|             | 1,2-Dichlorobenzene  | Blank              | <0.33  | mg/kg |            |
|             | 1,3-Dichlorobenzene  | Blank              | <0.33  | mg/kg |            |
|             | Acenaphthene         | Blank              | <0.33  | mg/kg |            |
|             | Acenaphthylene       | Blank              | <0.33  | mg/kg |            |
|             | Aniline              | Blank              | <0.33  | mg/kg |            |
|             | Anthracene           | Blank              | <0.33  | mg/kg |            |
|             | Benzidene            | Blank              | <2.33  | mg/kg |            |
|             | Benzo(a)anthracene   | Blank              | <0.33  | mg/kg |            |
|             | Benzo(a)pyrene       | Blank              | <0.67  | mg/kg |            |
|             | Benzo(b)fluoranthene | Blank              | <0.33  | mg/kg |            |
|             | Benzo(g,h,i)perylene | Blank              | <1.00  | mg/kg |            |
|             | Benzoic Acid         | Blank              | <1.00  | mg/kg |            |
|             | Benzyl Alcohol       | Blank              | <0.67  | mg/kg |            |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/02/97

Lims Bat #: LIMS-29711

Page 3 of 8

QC Batch Number: GCMS/SEMI-0741

| Sample Id | Analysis               | QC Analysis | Values | Units | Limits |
|-----------|------------------------|-------------|--------|-------|--------|
| -----     | -----                  | -----       | -----  | ----- | -----  |
|           | Bis(2-chloroethyl)et   | Blank       | <0.33  | mg/kg |        |
|           | Bis(2-chloroethoxy)m   | Blank       | <0.33  | mg/kg |        |
|           | Bis(2-chloroisopropyl) | Blank       | <0.33  | mg/kg |        |
|           | Bis(2-ethylhexyl)pht   | Blank       | <0.33  | mg/kg |        |
|           | 4-Bromophenylphenyle   | Blank       | <0.33  | mg/kg |        |
|           | Butylbenzylphthalate   | Blank       | <0.67  | mg/kg |        |
|           | 4-Chloroaniline        | Blank       | <0.67  | mg/kg |        |
|           | 2-Chloronaphthalene    | Blank       | <0.33  | mg/kg |        |
|           | 4-Chlorophenylphenyl   | Blank       | <0.33  | mg/kg |        |
|           | Chrysene               | Blank       | <0.67  | mg/kg |        |
|           | Dibenz(a,h)anthracen   | Blank       | <0.67  | mg/kg |        |
|           | Dibenzofuran           | Blank       | <0.33  | mg/kg |        |
|           | 3,3'-Dichlorobenzidi   | Blank       | <0.67  | mg/kg |        |
|           | Diethylphthalate       | Blank       | <0.33  | mg/kg |        |
|           | Dimethylphthalate      | Blank       | <0.67  | mg/kg |        |
|           | Di-n-butylphthalate    | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dinitrotoluene     | Blank       | <0.33  | mg/kg |        |
|           | 2,6-Dinitrotoluene     | Blank       | <0.33  | mg/kg |        |
|           | 1,2-Diphenylhydrazin   | Blank       | <0.33  | mg/kg |        |
|           | Di-n-octylphthalate    | Blank       | <0.67  | mg/kg |        |
|           | Fluoranthene           | Blank       | <0.33  | mg/kg |        |
|           | Fluorene               | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorobenzene      | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorobutadiene    | Blank       | <0.33  | mg/kg |        |
|           | Hexachlorocyclopenta   | Blank       | <0.33  | mg/kg |        |
|           | Hexachloroethane       | Blank       | <0.33  | mg/kg |        |
|           | Indeno(1,2,3-cd)pyre   | Blank       | <0.33  | mg/kg |        |
|           | Isophorone             | Blank       | <0.33  | mg/kg |        |
|           | 2-Methylnaphthalene    | Blank       | <0.33  | mg/kg |        |
|           | 2-Nitroaniline         | Blank       | <0.33  | mg/kg |        |
|           | 3-Nitroaniline         | Blank       | <0.33  | mg/kg |        |
|           | Nitrobenzene           | Blank       | <0.33  | mg/kg |        |
|           | N-Nitrosodimethylami   | Blank       | <0.33  | mg/kg |        |
|           | N-Nitroso-di-n-propyl  | Blank       | <0.33  | mg/kg |        |
|           | N-Nitrosodiphenylami   | Blank       | <0.33  | mg/kg |        |
|           | Phenanthrene           | Blank       | <0.33  | mg/kg |        |
|           | Pyrene                 | Blank       | <1.00  | mg/kg |        |
|           | 1,2,4-Trichlorobenze   | Blank       | <0.33  | mg/kg |        |
|           | 4-Chloro-3-methylphe   | Blank       | <0.67  | mg/kg |        |



## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/02/97

Lims Bat #: LIMS-29711

Page 4 of 8

QC Batch Number: GCMS/SEMI-0741

| Sample Id | Analysis             | QC Analysis | Values | Units | Limits |
|-----------|----------------------|-------------|--------|-------|--------|
| -----     | -----                | -----       | -----  | ----- | -----  |
|           | 2-Chlorophenol       | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dichlorophenol   | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dimethylphenol   | Blank       | <1.33  | mg/kg |        |
|           | 4,6-Dinitro-2-methyl | Blank       | <0.33  | mg/kg |        |
|           | 2,4-Dinitrophenol    | Blank       | <0.33  | mg/kg |        |
|           | 2-Methylphenol (o-cr | Blank       | <0.33  | mg/kg |        |
|           | 3- & 4-Methylphenol  | Blank       | <0.33  | mg/kg |        |
|           | 2-Nitrophenol        | Blank       | <0.33  | mg/kg |        |
|           | 4-Nitrophenol        | Blank       | <0.33  | mg/kg |        |
|           | Phenol               | Blank       | <0.33  | mg/kg |        |
|           | 2,4,5-Trichloropheno | Blank       | <0.33  | mg/kg |        |
|           | 2,4,6-Trichloropheno | Blank       | <0.33  | mg/kg |        |
|           | Pentachlorophenol    | Blank       | <0.33  | mg/kg |        |
|           | Pyridine             | Blank       | <0.33  | mg/kg |        |
|           | Benzo(k)fluoranthene | Blank       | <0.67  | mg/kg |        |
|           | 4-Nitroaniline       | Blank       | <0.33  | mg/kg |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/02/97

Lims Bat #: LIMS-29711

Page 5 of 8

QC Batch Number: GCMS/VOL-1304

| Sample Id   | Analysis             | QC Analysis        | Values  | Units | Limits         |
|-------------|----------------------|--------------------|---------|-------|----------------|
| -----       | -----                | -----              | -----   | ----- | -----          |
| 97B09377    | d4-12-Dichloroethane | Surrogate Recovery | 118.400 | %     | 56.000-128.000 |
|             | d8-Toluene (8240 dry | Surrogate Recovery | 106.000 | %     | 65.000-113.000 |
|             | Bromofluorobenzene   | Surrogate Recovery | 114.800 | %     | 62.000-137.000 |
| 97B09379    | d4-12-Dichloroethane | Surrogate Recovery | 106.000 | %     | 56.000-128.000 |
|             | d8-Toluene (8240 dry | Surrogate Recovery | 103.200 | %     | 65.000-113.000 |
|             | Bromofluorobenzene   | Surrogate Recovery | 107.600 | %     | 62.000-137.000 |
| BLANK-07996 | Acetone              | Blank              | <0.080  | mg/kg |                |
|             | Benzene              | Blank              | <0.003  | mg/kg |                |
|             | Carbon Tetrachloride | Blank              | <0.002  | mg/kg |                |
|             | Chloroform           | Blank              | <0.004  | mg/kg |                |
|             | 1,2-Dichloroethane   | Blank              | <0.004  | mg/kg |                |
|             | 1,4-Dichlorobenzene  | Blank              | <0.004  | mg/kg |                |
|             | Ethyl Benzene        | Blank              | <0.003  | mg/kg |                |
|             | 2-Butanone (MEK)     | Blank              | <0.060  | mg/kg |                |
|             | 4-Methyl-2-Pentanone | Blank              | <0.044  | mg/kg |                |
|             | Styrene              | Blank              | <0.004  | mg/kg |                |
|             | Tetrachloroethylene  | Blank              | <0.002  | mg/kg |                |
|             | Toluene              | Blank              | <0.004  | mg/kg |                |
|             | 1,1,1-Trichloroethan | Blank              | <0.004  | mg/kg |                |
|             | Trichloroethylene    | Blank              | <0.005  | mg/kg |                |
|             | Trichlorofluorometha | Blank              | <0.004  | mg/kg |                |
|             | o&p-Xylene           | Blank              | <0.002  | mg/kg |                |
|             | m-Xylene             | Blank              | <0.006  | mg/kg |                |
|             | 1,2-Dichlorobenzene  | Blank              | <0.004  | mg/kg |                |
|             | 1,3-Dichlorobenzene  | Blank              | <0.003  | mg/kg |                |
|             | 1,1-Dichloroethane   | Blank              | <0.004  | mg/kg |                |
|             | 1,1-Dichloroethylene | Blank              | <0.003  | mg/kg |                |
|             | Methyl tert-Butyl Et | Blank              | <0.004  | mg/kg |                |
|             | t-1,2-Dichloroethyle | Blank              | <0.004  | mg/kg |                |
|             | Vinyl Chloride       | Blank              | <0.002  | mg/kg |                |
|             | Methylene Chloride   | Blank              | <0.015  | mg/kg |                |
|             | Chlorobenzene        | Blank              | <0.003  | mg/kg |                |
|             | Chloromethane        | Blank              | <0.006  | mg/kg |                |
|             | Bromomethane         | Blank              | <0.006  | mg/kg |                |
|             | Chloroethane         | Blank              | <0.004  | mg/kg |                |
|             | cis-1,3-Dichloroprop | Blank              | <0.002  | mg/kg |                |
|             | t-1,3-Dichloropropen | Blank              | <0.002  | mg/kg |                |
|             | Chlorodibromomethane | Blank              | <0.002  | mg/kg |                |
|             | 1,1,2-Trichloroethan | Blank              | <0.004  | mg/kg |                |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/02/97

Lims Bat #: LIMS-29711

Page 6 of 8

QC Batch Number: GCMS/VOL-1304

| Sample Id | Analysis             | QC Analysis | Values | Units | Limits |
|-----------|----------------------|-------------|--------|-------|--------|
| -----     | -----                | -----       | -----  | ----- | -----  |
|           | 2-Chloroethylvinylet | Blank       | <0.048 | mg/kg |        |
|           | Bromoform            | Blank       | <0.006 | mg/kg |        |
|           | 1,1,2,2-Tetrachloroe | Blank       | <0.007 | mg/kg |        |
|           | Dibromomethane       | Blank       | <0.006 | mg/kg |        |
|           | 1,2-Dichloropropane  | Blank       | <0.003 | mg/kg |        |
|           | 1,2,3-Trichloropropa | Blank       | <0.006 | mg/kg |        |
|           | Dichlorodifluorometh | Blank       | <0.005 | mg/kg |        |
|           | Iodomethane          | Blank       | <0.004 | mg/kg |        |
|           | Acrolein             | Blank       | <0.100 | mg/kg |        |
|           | Acrylonitrile        | Blank       | <0.038 | mg/kg |        |
|           | Carbon Disulfide     | Blank       | <0.002 | mg/kg |        |
|           | Vinyl Acetate        | Blank       | <0.082 | mg/kg |        |
|           | 2-Hexanone           | Blank       | <0.048 | mg/kg |        |
|           | t-1,4-Dichloro-2-But | Blank       | <0.010 | mg/kg |        |
|           | Ethyl Methacrylate   | Blank       | <0.004 | mg/kg |        |
|           | c-1,4-Dichloro-2-But | Blank       | <0.012 | mg/kg |        |
|           | Bromodichloromethane | Blank       | <0.002 | mg/kg |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike DuplicatesBATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/02/97

Lims Bat #: LIMS-29711

Page 7 of 8

QC Batch Number: HG-0494

| Sample Id    | Analysis | QC Analysis          | Values  | Units | Limits |
|--------------|----------|----------------------|---------|-------|--------|
| -----        | -----    | -----                | -----   | ----- | -----  |
| LFBANK-03956 | Mercury  | Lab Fort Blank Amt.  | 0.200   | mg/kg |        |
|              |          | Lab Fort Blk. Found  | 0.230   | mg/kg |        |
|              |          | Lab Fort Blk. % Rec. | 115.000 | %     |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike DuplicatesBATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/02/97

Lims Bat #: LIMS-29711

Page 8 of 8

QC Batch Number: TPH-0759

| Sample Id | Analysis             | QC Analysis     | Values  | Units | Limits |
|-----------|----------------------|-----------------|---------|-------|--------|
| -----     | -----                | -----           | -----   | ----- | -----  |
| 97809379  | Total Petroleum Hydr | Sample Amount   | 5202.17 | mg/kg |        |
|           |                      | Duplicate Value | 4566.93 | mg/kg |        |
|           |                      | Duplicate RPD   | 13.01   | %     |        |

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

[illegible]



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

REPORT DATE: 06/16/97

PURCHASE ORDER NUMBER: 40163  
PROJECT NUMBER: PRJ.# 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29604  
JOB NUMBER: 29604

The results of analyses performed on the following samples submitted to the CON-TEST Analytical Laboratory are found in this report

PROJECT LOCATION: MIDDLETOWN, CT

| FIELD SAMPLE # | LAB ID   | MATRIX       | SAMPLE DESCRIPTION   | TEST         |
|----------------|----------|--------------|----------------------|--------------|
| 10-F           | 97808805 | WIPE - OTHER | WIPE FLOOR           | special test |
| 10-NW          | 97808806 | WIPE - OTHER | WIPE NORTH WALL      | special test |
| 10-SW          | 97808807 | WIPE - OTHER | WIPE SOUTH WALL      | special test |
| 4-EW           | 97808811 | WIPE - OTHER | WIPE EAST WALL       | special test |
| 4-WW           | 97808812 | WIPE - OTHER | WIPE WEST WALL       | special test |
| 5-ES           | 97808809 | WIPE - OTHER | WIPE ELECTRIC SWITCH | special test |
| 5-EW           | 97808810 | WIPE - OTHER | WIPE EAST WALL       | special test |
| 5-FD           | 97808808 | WIPE - OTHER | WIPE FIRE DOOR       | special test |

The CON-TEST Environmental Laboratory operates under the following certifications and accreditations:

|                             |                              |
|-----------------------------|------------------------------|
| AIHA 308                    | AIHA ELLAP (LEAD) 6838       |
| MASSACHUSETTS MA100         | MAINE (POTABLE/NON-POTABLE)  |
| CONNECTICUT PH-0567         | VERMONT DOH (LEAD) No. 15036 |
| NEW YORK ELAP 10899         | RHODE ISLAND (LIC. No. 112)  |
| OHIO (ENVIRO. LEAD) # 10005 |                              |
| NEW HAMPSHIRE 2516          |                              |

I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document.

Edward Denson 6/16/97  
SIGNATURE DATE

Tod Kopyscinski  
Director of Operations

Edward Denson  
Technical Director



39 Spruce Street • 2nd Floor • East longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332

MARC RICHARDS  
VANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272

Purchase Order Number: 40163  
Project Number: PRJ.# 40163

06/16/97  
page 1 of 5

Project Location: MIDDLETOWN, CT  
Date Received: 05/15/97

LIMS-BAT #: LIMS-29604  
Job Number: 29604  
Sample Matrix: WIPE - OTHER

Sampled: 05/15/97  
WIPE FLOOR  
10-F

|              | Units | 97808805 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|-------|----------|---------------|---------|-----|------------|-----|
| -----        | ----- | -----    | -----         | -----   | --- | -----      | --- |
| SPECIAL TEST |       | - Note - | 05/22/97      | KLF     |     |            |     |

Sampled: 05/15/97  
WIPE NORTH WALL  
10-NW

|              | Units | 97808806 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|-------|----------|---------------|---------|-----|------------|-----|
| -----        | ----- | -----    | -----         | -----   | --- | -----      | --- |
| SPECIAL TEST |       | - Note - | 05/22/97      | KLF     |     |            |     |

Sampled: 05/15/97  
WIPE SOUTH WALL  
10-SW

|              | Units | 97808807 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|-------|----------|---------------|---------|-----|------------|-----|
| -----        | ----- | -----    | -----         | -----   | --- | -----      | --- |
| SPECIAL TEST |       | - Note - | 05/22/97      | KLF     |     |            |     |

Sampled: 05/15/97  
WIPE EAST WALL  
4-EW

|              | Units | 97808811 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|-------|----------|---------------|---------|-----|------------|-----|
| -----        | ----- | -----    | -----         | -----   | --- | -----      | --- |
| SPECIAL TEST |       | - Note - | 05/22/97      | KLF     |     |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



06/16/97  
 page 2 of 5

 Purchase Order Number: 40163  
 Project Number: PRJ.# 40163

 LIMS-BAT #: LIMS-29604  
 Job Number: 29604  
 Sample Matrix: WIPE - OTHER

 Sampled: 05/15/97  
 WIPE WEST WALL  
 4-WW

|              | Units | 97808812 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|-------|----------|---------------|---------|-----|------------|-----|
| SPECIAL TEST |       | - Note - | 05/22/97      | KLF     |     |            |     |

 Sampled: 05/15/97  
 WIPE ELECTRIC SWITCH  
 5-ES

|              | Units | 97808809 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|-------|----------|---------------|---------|-----|------------|-----|
| SPECIAL TEST |       | - Note - | 05/22/97      | KLF     |     |            |     |

 Sampled: 05/15/97  
 WIPE EAST WALL  
 5-EW

|              | Units | 97808810 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|-------|----------|---------------|---------|-----|------------|-----|
| SPECIAL TEST |       | - Note - | 05/22/97      | KLF     |     |            |     |

 Sampled: 05/15/97  
 WIPE FIRE DOOR  
 5-FD

|              | Units | 97808808 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|-------|----------|---------------|---------|-----|------------|-----|
| SPECIAL TEST |       | - Note - | 05/22/97      | KLF     |     |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/16/97

page 3 of 5

Analytical Method(s):

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/16/97  
page 4 of 5

The following notes were attached to the reported analysis:

| Analysis: SPECIAL TEST |          |          |          |          |
|------------------------|----------|----------|----------|----------|
|                        | 97B08805 | 97B08806 | 97B08807 | 97B08808 |
| ANALYTE(ug/cm2)        |          |          |          |          |
| ANTIMONY               | <0.05    | <0.05    | <0.05    | 0.12     |
| ARSENIC                | 0.42     | 0.47     | 0.33     | 0.62     |
| BERYLLIUM              | 0.003    | 0.004    | 0.007    | 0.005    |
| CADMIUM                | 0.070    | 0.079    | 0.144    | 0.203    |
| CHROMIUM               | 0.651    | 0.627    | 1.94     | 0.779    |
| COPPER                 | 1.02     | 1.26     | 2.86     | 1.55     |
| LEAD                   | 2.57     | 5.15     | 7.25     | 37.7     |
| MERCURY                | 0.0052   | 0.0070   | 0.016    | 0.072    |
| NICKEL                 | 0.495    | 0.502    | 0.952    | 0.595    |
| SELENIUM               | <0.10    | 0.13     | 0.16     | 0.13     |
| SILVER                 | 0.02     | <0.01    | 0.02     | <0.01    |
| THALLIUM               | <0.20    | <0.20    | <0.20    | <0.20    |
| ZINC                   | 7.92     | 10.5     | 12.2     | 46.0     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

VANASSE HANGEN BRUSTLIN, INC.  
 101 WALNUT STREET  
 WATERTOWN, MA 02272  
 ATTN: MARC RICHARDS

REPORT DATE: 06/13/97

 PURCHASE ORDER NUMBER: A0163  
 PROJECT NUMBER: PROJ.# A0163

## ANALYTICAL SUMMARY

 LIMS BAT #: LIMS-29802  
 JOB NUMBER: 29802

The results of analyses performed on the following samples submitted to the CON-TEST Analytical Laboratory are found in this report

PROJECT LOCATION: MIDDLETOWN, CT

| FIELD SAMPLE # | LAB ID   | MATRIX     | SAMPLE DESCRIPTION | TEST             |
|----------------|----------|------------|--------------------|------------------|
| MW-1           | 97B09735 | GRND WATER | MONITORING WELL #1 | tph (mg/l)       |
| MW-1           | 97B09736 | GRND WATER | MONITORING WELL #1 | metals(w13) icp  |
| MW-1           | 97B09737 | GRND WATER | MONITORING WELL #1 | 8240 - water     |
| MW-1           | 97B09737 | GRND WATER | MONITORING WELL #1 | 8240 - water (b) |
| MW-2           | 97B09739 | GRND WATER | MONITORING WELL #2 | tph (mg/l)       |
| MW-2           | 97B09740 | GRND WATER | MONITORING WELL #2 | metals(w13) icp  |
| MW-2           | 97B09741 | GRND WATER | MONITORING WELL #2 | 8240 - water     |
| MW-2           | 97B09741 | GRND WATER | MONITORING WELL #2 | 8240 - water (b) |
| MW-3           | 97B09751 | GRND WATER | MONITORING WELL #3 | tph (mg/l)       |
| MW-3           | 97B09752 | GRND WATER | MONITORING WELL #3 | metals(w13) icp  |
| MW-3           | 97B09753 | GRND WATER | MONITORING WELL #3 | 8240 - water     |
| MW-3           | 97B09753 | GRND WATER | MONITORING WELL #3 | 8240 - water (b) |
| MW-3           | 97B09755 | GRND WATER | MONITORING WELL #3 | bod              |
| MW-3           | 97B09755 | GRND WATER | MONITORING WELL #3 | chloride         |
| MW-3           | 97B09755 | GRND WATER | MONITORING WELL #3 | nitrate          |
| MW-3           | 97B09756 | GRND WATER | MONITORING WELL #3 | ammonia          |
| MW-3           | 97B09757 | GRND WATER | MONITORING WELL #3 | fe (mg/l) icp    |
| MW-3           | 97B09757 | GRND WATER | MONITORING WELL #3 | mn (mg/l) icp    |
| MW-3           | 97B09758 | GRND WATER | MONITORING WELL #3 | alkalinity       |
| MW-3           | 97B09758 | GRND WATER | MONITORING WELL #3 | conductivity     |
| MW-3           | 97B09758 | GRND WATER | MONITORING WELL #3 | ph               |
| MW-3           | 97B09758 | GRND WATER | MONITORING WELL #3 | tds              |
| MW-3           | 97B09758 | GRND WATER | MONITORING WELL #3 | tss              |
| MW-4           | 97B09743 | GRND WATER | MONITORING WELL #4 | tph (mg/l)       |
| MW-4           | 97B09744 | GRND WATER | MONITORING WELL #4 | metals(w13) icp  |
| MW-4           | 97B09745 | GRND WATER | MONITORING WELL #4 | 8240 - water     |
| MW-4           | 97B09745 | GRND WATER | MONITORING WELL #4 | 8240 - water (b) |
| MW-5           | 97B09759 | GRND WATER | MONITORING WELL #5 | tph (mg/l)       |
| MW-5           | 97B09760 | GRND WATER | MONITORING WELL #5 | metals(w13) icp  |
| MW-5           | 97B09761 | GRND WATER | MONITORING WELL #5 | 8240 - water     |
| MW-5           | 97B09761 | GRND WATER | MONITORING WELL #5 | 8240 - water (b) |
| MW-5           | 97B09763 | GRND WATER | MONITORING WELL #5 | bod              |
| MW-5           | 97B09763 | GRND WATER | MONITORING WELL #5 | chloride         |
| MW-5           | 97B09763 | GRND WATER | MONITORING WELL #5 | nitrate          |
| MW-5           | 97B09764 | GRND WATER | MONITORING WELL #5 | ammonia          |
| MW-5           | 97B09765 | GRND WATER | MONITORING WELL #5 | fe (mg/l) icp    |
| MW-5           | 97B09765 | GRND WATER | MONITORING WELL #5 | mn (mg/l) icp    |
| MW-5           | 97B09766 | GRND WATER | MONITORING WELL #5 | alkalinity       |
| MW-5           | 97B09766 | GRND WATER | MONITORING WELL #5 | conductivity     |



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.

REPORT DATE: 06/13/97

101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

PURCHASE ORDER NUMBER: A0163  
PROJECT NUMBER: PROJ.# A0163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29802  
JOB NUMBER: 29802

| FIELD SAMPLE # | LAB ID   | MATRIX     | SAMPLE DESCRIPTION | TEST             |
|----------------|----------|------------|--------------------|------------------|
| MW-5           | 97B09766 | GRND WATER | MONITORING WELL #5 | ph               |
| MW-5           | 97B09766 | GRND WATER | MONITORING WELL #5 | tds              |
| MW-5           | 97B09766 | GRND WATER | MONITORING WELL #5 | tss              |
| MW-6           | 97B09747 | GRND WATER | MONITORING WELL #6 | tph (mg/l)       |
| MW-6           | 97B09748 | GRND WATER | MONITORING WELL #6 | metals(w13) icp  |
| MW-6           | 97B09749 | GRND WATER | MONITORING WELL #6 | 8240 - water     |
| MW-6           | 97B09749 | GRND WATER | MONITORING WELL #6 | 8240 - water (b) |

| FIELD SAMPLE # | LAB ID   | MATRIX     | SAMPLE DESCRIPTION | TEST             | SUBCONTRACTOR LABORATORY |
|----------------|----------|------------|--------------------|------------------|--------------------------|
| MW-1           | 97B09738 | GRND WATER | MONITORING WELL #1 | 625 - acid fract |                          |
| MW-1           | 97B09738 | GRND WATER | MONITORING WELL #1 | 625 - b/n frac-1 |                          |
| MW-1           | 97B09738 | GRND WATER | MONITORING WELL #1 | 625 - b/n frac-2 |                          |
| MW-1           | 97B09738 | GRND WATER | MONITORING WELL #1 | herbicides - h2o | SUBCONTRACTED            |
| MW-1           | 97B09738 | GRND WATER | MONITORING WELL #1 | pcb - water      |                          |
| MW-2           | 97B09742 | GRND WATER | MONITORING WELL #2 | 625 - acid fract |                          |
| MW-2           | 97B09742 | GRND WATER | MONITORING WELL #2 | 625 - b/n frac-1 |                          |
| MW-2           | 97B09742 | GRND WATER | MONITORING WELL #2 | 625 - b/n frac-2 |                          |
| MW-2           | 97B09742 | GRND WATER | MONITORING WELL #2 | herbicides - h2o | SUBCONTRACTED            |
| MW-2           | 97B09742 | GRND WATER | MONITORING WELL #2 | pcb - water      |                          |
| MW-3           | 97B09754 | GRND WATER | MONITORING WELL #3 | 625 - acid fract |                          |
| MW-3           | 97B09754 | GRND WATER | MONITORING WELL #3 | 625 - b/n frac-1 |                          |
| MW-3           | 97B09754 | GRND WATER | MONITORING WELL #3 | 625 - b/n frac-2 |                          |
| MW-3           | 97B09754 | GRND WATER | MONITORING WELL #3 | herbicides - h2o | SUBCONTRACTED            |
| MW-3           | 97B09754 | GRND WATER | MONITORING WELL #3 | pcb - water      |                          |
| MW-4           | 97B09746 | GRND WATER | MONITORING WELL #4 | 625 - acid fract |                          |
| MW-4           | 97B09746 | GRND WATER | MONITORING WELL #4 | 625 - b/n frac-1 |                          |
| MW-4           | 97B09746 | GRND WATER | MONITORING WELL #4 | 625 - b/n frac-2 |                          |
| MW-4           | 97B09746 | GRND WATER | MONITORING WELL #4 | herbicides - h2o | SUBCONTRACTED            |
| MW-4           | 97B09746 | GRND WATER | MONITORING WELL #4 | pcb - water      |                          |
| MW-5           | 97B09762 | GRND WATER | MONITORING WELL #5 | 625 - acid fract |                          |
| MW-5           | 97B09762 | GRND WATER | MONITORING WELL #5 | 625 - b/n frac-1 |                          |
| MW-5           | 97B09762 | GRND WATER | MONITORING WELL #5 | 625 - b/n frac-2 |                          |
| MW-5           | 97B09762 | GRND WATER | MONITORING WELL #5 | herbicides - h2o | SUBCONTRACTED            |
| MW-5           | 97B09762 | GRND WATER | MONITORING WELL #5 | pcb - water      |                          |
| MW-6           | 97B09750 | GRND WATER | MONITORING WELL #6 | 625 - acid fract |                          |
| MW-6           | 97B09750 | GRND WATER | MONITORING WELL #6 | 625 - b/n frac-1 |                          |
| MW-6           | 97B09750 | GRND WATER | MONITORING WELL #6 | 625 - b/n frac-2 |                          |
| MW-6           | 97B09750 | GRND WATER | MONITORING WELL #6 | herbicides - h2o | SUBCONTRACTED            |
| MW-6           | 97B09750 | GRND WATER | MONITORING WELL #6 | pcb - water      |                          |



39 Spruce Street • 2nd Floor • East longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.

REPORT DATE: 06/13/97

101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

PURCHASE ORDER NUMBER: A0163  
PROJECT NUMBER: PROJ.# A0163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-29802  
JOB NUMBER: 29802

| FIELD SAMPLE # | LAB ID | MATRIX | SAMPLE DESCRIPTION | TEST | SUBCONTRACTOR LABORATORY |
|----------------|--------|--------|--------------------|------|--------------------------|
|----------------|--------|--------|--------------------|------|--------------------------|

The CON-TEST Environmental Laboratory operates under the following certifications and accreditations:

|                             |                              |
|-----------------------------|------------------------------|
| AIHA 308                    | AIHA ELLAP (LEAD) 6838       |
| MASSACHUSETTS MA100         | MAINE (POTABLE/NON-POTABLE)  |
| CONNECTICUT PH-0567         | VERMONT DOH (LEAD) No. 15036 |
| NEW YORK ELAP 10899         | RHODE ISLAND (LIC. No. 112)  |
| OHIO (ENVIRO. LEAD) # 10005 |                              |
| NEW HAMPSHIRE 2516          |                              |

I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document.

Edward Denson 6/16/97  
SIGNATURE DATE

Tod Kopyscinski  
Director of Operations

Edward Denson  
Technical Director



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332

MARC RICHARDS  
VANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

06/13/97  
page 1 of 53

Project Location: MIDDLETOWN, CT  
Date Received: 05/28/97

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #1  
MW-1

|                                  | Units | 97809738 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | ug/l  | ND       | 06/03/97         | WSD     | 40.0 |               |     |
| 2-Chlorophenol                   | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4-Dichlorophenol               | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4-Dimethylphenol               | ug/l  | ND       | 06/03/97         | WSD     | 80.0 |               |     |
| 4,6-Dinitro-2-methylphenol       | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4-Dinitrophenol                | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Methylphenol (o-cresol)        | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Nitrophenol                    | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 4-Nitrophenol                    | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Pentachlorophenol                | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Phenol                           | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4,5-Trichlorophenol            | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4,6-Trichlorophenol            | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |

Sampled: 05/27/97  
MONITORING WELL #2  
MW-2

|                                  | Units | 97809742 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Chlorophenol                   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4-Dichlorophenol               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4-Dimethylphenol               | ug/l  | ND       | 06/03/97         | WSD     | 40.0 |               |     |
| 4,6-Dinitro-2-methylphenol       | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4-Dinitrophenol                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2-Methylphenol (o-cresol)        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2-Nitrophenol                    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Nitrophenol                    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 2 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #2

MW-2

|                       | Units | 97809742 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                 | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Pentachlorophenol     | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Phenol                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4,5-Trichlorophenol | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4,6-Trichlorophenol | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |

Sampled: 05/27/97

MONITORING WELL #3

MW-3

|                                  | Units | 97809754 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | ug/l  | ND       | 06/03/97         | WSD     | 40.0 |               |     |
| 2-Chlorophenol                   | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4-Dichlorophenol               | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4-Dimethylphenol               | ug/l  | ND       | 06/03/97         | WSD     | 80.0 |               |     |
| 4,6-Dinitro-2-methylphenol       | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4-Dinitrophenol                | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Methylphenol (o-cresol)        | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Nitrophenol                    | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 4-Nitrophenol                    | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Pentachlorophenol                | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Phenol                           | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4,5-Trichlorophenol            | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2,4,6-Trichlorophenol            | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.



06/13/97  
 page 3 of 53

 Purchase Order Number: A0163  
 Project Number: PROJ.# A0163

 LIMS-BAT #: LIMS-29802  
 Job Number: 29802  
 Sample Matrix: GRND WATER

 Sampled: 05/27/97  
 MONITORING WELL #4  
 MW-4

|                                  | Units | 97B09746 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Chlorophenol                   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4-Dichlorophenol               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,4-Dimethylphenol               | ug/l  | ND       | 06/03/97         | WSD     | 40.0 |               |     |
| 4,6-Dinitro-2-methylphenol       | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4-Dinitrophenol                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3-Methylphenol (o-cresol)        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2-Nitrophenol                    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Nitrophenol                    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4,6-Trichlorophenol            | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Phenol                           | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4,5-Trichlorophenol            | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,4,6-Trichlorophenol            | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |

 Sampled: 05/27/97  
 MONITORING WELL #5  
 MW-5

|                                  | Units | 97B09762 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|-----|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | --- | -----         | --- |
| 4-Chloro-3-methylphenol          | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 2-Chlorophenol                   | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 2,4-Dichlorophenol               | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 2,4-Dimethylphenol               | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 4,6-Dinitro-2-methylphenol       | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 2,4-Dinitrophenol                | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 2-Methylphenol (o-cresol)        | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 2-Nitrophenol                    | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 4-Nitrophenol                    | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 4 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #5  
MW-5

|                       | Units | 97B09762 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|-----------------------|-------|----------|------------------|---------|-----|---------------|-----|
| -----                 | ----- | -----    | -----            | -----   | --- | -----         | --- |
| Pentachlorophenol     | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| Phenol                | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 2,4,5-Trichlorophenol | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |
| 2,4,6-Trichlorophenol | ug/l  | NM       | 06/03/97         | WSD     |     |               |     |

Sampled: 05/27/97  
MONITORING WELL #6  
MW-6

|                                  | Units | 97B09750 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                            | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 4-Chloro-3-methylphenol          | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Chlorophenol                   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4-Dichlorophenol               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4-Dimethylphenol               | ug/l  | ND       | 06/03/97         | WSD     | 40.0 |               |     |
| 4,6-Dinitro-2-methylphenol       | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4-Dinitrophenol                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2-Methylphenol (o-cresol)        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3- & 4-Methylphenol (m&p-cresol) | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2-Nitrophenol                    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Nitrophenol                    | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Pentachlorophenol                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Phenol                           | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4,5-Trichlorophenol            | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,4,6-Trichlorophenol            | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |

Analytical Method(s):

EPA 625

SAMPLES ARE EXTRACTED INTO METHYLENE CHLORIDE, FOLLOWED BY KUDERNA-DANISH

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

EVAPORATIVE CONCENTRATION AND QUANTITATED BY GC/MS TARGET COMPOUND ANALYSIS

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 6 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #1

HW-1

|                             | Units | 97B09738 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                       | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acenaphthene                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Acenaphthylene              | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Aniline                     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Anthracene                  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benidene                    | ug/l  | ND       | 06/03/97         | WSD     | 70.0 |               |     |
| Benzoic Acid                | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(a)anthracene          | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(a)pyrene              | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Benzo(b)fluoranthene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(g,h,i)perylene        | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(k)fluoranthene        | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Benzyl Alcohol              | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Bis(2-chloroethoxy)methane  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroethyl)ether     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroisopropyl)ether | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-ethylhexyl)phthalate  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Bromophenylphenylether    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Butylbenzylphthalate        | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 4-Chloroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Chloronaphthalene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Chlorophenylphenylether   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Chrysene                    | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Dibenzofuran                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Dibenz(a,h)anthracene       | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 1,2-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,3-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,4-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3,3'-Dichlorobenzidine      | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Diethylphthalate            | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Dimethylphthalate           | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Di-n-butylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Di-n-octylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or

regulatory level for comparison with data to

determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 7 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #1

MW-1

|                            | Units | 97B09738 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| 2,4-Dinitrotoluene         | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 2,6-Dinitrotoluene         | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 1,2-Diphenylhydrazine      | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Fluoranthene               | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Fluorene                   | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachlorobenzene          | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachlorobutadiene        | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachlorocyclopentadiene  | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachloroethane           | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Indeno(1,2,3-cd)pyrene     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Isophorone                 | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 2-Methylnaphthalene        | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Naphthalene                | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 2-Nitroaniline             | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 3-Nitroaniline             | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 4-Nitroaniline             | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Nitrobenzene               | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| N-Nitrosodimethylamine     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| N-Nitrosodiphenylamine     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| N-Nitroso-di-n-propylamine | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Phenanthrene               | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Pyrene                     | ug/l  | ND       | 06/03/97      | WSD     | 30.0 |            |     |
| Pyridine                   | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 1,2,4-Trichlorobenzene     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 8 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #2

MW-2

|                             | Units | 97809742 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                       | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acenaphthene                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Acenaphthylene              | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Aniline                     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Anthracene                  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benzidene                   | ug/l  | ND       | 06/03/97         | WSD     | 70.0 |               |     |
| Benzoic Acid                | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(a)anthracene          | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(a)pyrene              | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Benzo(b)fluoranthene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(g,h,i)perylene        | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(k)fluoranthene        | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Benzyl Alcohol              | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Bis(2-chloroethoxy)methane  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroethyl)ether     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroisopropyl)ether | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-ethylhexyl)phthalate  | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Bromophenylphenylether    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Butylbenzylphthalate        | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |
| 4-Chloroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Chloronaphthalene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Chlorophenylphenylether   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Chrysene                    | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Dibenzofuran                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Dibenz(a,h)anthracene       | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 1,2-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,3-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,4-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3,3'-Dichlorobenzidine      | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Diethylphthalate            | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Dimethylphthalate           | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Di-n-butylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Di-n-octylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 9 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #2

MW-2

|                            | Units | 97809742 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| 1,4-Dinitrotoluene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,6-Dinitrotoluene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,2-Diphenylhydrazine      | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Fluoranthene               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Fluorene                   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Hexachlorobenzene          | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Hexachlorobutadiene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Hexachlorocyclopentadiene  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Hexachloroethane           | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Indeno(1,2,3-cd)pyrene     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Isochlorophene             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2-Methylnaphthalene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Naphthalene                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2-Nitroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3-Nitroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Nitroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Nitrobenzene               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| N-Nitrosodimethylamine     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| N-Nitrosodiphenylamine     | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| N-Nitroso-di-n-propylamine | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Phenanthrene               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Pyrene                     | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Pyridine                   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,2,4-Trichlorobenzene     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 10 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #3

MW-3

|                             | Units | 97809754 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                       | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acenaphthene                | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Acenaphthylene              | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Aniline                     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Anthracene                  | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Benfzidene                  | ug/l  | BDL      | 06/03/97         | WSD     | 70.0 |               |     |
| Benzoic Acid                | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(a)anthracene          | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(a)pyrene              | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |
| Benzo(b)fluoranthene        | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(g,h,i)perylene        | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(k)fluoranthene        | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |
| Benzyl Alcohol              | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Bis(2-chloroethoxy)methane  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroethyl)ether     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroisopropyl)ether | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-ethylhexyl)phthalate  | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Bromophenylphenylether    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Butylbenzylphthalate        | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |
| 4-Chloroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Chloronaphthalene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Chlorophenylphenylether   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Chrysene                    | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |
| Dibenzofuran                | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Dibenz(a,h)anthracene       | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 1,2-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,3-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,4-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3,3'-Dichlorobenzidine      | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Diethylphthalate            | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Dimethylphthalate           | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |
| Di-n-butylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Di-n-octylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: A0163  
 Project Number: PROJ.# A0163

 LIMS-BAT #: LIMS-29802  
 Job Number: 29802  
 Sample Matrix: GRND WATER

 Sampled: 05/27/97  
 MONITORING WELL #3  
 MW-3

|                            | Units | 97809754 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| 2,4-Dinitrotoluene         | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| 2,6-Dinitrotoluene         | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 1,2-Diphenylhydrazine      | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Fluoranthene               | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Fluorene                   | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachlorobenzene          | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachlorobutadiene        | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachlorocyclopentadiene  | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachloroethane           | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Indeno(1,2,3-cd)pyrene     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Isophorone                 | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| 2-Methylnaphthalene        | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Naphthalene                | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 2-Nitroaniline             | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| 3-Nitroaniline             | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| 4-Nitroaniline             | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Nitrobenzene               | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| N-Nitrosodimethylamine     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| N-Nitrosodiphenylamine     | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| N-Nitroso-di-n-propylamine | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Phenanthrene               | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Pyrene                     | ug/l  | BDL      | 06/03/97      | WSD     | 30.0 |            |     |
| Pyridine                   | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 1,2,4-Trichlorobenzene     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 12 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #4

MW-4

|                             | Units | 97809746 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                       | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acenaphthene                | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Acenaphthylene              | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Aniline                     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Anthracene                  | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Benidene                    | ug/l  | ND       | 06/03/97         | WSD     | 70.0 |               |     |
| Benzoic Acid                | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(a)anthracene          | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(a)pyrene              | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Benzo(b)fluoranthene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(g,h,i)perylene        | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(k)fluoranthene        | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Benzyl Alcohol              | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Bis(2-chloroethoxy)methane  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroethyl)ether     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroisopropyl)ether | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-ethylhexyl)phthalate  | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Bromophenylphenylether    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Butylbenzylphthalate        | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 4-Chloroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Chloronaphthalene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Chlorophenylphenylether   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Chrysene                    | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |
| Dibenzofuran                | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Dibenz(a,h)anthracene       | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 1,2-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,3-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,4-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3,3'-Dichlorobenzidine      | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Diethylphthalate            | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Dimethylphthalate           | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Di-n-butylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Di-n-octylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 13 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #4

MW-4

|                            | Units | 97809746 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| 1,4-Dinitrotoluene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| 2,6-Dinitrotoluene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| 1,2-Diphenylhydrazine      | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Fluoranthene               | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Fluorene                   | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Hexachlorobenzene          | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Hexachlorobutadiene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Hexachlorocyclopentadiene  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Hexachloroethane           | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Indeno(1,2,3-cd)pyrene     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Isophorone                 | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| 2-Methylnaphthalene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Naphthalene                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| 2-Nitroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| 3-Nitroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| 4-Nitroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Nitrobenzene               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| N-Nitrosodimethylamine     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| N-Nitrosodiphenylamine     | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 | ----          | --- |
| N-Nitroso-di-n-propylamine | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Phenanthrene               | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 | ----          | --- |
| Pyrene                     | ug/l  | BDL      | 06/03/97         | WSD     | 30.0 | ----          | --- |
| Pyridine                   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |
| 1,2,4-Trichlorobenzene     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 | ----          | --- |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 14 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #5

MW-5

|                             | Units | 97809762 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                       | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acenaphthene                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Acenaphthylene              | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Aniline                     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Anthracene                  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benzidene                   | ug/l  | ND       | 06/03/97         | WSD     | 70.0 |               |     |
| Benzoic Acid                | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(a)anthracene          | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(a)pyrene              | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Benzo(b)fluoranthene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Benzo(g,h,i)perylene        | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Benzo(k)fluoranthene        | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Benzyl Alcohol              | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Bis(2-chloroethoxy)methane  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroethyl)ether     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-chloroisopropyl)ether | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Bis(2-ethylhexyl)phthalate  | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Bromophenylphenylether    | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Butylbenzylphthalate        | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 4-Chloroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 2-Chloronaphthalene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Chlorophenylphenylether   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Chrysene                    | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Dibenzofuran                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Dibenz(a,h)anthracene       | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| 1,2-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,3-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,4-Dichlorobenzene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3,3'-Dichlorobenzidine      | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Diethylphthalate            | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Dimethylphthalate           | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Di-n-butylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Di-n-octylphthalate         | ug/l  | BDL      | 06/03/97         | WSD     | 20.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 15 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #5

MW-5

|                            | Units | 97809762 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                      | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| 2,4-Dinitrotoluene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2,6-Dinitrotoluene         | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,2-Diphenylhydrazine      | ug/l  | BDL      | 06/03/97         | WSD     | 10.0 |               |     |
| Fluoranthene               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Fluorene                   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Hexachlorobenzene          | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Hexachlorobutadiene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Hexachlorocyclopentadiene  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Hexachloroethane           | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Indeno(1,2,3-cd)pyrene     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Isophorone                 | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2-Methylnaphthalene        | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Naphthalene                | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 2-Nitroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 3-Nitroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 4-Nitroaniline             | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Nitrobenzene               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| N-Nitrosodimethylamine     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| N-Nitrosodiphenylamine     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| N-Nitroso-di-n-propylamine | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Phenanthrene               | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Pyrene                     | ug/l  | ND       | 06/03/97         | WSD     | 30.0 |               |     |
| Pyridine                   | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,2,4-Trichlorobenzene     | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or

regulatory level for comparison with data to

determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 16 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #6

MW-6

|                             | Units | 97B09750 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|-----------------------------|-------|----------|---------------|---------|------|------------|-----|
| Acenaphthene                | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Acenaphthylene              | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Aniline                     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Anthracene                  | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Benzidene                   | ug/l  | ND       | 06/03/97      | WSD     | 70.0 |            |     |
| Benzoic Acid                | ug/l  | ND       | 06/03/97      | WSD     | 30.0 |            |     |
| Benzo(a)anthracene          | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Benzo(a)pyrene              | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| Benzo(b)fluoranthene        | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Benzo(g,h,i)perylene        | ug/l  | ND       | 06/03/97      | WSD     | 30.0 |            |     |
| Benzo(k)fluoranthene        | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| Benzyl Alcohol              | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| Bis(2-chloroethoxy)methane  | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Bis(2-chloroethyl)ether     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Bis(2-chloroisopropyl)ether | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Bis(2-ethylhexyl)phthalate  | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| 4-Bromophenylphenylether    | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Butylbenzylphthalate        | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| 4-Chloroaniline             | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| 2-Chloronaphthalene         | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 4-Chlorophenylphenylether   | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Chrysene                    | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| Dibenzofuran                | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Dibenz(a,h)anthracene       | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| 1,2-Dichlorobenzene         | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 1,3-Dichlorobenzene         | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 1,4-Dichlorobenzene         | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 3,3'-Dichlorobenzidine      | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| Diethylphthalate            | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Dimethylphthalate           | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| Di-n-butylphthalate         | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Di-n-octylphthalate         | ug/l  | BDL      | 06/03/97      | WSD     | 20.0 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/13/97  
 page 17 of 53

 Purchase Order Number: A0163  
 Project Number: PROJ.# A0163

 LIMS-BAT #: LIMS-29802  
 Job Number: 29802  
 Sample Matrix: GRND WATER

 Sampled: 05/27/97  
 MONITORING WELL #6  
 MW-6

|                            | Units | 97B09750 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------|-------|----------|---------------|---------|------|------------|-----|
| 1,4-Dinitrotoluene         | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 2,6-Dinitrotoluene         | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 1,2-Diphenylhydrazine      | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Fluoranthene               | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Fluorene                   | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachlorobenzene          | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachlorobutadiene        | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachlorocyclopentadiene  | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Hexachloroethane           | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Indeno(1,2,3-cd)pyrene     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Isophorone                 | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 2-Methylnaphthalene        | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Naphthalene                | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 2-Nitroaniline             | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 3-Nitroaniline             | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 4-Nitroaniline             | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| Nitrobenzene               | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| N-Nitrosodimethylamine     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| N-Nitrosodiphenylamine     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| N-Nitroso-di-n-propylamine | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Phenanthrene               | ug/l  | BDL      | 06/03/97      | WSD     | 10.0 |            |     |
| Pyrene                     | ug/l  | ND       | 06/03/97      | WSD     | 30.0 |            |     |
| Pyridine                   | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |
| 1,2,4-Trichlorobenzene     | ug/l  | ND       | 06/03/97      | WSD     | 10.0 |            |     |

Analytical Method(s):

EPA 625

 SAMPLES ARE EXTRACTED INTO METHYLENE CHLORIDE, FOLLOWED BY KUDERNA-DANISH  
 EVAPORATIVE CONCENTRATION AND QUANTITATED BY GC/MS TARGET COMPOUND ANALYSIS

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 18 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #1  
MW-1

|                          | Units | 97B09737 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|--------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                    | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Acetone                  | ug/l  | ND       | 06/03/97      | WSD     | 16.1 |            |     |
| Acrolein                 | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| Acrylonitrile            | ug/l  | ND       | 06/03/97      | WSD     | 7.6  |            |     |
| Benzene                  | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |
| Bromodichloromethane     | ug/l  | ND       | 06/03/97      | WSD     | 0.4  |            |     |
| Bromomethane             | ug/l  | ND       | 06/03/97      | WSD     | 1.2  |            |     |
| Bromoform                | ug/l  | ND       | 06/03/97      | WSD     | 1.2  |            |     |
| 2-Butanone (MEK)         | ug/l  | ND       | 06/03/97      | WSD     | 12.0 |            |     |
| Carbon Disulfide         | ug/l  | ND       | 06/03/97      | WSD     | 0.5  |            |     |
| Carbon Tetrachloride     | ug/l  | ND       | 06/03/97      | WSD     | 0.5  |            |     |
| Chlorobenzene            | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |
| Chlorodibromomethane     | ug/l  | ND       | 06/03/97      | WSD     | 0.5  |            |     |
| Chloroethane             | ug/l  | ND       | 06/03/97      | WSD     | 0.8  |            |     |
| 2-Chloroethylvinylether  | ug/l  | ND       | 06/03/97      | WSD     | 9.6  |            |     |
| Chloroform               | ug/l  | ND       | 06/03/97      | WSD     | 0.8  |            |     |
| Chloromethane            | ug/l  | ND       | 06/03/97      | WSD     | 1.2  |            |     |
| Dibromomethane           | ug/l  | ND       | 06/03/97      | WSD     | 1.1  |            |     |
| 1,2-Dichlorobenzene      | ug/l  | ND       | 06/03/97      | WSD     | 0.8  |            |     |
| 1,3-Dichlorobenzene      | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |
| 1,4-Dichlorobenzene      | ug/l  | ND       | 06/03/97      | WSD     | 0.8  |            |     |
| c-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97      | WSD     | 2.4  |            |     |
| t-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97      | WSD     | 2.1  |            |     |
| Dichlorodifluoromethane  | ug/l  | ND       | 06/03/97      | WSD     | 1.0  |            |     |
| 1,1-Dichloroethane       | ug/l  | ND       | 06/03/97      | WSD     | 0.7  |            |     |
| 1,2-Dichloroethane       | ug/l  | ND       | 06/03/97      | WSD     | 0.9  |            |     |
| 1,1-Dichloroethylene     | ug/l  | 3.1      | 06/03/97      | WSD     | 0.6  |            |     |
| cis-1,2-Dichloroethylene | ug/l  | 71.6     | 06/03/97      | WSD     | 0.5  |            |     |
| t-1,2-Dichloroethylene   | ug/l  | 1.2      | 06/03/97      | WSD     | 0.8  |            |     |
| 1,2-Dichloropropane      | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |
| cis-1,3-Dichloropropene  | ug/l  | ND       | 06/03/97      | WSD     | 0.5  |            |     |
| t-1,3-Dichloropropene    | ug/l  | ND       | 06/03/97      | WSD     | 0.4  |            |     |
| Ethyl Benzene            | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.



06/13/97

page 19 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #1

MW-1

|                                | Units | 97809737 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Ethyl Methacrylate             | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| 2-Hexanone                     | ug/l  | ND       | 06/03/97         | WSD     | 9.7  |               |     |
| Iodomethane                    | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| Methyl tert-Butyl Ether (MTBE) | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| Methylene Chloride             | ug/l  | ND       | 06/03/97         | WSD     | 3.0  |               |     |
| 4-Methyl-2-Pentanone (MIBK)    | ug/l  | ND       | 06/03/97         | WSD     | 8.8  |               |     |
| Styrene                        | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,1,2,2-Tetrachloroethane      | ug/l  | ND       | 06/03/97         | WSD     | 1.4  |               |     |
| Tetrachloroethylene            | ug/l  | ND       | 06/03/97         | WSD     | 0.4  |               |     |
| Toluene                        | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,1,1-Trichloroethane          | ug/l  | ND       | 06/03/97         | WSD     | 0.9  |               |     |
| 1,1,2-Trichloroethane          | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| Trichloroethylene              | ug/l  | 275      | 06/03/97         | WSD     | 1.0  |               |     |
| Trichlorofluoromethane         | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,2,3-Trichloropropane         | ug/l  | ND       | 06/03/97         | WSD     | 1.3  |               |     |
| Vinyl Acetate                  | ug/l  | ND       | 06/03/97         | WSD     | 16.4 |               |     |
| Vinyl Chloride                 | ug/l  | 17.9     | 06/03/97         | WSD     | 0.3  |               |     |
| m-Xylene                       | ug/l  | ND       | 06/03/97         | WSD     | 1.3  |               |     |
| o&p-Xylene                     | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 20 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #2

MW-2

|                          | Units | 97809741 | Date<br>Analyzed | Analyst | MOL  | SPEC<br>LIMIT | P/F |
|--------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                    | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acetone                  | ug/l  | ND       | 06/03/97         | WSD     | 161  |               |     |
| Acrolein                 | ug/l  | ND       | 06/03/97         | WSD     | 200  |               |     |
| Acrylonitrile            | ug/l  | ND       | 06/03/97         | WSD     | 76.0 |               |     |
| Benzene                  | ug/l  | ND       | 06/03/97         | WSD     | 6.0  |               |     |
| Bromodichloromethane     | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| Bromomethane             | ug/l  | ND       | 06/03/97         | WSD     | 12.0 |               |     |
| Bromoform                | ug/l  | ND       | 06/03/97         | WSD     | 12.0 |               |     |
| 2-Butanone (MEK)         | ug/l  | ND       | 06/03/97         | WSD     | 120  |               |     |
| Carbon Disulfide         | ug/l  | ND       | 06/03/97         | WSD     | 5.0  |               |     |
| Carbon Tetrachloride     | ug/l  | ND       | 06/03/97         | WSD     | 5.0  |               |     |
| Chlorobenzene            | ug/l  | ND       | 06/03/97         | WSD     | 6.0  |               |     |
| Chlorodibromomethane     | ug/l  | ND       | 06/03/97         | WSD     | 5.0  |               |     |
| Chloroethane             | ug/l  | ND       | 06/03/97         | WSD     | 8.0  |               |     |
| 2-Chloroethylvinylether  | ug/l  | ND       | 06/03/97         | WSD     | 96.0 |               |     |
| Chloroform               | ug/l  | ND       | 06/03/97         | WSD     | 8.0  |               |     |
| Chloromethane            | ug/l  | ND       | 06/03/97         | WSD     | 12.0 |               |     |
| Dibromomethane           | ug/l  | ND       | 06/03/97         | WSD     | 11.0 |               |     |
| 1,2-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 8.0  |               |     |
| 1,3-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 6.0  |               |     |
| 1,4-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 8.0  |               |     |
| c-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97         | WSD     | 24.0 |               |     |
| t-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97         | WSD     | 21.0 |               |     |
| Dichlorodifluoromethane  | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| 1,1-Dichloroethane       | ug/l  | ND       | 06/03/97         | WSD     | 7.0  |               |     |
| 1,2-Dichloroethane       | ug/l  | ND       | 06/03/97         | WSD     | 9.0  |               |     |
| 1,1-Dichloroethylene     | ug/l  | ND       | 06/03/97         | WSD     | 6.0  |               |     |
| cis-1,2-Dichloroethylene | ug/l  | ND       | 06/03/97         | WSD     | 5.0  |               |     |
| t-1,2-Dichloroethylene   | ug/l  | ND       | 06/03/97         | WSD     | 8.0  |               |     |
| 1,2-Dichloropropane      | ug/l  | ND       | 06/03/97         | WSD     | 6.0  |               |     |
| cis-1,3-Dichloropropene  | ug/l  | ND       | 06/03/97         | WSD     | 5.0  |               |     |
| t-1,3-Dichloropropene    | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| Ethyl Benzene            | ug/l  | ND       | 06/03/97         | WSD     | 6.0  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 21 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #2

MW-2

|                                | Units | 97809741 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Ethyl Methacrylate             | ug/l  | ND       | 06/03/97         | WSD     | 8.0  |               |     |
| 2-Hexanone                     | ug/l  | ND       | 06/03/97         | WSD     | 97.0 |               |     |
| Iodomethane                    | ug/l  | ND       | 06/03/97         | WSD     | 8.0  |               |     |
| Methyl tert-Butyl Ether (MTBE) | ug/l  | 2110     | 06/03/97         | WSD     | 8.0  |               |     |
| Methylene Chloride             | ug/l  | 61.0     | 06/03/97         | WSD     | 30.0 |               |     |
| 4-Methyl-2-Pentanone (MIBK)    | ug/l  | ND       | 06/03/97         | WSD     | 88.0 |               |     |
| Styrene                        | ug/l  | ND       | 06/03/97         | WSD     | 7.0  |               |     |
| 1,1,2,2-Tetrachloroethane      | ug/l  | ND       | 06/03/97         | WSD     | 14.0 |               |     |
| Tetrachloroethylene            | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| Toluene                        | ug/l  | ND       | 06/03/97         | WSD     | 7.0  |               |     |
| 1,1,1-Trichloroethane          | ug/l  | ND       | 06/03/97         | WSD     | 9.0  |               |     |
| 1,1,2-Trichloroethane          | ug/l  | ND       | 06/03/97         | WSD     | 7.0  |               |     |
| Trichloroethylene              | ug/l  | ND       | 06/03/97         | WSD     | 10.0 |               |     |
| Trichlorofluoromethane         | ug/l  | ND       | 06/03/97         | WSD     | 7.0  |               |     |
| 1,2,3-Trichloropropane         | ug/l  | ND       | 06/03/97         | WSD     | 13.0 |               |     |
| Vinyl Acetate                  | ug/l  | ND       | 06/03/97         | WSD     | 164  |               |     |
| Vinyl Chloride                 | ug/l  | ND       | 06/03/97         | WSD     | 3.0  |               |     |
| m-Xylene                       | ug/l  | ND       | 06/03/97         | WSD     | 13.0 |               |     |
| o&p-Xylene                     | ug/l  | ND       | 06/03/97         | WSD     | 5.0  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #3

MW-3

|                          | Units | 97809753 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|--------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                    | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acetone                  | ug/l  | ND       | 06/03/97         | WSD     | 16.1 |               |     |
| Acrolein                 | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Acrylonitrile            | ug/l  | ND       | 06/03/97         | WSD     | 7.6  |               |     |
| Benzene                  | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| Bromodichloromethane     | ug/l  | ND       | 06/03/97         | WSD     | 0.4  |               |     |
| Bromomethane             | ug/l  | ND       | 06/03/97         | WSD     | 1.2  |               |     |
| Bromoform                | ug/l  | ND       | 06/03/97         | WSD     | 1.2  |               |     |
| 2-Butanone (MEK)         | ug/l  | ND       | 06/03/97         | WSD     | 12.0 |               |     |
| Carbon Disulfide         | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| Carbon Tetrachloride     | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| Chlorobenzene            | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| Chlorodibromomethane     | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| Chloroethane             | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| 2-Chloroethylvinylether  | ug/l  | ND       | 06/03/97         | WSD     | 9.6  |               |     |
| Chloroform               | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| Chloromethane            | ug/l  | ND       | 06/03/97         | WSD     | 1.2  |               |     |
| Dibromomethane           | ug/l  | ND       | 06/03/97         | WSD     | 1.1  |               |     |
| 1,2-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| 1,3-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| 1,4-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| c-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97         | WSD     | 2.4  |               |     |
| t-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97         | WSD     | 2.1  |               |     |
| Dichlorodifluoromethane  | ug/l  | ND       | 06/03/97         | WSD     | 1.0  |               |     |
| 1,1-Dichloroethane       | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,2-Dichloroethane       | ug/l  | ND       | 06/03/97         | WSD     | 0.9  |               |     |
| 1,1-Dichloroethylene     | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| cis-1,2-Dichloroethylene | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| t-1,2-Dichloroethylene   | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| 1,2-Dichloropropane      | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| cis-1,3-Dichloropropene  | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| t-1,3-Dichloropropene    | ug/l  | ND       | 06/03/97         | WSD     | 0.4  |               |     |
| Ethyl Benzene            | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 23 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #3

MW-3

|                               | Units | 97809753 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|-------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                         | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| thyl Methacrylate             | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| 2-Hexanone                    | ug/l  | ND       | 06/03/97         | WSD     | 9.7  |               |     |
| Iodomethane                   | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| ethyl tert-Butyl Ether (MTBE) | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| ethylene Chloride             | ug/l  | ND       | 06/03/97         | WSD     | 3.0  |               |     |
| 4-Methyl-2-Pentanone (MIBK)   | ug/l  | ND       | 06/03/97         | WSD     | 8.8  |               |     |
| tyrene                        | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,1,2,2-Tetrachloroethane     | ug/l  | ND       | 06/03/97         | WSD     | 1.4  |               |     |
| Tetrachloroethylene           | ug/l  | ND       | 06/03/97         | WSD     | 0.4  |               |     |
| Toluene                       | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,1,1-Trichloroethane         | ug/l  | ND       | 06/03/97         | WSD     | 0.9  |               |     |
| 1,1,2-Trichloroethane         | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| Trichloroethylene             | ug/l  | ND       | 06/03/97         | WSD     | 1.0  |               |     |
| Trichlorofluoromethane        | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,2,3-Trichloropropane        | ug/l  | ND       | 06/03/97         | WSD     | 1.3  |               |     |
| Vinyl Acetate                 | ug/l  | ND       | 06/03/97         | WSD     | 16.4 |               |     |
| Vinyl Chloride                | ug/l  | ND       | 06/03/97         | WSD     | 0.3  |               |     |
| m-Xylene                      | ug/l  | ND       | 06/03/97         | WSD     | 1.3  |               |     |
| o&p-Xylene                    | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or

regulatory level for comparison with data to

determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 24 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

 Sampled: 05/27/97  
 MONITORING WELL #4  
 MW-4

|                          | Units | 97809745 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|--------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                    | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acetone                  | ug/l  | ND       | 06/03/97         | WSD     | 80.5 |               |     |
| Acrolein                 | ug/l  | ND       | 06/03/97         | WSD     | 100  |               |     |
| Acrylonitrile            | ug/l  | ND       | 06/03/97         | WSD     | 38.0 |               |     |
| Benzene                  | ug/l  | ND       | 06/03/97         | WSD     | 3.0  |               |     |
| Bromodichloromethane     | ug/l  | ND       | 06/03/97         | WSD     | 2.0  |               |     |
| Bromomethane             | ug/l  | ND       | 06/03/97         | WSD     | 6.0  |               |     |
| Bromoform                | ug/l  | ND       | 06/03/97         | WSD     | 6.0  |               |     |
| 2-Butanone (MEK)         | ug/l  | ND       | 06/03/97         | WSD     | 60.0 |               |     |
| Carbon Disulfide         | ug/l  | ND       | 06/03/97         | WSD     | 2.5  |               |     |
| Carbon Tetrachloride     | ug/l  | ND       | 06/03/97         | WSD     | 2.5  |               |     |
| Chlorobenzene            | ug/l  | ND       | 06/03/97         | WSD     | 3.0  |               |     |
| Chlorodibromomethane     | ug/l  | ND       | 06/03/97         | WSD     | 2.5  |               |     |
| Chloroethane             | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| 2-Chloroethylvinylether  | ug/l  | ND       | 06/03/97         | WSD     | 48.0 |               |     |
| Chloroform               | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| Chloromethane            | ug/l  | ND       | 06/03/97         | WSD     | 6.0  |               |     |
| Dibromomethane           | ug/l  | ND       | 06/03/97         | WSD     | 5.5  |               |     |
| 1,2-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| 1,3-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 3.0  |               |     |
| 1,4-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| c-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97         | WSD     | 12.0 |               |     |
| t-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97         | WSD     | 10.5 |               |     |
| Dichlorodifluoromethane  | ug/l  | ND       | 06/03/97         | WSD     | 5.0  |               |     |
| 1,1-Dichloroethane       | ug/l  | ND       | 06/03/97         | WSD     | 3.5  |               |     |
| 1,2-Dichloroethane       | ug/l  | ND       | 06/03/97         | WSD     | 4.5  |               |     |
| 1,1-Dichloroethylene     | ug/l  | ND       | 06/03/97         | WSD     | 3.0  |               |     |
| cis-1,2-Dichloroethylene | ug/l  | ND       | 06/03/97         | WSD     | 2.5  |               |     |
| t-1,2-Dichloroethylene   | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| 1,2-Dichloropropane      | ug/l  | ND       | 06/03/97         | WSD     | 3.0  |               |     |
| cis-1,3-Dichloropropene  | ug/l  | ND       | 06/03/97         | WSD     | 2.5  |               |     |
| t-1,3-Dichloropropene    | ug/l  | ND       | 06/03/97         | WSD     | 2.0  |               |     |
| Ethyl Benzene            | ug/l  | BDL      | 06/03/97         | WSD     | 3.0  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 25 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #4

MW-4

|                                | Units | 97809745 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|--------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                          | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Ethyl Methacrylate             | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| 2-Hexanone                     | ug/l  | ND       | 06/03/97         | WSD     | 48.5 |               |     |
| Iodomethane                    | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| Methyl tert-Butyl Ether (MTBE) | ug/l  | ND       | 06/03/97         | WSD     | 4.0  |               |     |
| Methylene Chloride             | ug/l  | BDL      | 06/03/97         | WSD     | 15.0 |               |     |
| 4-Methyl-2-Pentanone (MIBK)    | ug/l  | ND       | 06/03/97         | WSD     | 44.0 |               |     |
| Styrene                        | ug/l  | ND       | 06/03/97         | WSD     | 3.5  |               |     |
| 1,1,2,2-Tetrachloroethane      | ug/l  | ND       | 06/03/97         | WSD     | 7.0  |               |     |
| Tetrachloroethylene            | ug/l  | ND       | 06/03/97         | WSD     | 2.0  |               |     |
| Toluene                        | ug/l  | BDL      | 06/03/97         | WSD     | 3.5  |               |     |
| 1,1,1-Trichloroethane          | ug/l  | ND       | 06/03/97         | WSD     | 4.5  |               |     |
| 1,1,2-Trichloroethane          | ug/l  | ND       | 06/03/97         | WSD     | 3.5  |               |     |
| Trichloroethylene              | ug/l  | 37.0     | 06/03/97         | WSD     | 5.0  |               |     |
| Trichlorofluoromethane         | ug/l  | ND       | 06/03/97         | WSD     | 3.5  |               |     |
| 1,2,3-Trichloropropane         | ug/l  | ND       | 06/03/97         | WSD     | 6.5  |               |     |
| Vinyl Acetate                  | ug/l  | ND       | 06/03/97         | WSD     | 82.0 |               |     |
| Vinyl Chloride                 | ug/l  | ND       | 06/03/97         | WSD     | 1.5  |               |     |
| m-Xylene                       | ug/l  | BDL      | 06/03/97         | WSD     | 6.5  |               |     |
| o&p-Xylene                     | ug/l  | ND       | 06/03/97         | WSD     | 2.5  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 26 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #5

MW-5

|                          | Units | 97B09761 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|--------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                    | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Acetone                  | ug/l  | ND       | 06/03/97      | WSD     | 16.1 |            |     |
| Acrolein                 | ug/l  | ND       | 06/03/97      | WSD     | 20.0 |            |     |
| Acrylonitrile            | ug/l  | ND       | 06/03/97      | WSD     | 7.6  |            |     |
| Benzene                  | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |
| Bromodichloromethane     | ug/l  | ND       | 06/03/97      | WSD     | 0.4  |            |     |
| Bromomethane             | ug/l  | ND       | 06/03/97      | WSD     | 1.2  |            |     |
| Bromoform                | ug/l  | ND       | 06/03/97      | WSD     | 1.2  |            |     |
| 2-Butanone (MEK)         | ug/l  | ND       | 06/03/97      | WSD     | 12.0 |            |     |
| Carbon Disulfide         | ug/l  | ND       | 06/03/97      | WSD     | 0.5  |            |     |
| Carbon Tetrachloride     | ug/l  | ND       | 06/03/97      | WSD     | 0.5  |            |     |
| Chlorobenzene            | ug/l  | 3.7      | 06/03/97      | WSD     | 0.6  |            |     |
| Chlorodibromomethane     | ug/l  | ND       | 06/03/97      | WSD     | 0.5  |            |     |
| Chloroethane             | ug/l  | 14.5     | 06/03/97      | WSD     | 0.8  |            |     |
| 2-Chloroethylvinylether  | ug/l  | ND       | 06/03/97      | WSD     | 9.6  |            |     |
| Chloroform               | ug/l  | ND       | 06/03/97      | WSD     | 0.8  |            |     |
| Chloromethane            | ug/l  | ND       | 06/03/97      | WSD     | 1.2  |            |     |
| Dibromomethane           | ug/l  | ND       | 06/03/97      | WSD     | 1.1  |            |     |
| 1,2-Dichlorobenzene      | ug/l  | ND       | 06/03/97      | WSD     | 0.8  |            |     |
| 1,3-Dichlorobenzene      | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |
| 1,4-Dichlorobenzene      | ug/l  | ND       | 06/03/97      | WSD     | 0.8  |            |     |
| c-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97      | WSD     | 2.4  |            |     |
| t-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97      | WSD     | 2.1  |            |     |
| Dichlorodifluoromethane  | ug/l  | ND       | 06/03/97      | WSD     | 1.0  |            |     |
| 1,1-Dichloroethane       | ug/l  | ND       | 06/03/97      | WSD     | 0.7  |            |     |
| 1,2-Dichloroethane       | ug/l  | ND       | 06/03/97      | WSD     | 0.9  |            |     |
| 1,1-Dichloroethylene     | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |
| cis-1,2-Dichloroethylene | ug/l  | ND       | 06/03/97      | WSD     | 0.5  |            |     |
| t-1,2-Dichloroethylene   | ug/l  | ND       | 06/03/97      | WSD     | 0.8  |            |     |
| 1,2-Dichloropropane      | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |
| cis-1,3-Dichloropropene  | ug/l  | ND       | 06/03/97      | WSD     | 0.5  |            |     |
| t-1,3-Dichloropropene    | ug/l  | ND       | 06/03/97      | WSD     | 0.4  |            |     |
| Ethyl Benzene            | ug/l  | ND       | 06/03/97      | WSD     | 0.6  |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.



06/13/97

page 27 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #5

MW-5

|                                 | Units | 97809761 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|---------------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                           | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Ethyl Methacrylate              | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| 2-Hexanone                      | ug/l  | ND       | 06/03/97         | WSD     | 9.7  |               |     |
| Iodomethane                     | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| Diethyl tert-Butyl Ether (MTBE) | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| Dichloroethylene                | ug/l  | ND       | 06/03/97         | WSD     | 3.0  |               |     |
| 4-Methyl-2-Pentanone (MIBK)     | ug/l  | ND       | 06/03/97         | WSD     | 8.8  |               |     |
| Styrene                         | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,1,2,2-Tetrachloroethane       | ug/l  | ND       | 06/03/97         | WSD     | 1.4  |               |     |
| Tetrachloroethylene             | ug/l  | ND       | 06/03/97         | WSD     | 0.4  |               |     |
| Toluene                         | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,1,1-Trichloroethane           | ug/l  | ND       | 06/03/97         | WSD     | 0.9  |               |     |
| 1,1,2-Trichloroethane           | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| Trichloroethylene               | ug/l  | 16.7     | 06/03/97         | WSD     | 1.0  |               |     |
| Trichlorofluoromethane          | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,2,3-Trichloropropane          | ug/l  | ND       | 06/03/97         | WSD     | 1.3  |               |     |
| Vinyl Acetate                   | ug/l  | ND       | 06/03/97         | WSD     | 16.4 |               |     |
| Vinyl Chloride                  | ug/l  | ND       | 06/03/97         | WSD     | 0.3  |               |     |
| m-Xylene                        | ug/l  | ND       | 06/03/97         | WSD     | 1.3  |               |     |
| o&p-Xylene                      | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to

determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 28 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #6

MW-6

|                          | Units | 97B09749 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|--------------------------|-------|----------|------------------|---------|------|---------------|-----|
| -----                    | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| Acetone                  | ug/l  | ND       | 06/03/97         | WSD     | 16.1 |               |     |
| Acrolein                 | ug/l  | ND       | 06/03/97         | WSD     | 20.0 |               |     |
| Acrylonitrile            | ug/l  | ND       | 06/03/97         | WSD     | 7.6  |               |     |
| Benzene                  | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| Bromodichloromethane     | ug/l  | ND       | 06/03/97         | WSD     | 0.4  |               |     |
| Bromomethane             | ug/l  | ND       | 06/03/97         | WSD     | 1.2  |               |     |
| Bromoform                | ug/l  | ND       | 06/03/97         | WSD     | 1.2  |               |     |
| 2-Butanone (MEK)         | ug/l  | ND       | 06/03/97         | WSD     | 12.0 |               |     |
| Carbon Disulfide         | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| Carbon Tetrachloride     | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| Chlorobenzene            | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| Chlorodibromomethane     | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| Chloroethane             | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| 2-Chloroethylvinylether  | ug/l  | ND       | 06/03/97         | WSD     | 9.6  |               |     |
| Chloroform               | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| Chloromethane            | ug/l  | ND       | 06/03/97         | WSD     | 1.2  |               |     |
| Dibromomethane           | ug/l  | ND       | 06/03/97         | WSD     | 1.1  |               |     |
| 1,2-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| 1,3-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| 1,4-Dichlorobenzene      | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| c-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97         | WSD     | 2.4  |               |     |
| t-1,4-Dichloro-2-Butene  | ug/l  | ND       | 06/03/97         | WSD     | 2.1  |               |     |
| Dichlorodifluoromethane  | ug/l  | ND       | 06/03/97         | WSD     | 1.0  |               |     |
| 1,1-Dichloroethane       | ug/l  | ND       | 06/03/97         | WSD     | 0.7  |               |     |
| 1,2-Dichloroethane       | ug/l  | ND       | 06/03/97         | WSD     | 0.9  |               |     |
| 1,1-Dichloroethylene     | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| cis-1,2-Dichloroethylene | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| t-1,2-Dichloroethylene   | ug/l  | ND       | 06/03/97         | WSD     | 0.8  |               |     |
| 1,2-Dichloropropane      | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |
| cis-1,3-Dichloropropene  | ug/l  | ND       | 06/03/97         | WSD     | 0.5  |               |     |
| t-1,3-Dichloropropene    | ug/l  | ND       | 06/03/97         | WSD     | 0.4  |               |     |
| Ethyl Benzene            | ug/l  | ND       | 06/03/97         | WSD     | 0.6  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 31 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #3

MW-3

|         | Units | 97B09756 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|---------|-------|----------|---------------|---------|------|------------|-----|
| Ammonia | mg/l  | 1.96     | 06/02/97      | TAM     | 1.00 |            |     |

Sampled: 05/27/97

MONITORING WELL #5

MW-5

|         | Units | 97B09764 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|---------|-------|----------|---------------|---------|------|------------|-----|
| Ammonia | mg/l  | ND       | 06/02/97      | TAM     | 1.00 |            |     |

Analytical Method(s):

EPA 350.2

 ALKALINE STEAM DISTILLATION, ABSORPTION IN BORIC ACID SOLUTION, AND  
 TITRATION WITH 0.02 N SULFURIC ACID

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

06/13/97

page 32 of 53

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #3

MW-3

|       | Units | 97809755 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|-------|-------|----------|------------------|---------|-----|---------------|-----|
| ----- | ----- | -----    | -----            | -----   | --- | -----         | --- |
| BOD   | mg/l  | <2.0     | 06/03/97         | SBP     | 2.0 |               |     |

Sampled: 05/27/97

MONITORING WELL #5

MW-5

|       | Units | 97809763 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|-------|-------|----------|------------------|---------|-----|---------------|-----|
| ----- | ----- | -----    | -----            | -----   | --- | -----         | --- |
| BOD   | mg/l  | 2.8      | 06/03/97         | SBP     | 2.0 |               |     |

# Analytical Method(s):

SM 52108

DISSOLVED OXYGEN CONSUMPTION IS MEASURED AFTER 5 DAYS OF INCUBATION AT  
 20 DEGREES C. BY THE OXYGEN PROBE METHOD

MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 TEL 413/525-2332  
06/13/97  
page 33 of 53

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #3  
MW-3

|          | Units | 97809755 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------|-------|----------|------------------|---------|------|---------------|-----|
| Chloride | mg/l  | 5.40     | 06/03/97         | RCL     | 1.00 |               |     |

Sampled: 05/27/97  
MONITORING WELL #5  
MW-5

|          | Units | 97809763 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------|-------|----------|------------------|---------|------|---------------|-----|
| Chloride | mg/l  | 6.60     | 06/03/97         | RCL     | 1.00 |               |     |

Analytical Method(s):

EPA 325.2

AUTOMATED FLOW INJECTION COLORIMETRIC ANALYSIS IN WHICH THIOCYANATE IS  
LIBERATED FROM A MERCURIC COMPLEX IN THE PRESENCE OF CHLORIDE AND FERRIC  
ION TO PRODUCE FERRIC THIOCYANATE IN PROPORTION TO THE CHLORIDE  
CONCENTRATION.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



**con-test®**  
ANALYTICAL LABORATORY

39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332  
06/13/97  
page 34 of 53

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #3  
HW-3

|              | Units    | 97809758 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|----------|----------|---------------|---------|-----|------------|-----|
| Conductivity | umhos/cm | 740      | 05/29/97      | KMD     | --- | ---        | --- |

Sampled: 05/27/97  
MONITORING WELL #5  
HW-5

|              | Units    | 97809766 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
|--------------|----------|----------|---------------|---------|-----|------------|-----|
| Conductivity | umhos/cm | 520      | 05/29/97      | KMD     | --- | ---        | --- |

Analytical Method(s):

SM 2510 B

MEASUREMENT WITH WHEATSTONE BRIDGE TYPE CONDUCTIVITY METER

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332  
06/13/97  
page 35 of 53

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #3  
MW-3

|      | Units | 97B09757 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|------|-------|----------|------------------|---------|------|---------------|-----|
| Iron | mg/l  | 15.0     | 06/06/97         | KLF     | 0.02 | ---           | --- |

Sampled: 05/27/97  
MONITORING WELL #5  
MW-5

|      | Units | 97B09765 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|------|-------|----------|------------------|---------|------|---------------|-----|
| Iron | mg/l  | 138      | 06/06/97         | KLF     | 0.02 | ---           | --- |

Analytical Method(s):

EPA 200.7

SAMPLES ARE DIGESTED WITH MINERAL ACIDS AND ANALYZED BY INDUCTIVELY COUPLED  
PLASMA EMISSION SPECTROMETRY (ICP).

L = Method Detection Limit  
= Not Detected  
L = Below Detection Limit  
= Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332

06/13/97  
page 36 of 53

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #1  
MW-1

| Units    | 97809738 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|----------|---------------|---------|------|------------|-----|
| 2,4-D    | ND       | 06/11/97      | JE      | 1.00 |            |     |
| 2,4,5-TP | ND       | 06/11/97      | JE      | 0.20 |            |     |

Sampled: 05/27/97  
MONITORING WELL #2  
MW-2

| Units    | 97809742 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|----------|---------------|---------|------|------------|-----|
| 2,4-D    | ND       | 06/11/97      | JE      | 1.00 |            |     |
| 2,4,5-TP | ND       | 06/11/97      | JE      | 0.20 |            |     |

Sampled: 05/27/97  
MONITORING WELL #3  
MW-3

| Units    | 97809754 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|----------|---------------|---------|------|------------|-----|
| 2,4-D    | ND       | 06/11/97      | JE      | 1.00 |            |     |
| 2,4,5-TP | ND       | 06/11/97      | JE      | 0.20 |            |     |

Sampled: 05/27/97  
MONITORING WELL #4  
MW-4

| Units    | 97809746 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|----------|---------------|---------|------|------------|-----|
| 2,4-D    | ND       | 06/11/97      | JE      | 1.00 |            |     |
| 2,4,5-TP | ND       | 06/11/97      | JE      | 0.20 |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.



06/13/97  
page 37 of 53

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIHS-BAT #: LIHS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #5  
MW-5

|          | Units | 97809762 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|-------|----------|---------------|---------|------|------------|-----|
| 2,4-D    | ug/l  | ND       | 06/11/97      | JE      | 1.00 |            |     |
| 2,4,5-TP | ug/l  | ND       | 06/11/97      | JE      | 0.20 |            |     |

Sampled: 05/27/97  
MONITORING WELL #6  
MW-6

|          | Units | 97809750 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|-------|----------|---------------|---------|------|------------|-----|
| 2,4-D    | ug/l  | ND       | 06/11/97      | JE      | 1.00 |            |     |
| 2,4,5-TP | ug/l  | ND       | 06/11/97      | JE      | 0.20 |            |     |

Analytical Method(s):

SW846 8150

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

 Sampled: 05/27/97  
 MONITORING WELL #1  
 MW-1

|           | Units | 97809736 | Date<br>Analyzed | Analyst | MDL    | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|--------|---------------|-----|
| -----     | ----- | -----    | -----            | -----   | ---    | -----         | --- |
| Antimony  | mg/l  | ND       | 06/05/97         | KLF     | 0.02   |               |     |
| Arsenic   | mg/l  | ND       | 06/05/97         | KLF     | 0.05   |               |     |
| Beryllium | mg/l  | ND       | 06/05/97         | KLF     | 0.0010 |               |     |
| Cadmium   | mg/l  | 0.0030   | 06/05/97         | KLF     | 0.0005 |               |     |
| Chromium  | mg/l  | ND       | 06/05/97         | KLF     | 0.004  |               |     |
| Copper    | mg/l  | ND       | 06/05/97         | KLF     | 0.0010 |               |     |
| Lead      | mg/l  | ND       | 06/05/97         | KLF     | 0.02   |               |     |
| Mercury   | mg/l  | ND       | 06/04/97         | APP     | 0.0002 |               |     |
| Nickel    | mg/l  | 0.014    | 06/05/97         | KLF     | 0.002  |               |     |
| Selenium  | mg/l  | ND       | 06/05/97         | KLF     | 0.05   |               |     |
| Silver    | mg/l  | ND       | 06/05/97         | KLF     | 0.005  |               |     |
| Thallium  | mg/l  | ND       | 06/05/97         | KLF     | 0.10   |               |     |
| Zinc      | mg/l  | 0.213    | 06/05/97         | KLF     | 0.005  |               |     |

 Sampled: 05/27/97  
 MONITORING WELL #2  
 MW-2

|           | Units | 97809740 | Date<br>Analyzed | Analyst | MDL    | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|--------|---------------|-----|
| -----     | ----- | -----    | -----            | -----   | ---    | -----         | --- |
| Antimony  | mg/l  | ND       | 06/05/97         | KLF     | 0.02   |               |     |
| Arsenic   | mg/l  | ND       | 06/05/97         | KLF     | 0.05   |               |     |
| Beryllium | mg/l  | ND       | 06/05/97         | KLF     | 0.0010 |               |     |
| Cadmium   | mg/l  | ND       | 06/05/97         | KLF     | 0.0005 |               |     |
| Chromium  | mg/l  | ND       | 06/05/97         | KLF     | 0.004  |               |     |
| Copper    | mg/l  | ND       | 06/05/97         | KLF     | 0.0010 |               |     |
| Lead      | mg/l  | ND       | 06/05/97         | KLF     | 0.02   |               |     |
| Mercury   | mg/l  | ND       | 06/04/97         | APP     | 0.0002 |               |     |
| Nickel    | mg/l  | 0.059    | 06/05/97         | KLF     | 0.002  |               |     |
| Selenium  | mg/l  | ND       | 06/05/97         | KLF     | 0.05   |               |     |
| Silver    | mg/l  | ND       | 06/05/97         | KLF     | 0.005  |               |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163

Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802

Job Number: 29802

Sample Matrix: GRND WATER

Sampled: 05/27/97

MONITORING WELL #2

MW-2

|          | Units | 97809740 | Date Analyzed | Analyst | MDL   | SPEC LIMIT | P/F |
|----------|-------|----------|---------------|---------|-------|------------|-----|
|          |       |          |               |         |       |            |     |
| Thallium | mg/l  | ND       | 06/05/97      | KLF     | 0.10  |            |     |
| Zinc     | mg/l  | 0.020    | 06/05/97      | KLF     | 0.005 |            |     |

Sampled: 05/27/97

MONITORING WELL #3

MW-3

|           | Units | 97809752 | Date Analyzed | Analyst | MDL    | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|--------|------------|-----|
|           |       |          |               |         |        |            |     |
| Antimony  | mg/l  | ND       | 06/05/97      | KLF     | 0.02   |            |     |
| Arsenic   | mg/l  | ND       | 06/05/97      | KLF     | 0.05   |            |     |
| Beryllium | mg/l  | ND       | 06/05/97      | KLF     | 0.0010 |            |     |
| Cadmium   | mg/l  | ND       | 06/05/97      | KLF     | 0.0005 |            |     |
| Chromium  | mg/l  | ND       | 06/05/97      | KLF     | 0.004  |            |     |
| Copper    | mg/l  | 0.0015   | 06/05/97      | KLF     | 0.0010 |            |     |
| Lead      | mg/l  | ND       | 06/05/97      | KLF     | 0.02   |            |     |
| Mercury   | mg/l  | ND       | 06/04/97      | APP     | 0.0002 |            |     |
| Nickel    | mg/l  | 0.009    | 06/05/97      | KLF     | 0.002  |            |     |
| Selenium  | mg/l  | ND       | 06/05/97      | KLF     | 0.05   |            |     |
| Silver    | mg/l  | ND       | 06/05/97      | KLF     | 0.005  |            |     |
| Thallium  | mg/l  | ND       | 06/05/97      | KLF     | 0.10   |            |     |
| Zinc      | mg/l  | 0.118    | 06/05/97      | KLF     | 0.005  |            |     |

Sampled: 05/27/97

MONITORING WELL #4

MW-4

|          | Units | 97809744 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|-------|----------|---------------|---------|------|------------|-----|
|          |       |          |               |         |      |            |     |
| Antimony | mg/l  | ND       | 06/05/97      | KLF     | 0.02 |            |     |

MDL = Method Detection Limit

ND = Not Detected

BDL = Below Detection Limit

NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163  
 Project Number: PROJ.# A0163

 LIMS-BAT #: LIMS-29802  
 Job Number: 29802  
 Sample Matrix: GRND WATER

 Sampled: 05/27/97  
 MONITORING WELL #4  
 MW-4

|           | Units | 97809744 | Date Analyzed | Analyst | MDL    | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|--------|------------|-----|
| -----     | ----- | -----    | -----         | -----   | ---    | -----      | --- |
| Arsenic   | mg/l  | ND       | 06/05/97      | KLF     | 0.05   |            |     |
| Beryllium | mg/l  | ND       | 06/05/97      | KLF     | 0.0010 |            |     |
| Cadmium   | mg/l  | ND       | 06/05/97      | KLF     | 0.0005 |            |     |
| Chromium  | mg/l  | ND       | 06/05/97      | KLF     | 0.004  |            |     |
| Copper    | mg/l  | 0.0824   | 06/05/97      | KLF     | 0.0010 |            |     |
| Lead      | mg/l  | ND       | 06/05/97      | KLF     | 0.02   |            |     |
| Mercury   | mg/l  | ND       | 06/04/97      | APP     | 0.0002 |            |     |
| Nickel    | mg/l  | 0.284    | 06/05/97      | KLF     | 0.002  |            |     |
| Selenium  | mg/l  | ND       | 06/05/97      | KLF     | 0.05   |            |     |
| Silver    | mg/l  | ND       | 06/05/97      | KLF     | 0.005  |            |     |
| Thallium  | mg/l  | ND       | 06/05/97      | KLF     | 0.10   |            |     |
| Zinc      | mg/l  | 0.298    | 06/05/97      | KLF     | 0.005  |            |     |

 Sampled: 05/27/97  
 MONITORING WELL #5  
 MW-5

|           | Units | 97809760 | Date Analyzed | Analyst | MDL    | SPEC LIMIT | P/F |
|-----------|-------|----------|---------------|---------|--------|------------|-----|
| -----     | ----- | -----    | -----         | -----   | ---    | -----      | --- |
| Antimony  | mg/l  | ND       | 06/05/97      | KLF     | 0.02   |            |     |
| Arsenic   | mg/l  | ND       | 06/05/97      | KLF     | 0.05   |            |     |
| Beryllium | mg/l  | ND       | 06/05/97      | KLF     | 0.0010 |            |     |
| Cadmium   | mg/l  | ND       | 06/05/97      | KLF     | 0.0005 |            |     |
| Chromium  | mg/l  | ND       | 06/05/97      | KLF     | 0.004  |            |     |
| Copper    | mg/l  | 0.0028   | 06/05/97      | KLF     | 0.0010 |            |     |
| Lead      | mg/l  | ND       | 06/05/97      | KLF     | 0.02   |            |     |
| Mercury   | mg/l  | ND       | 06/04/97      | APP     | 0.0002 |            |     |
| Nickel    | mg/l  | 0.012    | 06/05/97      | KLF     | 0.002  |            |     |
| Selenium  | mg/l  | ND       | 06/05/97      | KLF     | 0.05   |            |     |
| Silver    | mg/l  | ND       | 06/05/97      | KLF     | 0.005  |            |     |
| Thallium  | mg/l  | ND       | 06/05/97      | KLF     | 0.10   |            |     |

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163  
 Project Number: PROJ.# A0163

 LIMS-BAT #: LIMS-29802  
 Job Number: 29802  
 Sample Matrix: GRND WATER

 Sampled: 05/27/97  
 MONITORING WELL #5  
 MW-5

|     | Units | 97809760 | Date<br>Analyzed | Analyst | MDL   | SPEC<br>LIMIT | P/F |
|-----|-------|----------|------------------|---------|-------|---------------|-----|
| inc | mg/l  | 0.022    | 06/05/97         | KLF     | 0.005 |               |     |

 Sampled: 05/27/97  
 MONITORING WELL #6  
 MW-6

|           | Units | 97809748 | Date<br>Analyzed | Analyst | MDL    | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|--------|---------------|-----|
| Antimony  | mg/l  | ND       | 06/05/97         | KLF     | 0.02   |               |     |
| Arsenic   | mg/l  | ND       | 06/05/97         | KLF     | 0.05   |               |     |
| Beryllium | mg/l  | ND       | 06/05/97         | KLF     | 0.0010 |               |     |
| Cadmium   | mg/l  | ND       | 06/05/97         | KLF     | 0.0005 |               |     |
| Chromium  | mg/l  | ND       | 06/05/97         | KLF     | 0.004  |               |     |
| Copper    | mg/l  | 0.0016   | 06/05/97         | KLF     | 0.0010 |               |     |
| Lead      | mg/l  | ND       | 06/05/97         | KLF     | 0.02   |               |     |
| Mercury   | mg/l  | ND       | 06/04/97         | APP     | 0.0002 |               |     |
| Nickel    | mg/l  | ND       | 06/05/97         | KLF     | 0.002  |               |     |
| Selenium  | mg/l  | ND       | 06/05/97         | KLF     | 0.05   |               |     |
| Silver    | mg/l  | ND       | 06/05/97         | KLF     | 0.005  |               |     |
| Thallium  | mg/l  | ND       | 06/05/97         | KLF     | 0.10   |               |     |
| Zinc      | mg/l  | 0.014    | 06/05/97         | KLF     | 0.005  |               |     |

Analytical Method(s):

EPA 200.7/EPA 245.1

ALL METALS EXCEPT MERCURY: EPA 200.7

 SAMPLES ARE DIGESTED WITH MINERAL ACIDS AND ANALYZED BY INDUCTIVELY COUPLED  
 PLASMA EMISSION SPECTROSCOPY. (ICP)

 MDL = Method Detection Limit  
 ND = Not Detected  
 BDL = Below Detection Limit  
 NM = Not Measured

 SPEC LIMIT = a client specified, recommended, or  
 regulatory level for comparison with data to  
 determine PASS (P) or FAIL (F) condition of results.

MERCURY: EPA 245.1

SAMPLES ARE DIGESTED WITH MINERAL ACIDS AND ANALYZED BY MANUAL COLD VAPOR  
ATOMIC ABSORPTION SPECTROPHOTOMETRY.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #3  
MW-3

|           | Units | 97B09757 | Date<br>Analyzed | Analyst | MDL    | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|--------|---------------|-----|
|           |       |          |                  |         |        |               |     |
| Manganese | mg/l  | 18.9     | 06/06/97         | KLF     | 0.0010 |               |     |

Sampled: 05/27/97  
MONITORING WELL #5  
MW-5

|           | Units | 97B09765 | Date<br>Analyzed | Analyst | MDL    | SPEC<br>LIMIT | P/F |
|-----------|-------|----------|------------------|---------|--------|---------------|-----|
|           |       |          |                  |         |        |               |     |
| Manganese | mg/l  | 49.8     | 06/06/97         | KLF     | 0.0010 |               |     |

Analytical Method(s):

EPA 200.7

SAMPLES ARE DIGESTED WITH MINERAL ACIDS AND ANALYZED BY INDUCTIVELY COUPLED  
PLASMA EMISSION SPECTROMETRY (ICP).

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #3  
MW-3

|         | Units | 97809755 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|---------|-------|----------|------------------|---------|------|---------------|-----|
| Nitrate | mg/l  | ND       | 05/29/97         | RCL     | 0.05 |               |     |

Sampled: 05/27/97  
MONITORING WELL #5  
MW-5

|         | Units | 97809763 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|---------|-------|----------|------------------|---------|------|---------------|-----|
| Nitrate | mg/l  | ND       | 05/29/97         | RCL     | 0.05 |               |     |

Analytical Method(s):

SM 4500-NO3 F

AUTOMATED-COLORIMETRIC ANALYSIS WITH SULFANILAMIDE, AMMONIUM CHLORIDE  
AND CADMIUM REDUCTION

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #1  
MW-1

|               | Units | 97809738 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| PCB 1221      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1232      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1242/1016 | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1248      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1254      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1260      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| Total PCB     | ug/l  | ND       | 05/31/97         | JB      | 0.10 |               |     |

Sampled: 05/27/97  
MONITORING WELL #2  
MW-2

|               | Units | 97809742 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| PCB 1221      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1232      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1242/1016 | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1248      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1254      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1260      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| Total PCB     | ug/l  | ND       | 05/31/97         | JB      | 0.10 |               |     |

Sampled: 05/27/97  
MONITORING WELL #3  
MW-3

|          | Units | 97809754 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|----------|-------|----------|------------------|---------|-----|---------------|-----|
| -----    | ----- | -----    | -----            | -----   | --- | -----         | --- |
| PCB 1221 | ug/l  | ND       | 05/31/97         | JB      |     |               |     |
| PCB 1232 | ug/l  | ND       | 05/31/97         | JB      |     |               |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #3  
MW-3

|               | Units | 97809754 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| PCB 1242/1016 | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1248      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1254      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1260      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| Total PCB     | ug/l  | ND       | 05/31/97         | JB      | 0.10 |               |     |

Sampled: 05/27/97  
MONITORING WELL #4  
MW-4

|               | Units | 97809746 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|------|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | ---  | -----         | --- |
| PCB 1221      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1232      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1242/1016 | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1248      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1254      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| PCB 1260      | ug/l  | ND       | 05/31/97         | JB      |      |               |     |
| Total PCB     | ug/l  | ND       | 05/31/97         | JB      | 0.10 |               |     |

Sampled: 05/27/97  
MONITORING WELL #5  
MW-5

|               | Units | 97809762 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|---------------|-------|----------|------------------|---------|-----|---------------|-----|
| -----         | ----- | -----    | -----            | -----   | --- | -----         | --- |
| PCB 1221      | ug/l  | ND       | 05/31/97         | JB      |     |               |     |
| PCB 1232      | ug/l  | ND       | 05/31/97         | JB      |     |               |     |
| PCB 1242/1016 | ug/l  | ND       | 05/31/97         | JB      |     |               |     |
| PCB 1248      | ug/l  | ND       | 05/31/97         | JB      |     |               |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

| Sampled: 05/27/97  |       |          |               |         |      |            |     |
|--------------------|-------|----------|---------------|---------|------|------------|-----|
| MONITORING WELL #5 |       |          |               |         |      |            |     |
| MW-5               |       |          |               |         |      |            |     |
|                    | Units | 97809762 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
| -----              |       |          |               |         |      |            |     |
| CB 1254            | ug/l  | ND       | 05/31/97      | JB      |      |            |     |
| CB 1260            | ug/l  | ND       | 05/31/97      | JB      |      |            |     |
| Total PCB          | ug/l  | ND       | 05/31/97      | JB      | 0.10 |            |     |

| Sampled: 05/27/97  |       |          |               |         |      |            |     |
|--------------------|-------|----------|---------------|---------|------|------------|-----|
| MONITORING WELL #6 |       |          |               |         |      |            |     |
| MW-6               |       |          |               |         |      |            |     |
|                    | Units | 97809750 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
| -----              |       |          |               |         |      |            |     |
| CB 1221            | ug/l  | ND       | 05/31/97      | JB      |      |            |     |
| PCB 1232           | ug/l  | ND       | 05/31/97      | JB      |      |            |     |
| PCB 1242/1016      | ug/l  | ND       | 05/31/97      | JB      |      |            |     |
| PCB 1248           | ug/l  | ND       | 05/31/97      | JB      |      |            |     |
| PCB 1254           | ug/l  | ND       | 05/31/97      | JB      |      |            |     |
| PCB 1260           | ug/l  | ND       | 05/31/97      | JB      |      |            |     |
| Total PCB          | ug/l  | ND       | 05/31/97      | JB      | 0.10 |            |     |

Analytical Method(s):

EPA 608

SAMPLES ARE EXTRACTED INTO METHYLENE CHLORIDE, SOLVENT EXCHANGED WITH HEXANE, CONCENTRATED BY KUDERNA-DANISH EVAPORATIVE METHODS, AND ANALYZED BY GAS CHROMATOGRAPHY WITH ELECTRON CAPTURE DETECTION.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #3  
MW-3

|       | Units | 97809758 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|-------|-------|----------|------------------|---------|-----|---------------|-----|
| ----- | ----- | -----    | -----            | -----   | --- | -----         | --- |
| pH    | units | 6.45     | 05/28/97         | ALB     |     |               |     |

Sampled: 05/27/97  
MONITORING WELL #5  
MW-5

|       | Units | 97809766 | Date<br>Analyzed | Analyst | MDL | SPEC<br>LIMIT | P/F |
|-------|-------|----------|------------------|---------|-----|---------------|-----|
| ----- | ----- | -----    | -----            | -----   | --- | -----         | --- |
| pH    | units | 6.07     | 05/28/97         | ALB     |     |               |     |

Analytical Method(s):

EPA 150.1

ELECTRODE DETERMINATION

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

|                              |       |          |          |         |     |       |     |
|------------------------------|-------|----------|----------|---------|-----|-------|-----|
| Sampled: 05/27/97            |       |          |          |         |     |       |     |
| MONITORING WELL #3           |       |          |          |         |     |       |     |
| MW-3                         |       |          |          |         |     |       |     |
|                              | Units | 97809758 | Date     | Analyst | MDL | SPEC  |     |
|                              |       |          | Analyzed |         |     | LIMIT | P/F |
| -----                        | ----- | -----    | -----    | -----   | --- | ----- | --- |
| Total Dissolved Solids (TDS) | mg/l  | 468      | 05/31/97 | ALB     | 5.0 |       |     |

|                              |       |          |          |         |     |       |     |
|------------------------------|-------|----------|----------|---------|-----|-------|-----|
| Sampled: 05/27/97            |       |          |          |         |     |       |     |
| MONITORING WELL #5           |       |          |          |         |     |       |     |
| MW-5                         |       |          |          |         |     |       |     |
|                              | Units | 97809766 | Date     | Analyst | MDL | SPEC  |     |
|                              |       |          | Analyzed |         |     | LIMIT | P/F |
| -----                        | ----- | -----    | -----    | -----   | --- | ----- | --- |
| Total Dissolved Solids (TDS) | mg/l  | 280      | 05/31/97 | ALB     | 5.0 |       |     |

Analytical Method(s):

SM 2540 C

GRAVIMETRIC DETERMINATION OF TOTAL SOLIDS LEFT IN FILTRATE  
AFTER DRYING AT 180 C.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

Sampled: 05/27/97  
MONITORING WELL #1  
MW-1

|                              | Units | 97B09735 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/l  | BDL      | 06/05/97      | AMC     | 0.42 |            |     |

Sampled: 05/27/97  
MONITORING WELL #2  
MW-2

|                              | Units | 97B09739 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/l  | 0.65     | 06/05/97      | AMC     | 0.42 |            |     |

Sampled: 05/27/97  
MONITORING WELL #3  
MW-3

|                              | Units | 97B09751 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/l  | 8.93     | 06/05/97      | AMC     | 0.41 |            |     |

Sampled: 05/27/97  
MONITORING WELL #4  
MW-4

|                              | Units | 97B09743 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------------------------------|-------|----------|---------------|---------|------|------------|-----|
| -----                        | ----- | -----    | -----         | -----   | ---  | -----      | --- |
| Total Petroleum Hydrocarbons | mg/l  | ND       | 06/05/97      | AMC     | 0.42 |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

|                              |       |          |          |         |      |       |
|------------------------------|-------|----------|----------|---------|------|-------|
| Sampled: 05/27/97            |       |          |          |         |      |       |
| MONITORING WELL #5           |       |          |          |         |      |       |
| MW-5                         |       |          |          |         |      |       |
|                              | Units | 97809759 | Date     | Analyst | MDL  | SPEC  |
|                              |       |          | Analyzed |         |      | LIMIT |
|                              |       |          |          |         |      | P/F   |
| -----                        |       |          |          |         |      |       |
| Total Petroleum Hydrocarbons | mg/l  | ND       | 06/05/97 | AMC     | 0.42 |       |

|                              |       |          |          |         |      |       |
|------------------------------|-------|----------|----------|---------|------|-------|
| Sampled: 05/27/97            |       |          |          |         |      |       |
| MONITORING WELL #6           |       |          |          |         |      |       |
| MW-6                         |       |          |          |         |      |       |
|                              | Units | 97809747 | Date     | Analyst | MDL  | SPEC  |
|                              |       |          | Analyzed |         |      | LIMIT |
|                              |       |          |          |         |      | P/F   |
| -----                        |       |          |          |         |      |       |
| Total Petroleum Hydrocarbons | mg/l  | 16.1     | 06/05/97 | AMC     | 0.42 |       |

Analytical Method(s):

EPA 418.1

INFRA-RED DETERMINATION FOLLOWING LIQUID-LIQUID EXTRACTION OF  
HYDROCARBONS INTO 1,1,2-TRICHLORO- 1,2,2-TRIFLUOROETHANE (FREON 113)

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

Purchase Order Number: A0163  
Project Number: PROJ.# A0163

LIMS-BAT #: LIMS-29802  
Job Number: 29802  
Sample Matrix: GRND WATER

|                              |       |          |               |         |     |            |     |
|------------------------------|-------|----------|---------------|---------|-----|------------|-----|
| Sampled: 05/27/97            |       |          |               |         |     |            |     |
| MONITORING WELL #3           |       |          |               |         |     |            |     |
| MW-3                         |       |          |               |         |     |            |     |
|                              | Units | 97809758 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
| -----                        | ----- | -----    | -----         | -----   | --- | -----      | --- |
| Total Suspended Solids (TSS) | mg/l  | 76       | 05/29/97      | ALB     | 10  |            |     |

|                              |       |          |               |         |     |            |     |
|------------------------------|-------|----------|---------------|---------|-----|------------|-----|
| Sampled: 05/27/97            |       |          |               |         |     |            |     |
| MONITORING WELL #5           |       |          |               |         |     |            |     |
| MW-5                         |       |          |               |         |     |            |     |
|                              | Units | 97809766 | Date Analyzed | Analyst | MDL | SPEC LIMIT | P/F |
| -----                        | ----- | -----    | -----         | -----   | --- | -----      | --- |
| Total Suspended Solids (TSS) | mg/l  | 520      | 05/29/97      | ALB     | 10  |            |     |

Analytical Method(s):

SH 2540 D

GRAVIMETRIC DETERMINATION OF TOTAL SOLIDS RETAINED ON A GLASS  
FIBER FILTER AFTER DRYING AT 103-105 C.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.



The following notes were attached to the reported analysis:

Sample: 97809762

ALL ACID FRACTION COMPOUNDS NOT REPORTED DUE TO UNACCEPTABLE SURROGATE  
STANDARD RECOVERIES. NO SAMPLE REMAINED FOR RE-EXTRACTION.

Sample: 97809736

Analysis: Mercury

SAMPLES WERE FILTERED PRIOR TO PRESERVATION. RESULTS ARE FOR DISSOLVED  
MERCURY NOT TOTAL.

Sample: 97809736

Analysis: Silver

SAMPLES WERE FILTERED IN THE LABORATORY PRIOR TO PRESERVATION.  
ALL RESULTS ARE FOR DISSOLVED METALS CONTENT.

Samples: 97809738, 97809754

ACID FRACTION ELEVATED LIMITS OF DETECTION DUE TO SAMPLE MATRIX INTERFERENCES.

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 1 of 22

QC Batch Number: B00-0487

| Sample Id    | Analysis | QC Analysis         | Values | Units | Limits      |
|--------------|----------|---------------------|--------|-------|-------------|
| -----        | -----    | -----               | -----  | ----- | -----       |
| STDADD-05869 | B00      | Standard Measured   | 170.0  | mg/l  | 130.0-232.0 |
|              |          | Standard Amt Added  | 200.0  | mg/l  |             |
|              |          | Standard % Recovery | 85.0   | %     |             |

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 2 of 22

QC Batch Number: GC/ECD-1302

| Sample Id     | Analysis            | QC Analysis          | Values | Units | Limits |
|---------------|---------------------|----------------------|--------|-------|--------|
| -----         | -----               | -----                | -----  | ----- | -----  |
| BLANK-08087   | PCB 1232            | Blank                | 0.00   | ug/l  |        |
|               | PCB 1242/1016       | Blank                | 0.00   | ug/l  |        |
|               | PCB 1254            | Blank                | 0.00   | ug/l  |        |
|               | PCB 1260            | Blank                | 0.00   | ug/l  |        |
|               | PCB 1248            | Blank                | 0.00   | ug/l  |        |
|               | PCB 1221            | Blank                | 0.00   | ug/l  |        |
|               | Total PCB           | Blank                | <0.05  | ug/l  |        |
|               | Dibutylchloredate ( | Blank                | 75.0   | %     |        |
| LFBLANK-04002 | PCB 1260            | Lab Fort Blank Amt.  | 1.00   | ug/l  |        |
|               |                     | Lab Fort Blk. Found  | 1.06   | ug/l  |        |
|               |                     | Lab Fort Blk. % Rec. | 106.00 | %     |        |
|               | Total PCB           | Lab Fort Blank Amt.  | 1.00   | ug/l  |        |
|               |                     | Lab Fort Blk. Found  | 1.06   | ug/l  |        |
|               |                     | Lab Fort Blk. % Rec. | 106.00 | %     |        |
|               | Dibutylchloredate ( | Lab Fort Blank Amt.  | 100.0  | %     |        |

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 3 of 22

QC Batch Number: GCMS/SEMI-0769

| Sample Id   | Analysis             | QC Analysis        | Values | Units | Limits     |
|-------------|----------------------|--------------------|--------|-------|------------|
| 97809738    | Phenol - D6 wet reco | Surrogate Recovery | 33.5   | %     | 10.0-94.0  |
|             | Nitrobenzene - D5 we | Surrogate Recovery | 76.2   | %     | 35.0-114.0 |
|             | 2-Fluorobiphenyl wet | Surrogate Recovery | 80.2   | %     | 43.0-116.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 68.6   | %     | 10.0-123.0 |
|             | Terphenyl - D14 (liq | Surrogate Recovery | 81.7   | %     | 33.0-141.0 |
|             | 2-Fluorophenol wet r | Surrogate Recovery | 52.4   | %     | 21.0-100.0 |
| 97809742    | Phenol - D6 wet reco | Surrogate Recovery | 23.8   | %     | 10.0-94.0  |
|             | Nitrobenzene - D5 we | Surrogate Recovery | 86.7   | %     | 35.0-114.0 |
|             | 2-Fluorobiphenyl wet | Surrogate Recovery | 81.2   | %     | 43.0-116.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 79.6   | %     | 10.0-123.0 |
|             | Terphenyl - D14 (liq | Surrogate Recovery | 80.2   | %     | 33.0-141.0 |
|             | 2-Fluorophenol wet r | Surrogate Recovery | 39.0   | %     | 21.0-100.0 |
| 97809746    | Phenol - D6 wet reco | Surrogate Recovery | 26.0   | %     | 10.0-94.0  |
|             | Nitrobenzene - D5 we | Surrogate Recovery | 68.7   | %     | 35.0-114.0 |
|             | 2-Fluorobiphenyl wet | Surrogate Recovery | 71.3   | %     | 43.0-116.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 59.8   | %     | 10.0-123.0 |
|             | Terphenyl - D14 (liq | Surrogate Recovery | 76.2   | %     | 33.0-141.0 |
|             | 2-Fluorophenol wet r | Surrogate Recovery | 41.0   | %     | 21.0-100.0 |
| 97809750    | Phenol - D6 wet reco | Surrogate Recovery | 27.0   | %     | 10.0-94.0  |
|             | Nitrobenzene - D5 we | Surrogate Recovery | 62.3   | %     | 35.0-114.0 |
|             | 2-Fluorobiphenyl wet | Surrogate Recovery | 68.8   | %     | 43.0-116.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 62.1   | %     | 10.0-123.0 |
|             | Terphenyl - D14 (liq | Surrogate Recovery | 56.2   | %     | 33.0-141.0 |
|             | 2-Fluorophenol wet r | Surrogate Recovery | 39.0   | %     | 21.0-100.0 |
| 97809754    | Phenol - D6 wet reco | Surrogate Recovery | 41.2   | %     | 10.0-94.0  |
|             | Nitrobenzene - D5 we | Surrogate Recovery | 83.7   | %     | 35.0-114.0 |
|             | 2-Fluorobiphenyl wet | Surrogate Recovery | 90.9   | %     | 43.0-116.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 95.5   | %     | 10.0-123.0 |
|             | Terphenyl - D14 (liq | Surrogate Recovery | 86.0   | %     | 33.0-141.0 |
|             | 2-Fluorophenol wet r | Surrogate Recovery | 64.5   | %     | 21.0-100.0 |
| 97809762    | Phenol - D6 wet reco | Surrogate Recovery | 0.0    | %     | 10.0-94.0  |
|             | Nitrobenzene - D5 we | Surrogate Recovery | 65.7   | %     | 35.0-114.0 |
|             | 2-Fluorobiphenyl wet | Surrogate Recovery | 77.1   | %     | 43.0-116.0 |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 2.9    | %     | 10.0-123.0 |
|             | Terphenyl - D14 (liq | Surrogate Recovery | 86.8   | %     | 33.0-141.0 |
|             | 2-Fluorophenol wet r | Surrogate Recovery | 1.3    | %     | 21.0-100.0 |
| BLANK-08102 | 1,4-Dichlorobenzene  | Blank              | <10.00 | ug/l  |            |
|             | Naphthalene          | Blank              | <10.00 | ug/l  |            |
|             | 1,2-Dichlorobenzene  | Blank              | <10.00 | ug/l  |            |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 4 of 22

QC Batch Number: GCMS/SEMI-0769

| Sample Id | Analysis             | QC Analysis | Values | Units | Limits |
|-----------|----------------------|-------------|--------|-------|--------|
| -----     | -----                | -----       | -----  | ----- | -----  |
|           | 1,3-Dichlorobenzene  | Blank       | <10.00 | ug/l  |        |
|           | Acenaphthene         | Blank       | <10.00 | ug/l  |        |
|           | Acenaphthylene       | Blank       | <10.00 | ug/l  |        |
|           | Aniline              | Blank       | <10.00 | ug/l  |        |
|           | Anthracene           | Blank       | <10.00 | ug/l  |        |
|           | Benzydene            | Blank       | <70.00 | ug/l  |        |
|           | Benzo(a)anthracene   | Blank       | <10.00 | ug/l  |        |
|           | Benzo(a)pyrene       | Blank       | <20.00 | ug/l  |        |
|           | Benzo(b)fluoranthene | Blank       | <10.00 | ug/l  |        |
|           | Benzo(g,h,i)perylene | Blank       | <30.00 | ug/l  |        |
|           | Benzoic Acid         | Blank       | <30.00 | ug/l  |        |
|           | Benzyl Alcohol       | Blank       | <20.00 | ug/l  |        |
|           | Bis(2-chloroethyl)et | Blank       | <10.00 | ug/l  |        |
|           | Bis(2-chloroethoxy)m | Blank       | <10.00 | ug/l  |        |
|           | Bis(2-chloroisoproyl | Blank       | <10.00 | ug/l  |        |
|           | Bis(2-ethylhexyl)pht | Blank       | <10.00 | ug/l  |        |
|           | 4-Bromophenylphenyle | Blank       | <10.00 | ug/l  |        |
|           | Butylbenzylphthalate | Blank       | <20.00 | ug/l  |        |
|           | 4-Chloroaniline      | Blank       | <20.00 | ug/l  |        |
|           | 2-Chloronaphthalene  | Blank       | <10.00 | ug/l  |        |
|           | 4-Chlorophenylphenyl | Blank       | <10.00 | ug/l  |        |
|           | Chrysene             | Blank       | <20.00 | ug/l  |        |
|           | Dibenz(a,h)anthracen | Blank       | <20.00 | ug/l  |        |
|           | Dibenzofuran         | Blank       | <10.00 | ug/l  |        |
|           | 3,3'-Dichlorobenzidi | Blank       | <20.00 | ug/l  |        |
|           | Diethylphthalate     | Blank       | <10.00 | ug/l  |        |
|           | Dimethylphthalate    | Blank       | <20.00 | ug/l  |        |
|           | Di-n-butylphthalate  | Blank       | <10.00 | ug/l  |        |
|           | 2,4-Dinitrotoluene   | Blank       | <10.00 | ug/l  |        |
|           | 2,6-Dinitrotoluene   | Blank       | <10.00 | ug/l  |        |
|           | 1,2-Diphenylhydrazin | Blank       | <10.00 | ug/l  |        |
|           | Di-n-octylphthalate  | Blank       | <20.00 | ug/l  |        |
|           | Fluoranthene         | Blank       | <10.00 | ug/l  |        |
|           | Fluorene             | Blank       | <10.00 | ug/l  |        |
|           | Hexachlorobenzene    | Blank       | <10.00 | ug/l  |        |
|           | Hexachlorobutadiene  | Blank       | <10.00 | ug/l  |        |
|           | Hexachlorocyclopenta | Blank       | <10.00 | ug/l  |        |
|           | Hexachloroethane     | Blank       | <10.00 | ug/l  |        |
|           | Indeno(1,2,3-cd)pyre | Blank       | <10.00 | ug/l  |        |

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 5 of 22

QC Batch Number: GCMS/SEMI-0769

| Sample Id     | Analysis             | QC Analysis          | Values | Units | Limits |
|---------------|----------------------|----------------------|--------|-------|--------|
|               | Isophorone           | Blank                | <10.00 | ug/l  |        |
|               | 2-Methylnaphthalene  | Blank                | <10.00 | ug/l  |        |
|               | 2-Nitroaniline       | Blank                | <10.00 | ug/l  |        |
|               | 3-Nitroaniline       | Blank                | <10.00 | ug/l  |        |
|               | Nitrobenzene         | Blank                | <10.00 | ug/l  |        |
|               | N-Nitrosodimethylami | Blank                | <10.00 | ug/l  |        |
|               | N-Nitroso-di-n-propy | Blank                | <10.00 | ug/l  |        |
|               | N-Nitrosodiphenylami | Blank                | <10.00 | ug/l  |        |
|               | Phenanthrene         | Blank                | <10.00 | ug/l  |        |
|               | Pyrene               | Blank                | <30.00 | ug/l  |        |
|               | 1,2,4-Trichlorobenze | Blank                | <10.00 | ug/l  |        |
|               | 4-Chloro-3-methylphe | Blank                | <20.00 | ug/l  |        |
|               | 2-Chlorophenol       | Blank                | <10.00 | ug/l  |        |
|               | 2,4-Dichlorophenol   | Blank                | <10.00 | ug/l  |        |
|               | 2,4-Dimethylphenol   | Blank                | <40.00 | ug/l  |        |
|               | 4,6-Dinitro-2-methyl | Blank                | <10.00 | ug/l  |        |
|               | 2,4-Dinitrophenol    | Blank                | <10.00 | ug/l  |        |
|               | 2-Methylphenol (o-cr | Blank                | <10.00 | ug/l  |        |
|               | 3- & 4-Methylphenol  | Blank                | <10.00 | ug/l  |        |
|               | 2-Nitrophenol        | Blank                | <10.00 | ug/l  |        |
|               | 4-Nitrophenol        | Blank                | <10.00 | ug/l  |        |
|               | Phenol               | Blank                | <10.00 | ug/l  |        |
|               | 2,4,5-Trichloropheno | Blank                | <10.00 | ug/l  |        |
|               | 2,4,6-Trichloropheno | Blank                | <10.00 | ug/l  |        |
|               | Pentachlorophenol    | Blank                | <10.00 | ug/l  |        |
|               | Pyridine             | Blank                | <10.0  | ug/l  |        |
|               | Benzo(k)fluoranthene | Blank                | <20.00 | ug/l  |        |
|               | 4-Nitroaniline       | Blank                | <10.00 | ug/l  |        |
| LFBLANK-04009 | 1,4-Dichlorobenzene  | Lab Fort Blank Amt.  | 100.00 | ug/l  |        |
|               |                      | Lab Fort Blk. Found  | 49.23  | ug/l  |        |
|               |                      | Lab Fort Blk. % Rec. | 49.23  | %     |        |
|               | Acenaphthene         | Lab Fort Blank Amt.  | 100.00 | ug/l  |        |
|               |                      | Lab Fort Blk. Found  | 73.67  | ug/l  |        |
|               |                      | Lab Fort Blk. % Rec. | 73.67  | %     |        |
|               | 2,4-Dinitrotoluene   | Lab Fort Blank Amt.  | 100.00 | ug/l  |        |
|               |                      | Lab Fort Blk. Found  | 68.71  | ug/l  |        |
|               |                      | Lab Fort Blk. % Rec. | 68.71  | %     |        |
|               | N-Nitroso-di-n-propy | Lab Fort Blank Amt.  | 100.00 | ug/l  |        |
|               |                      | Lab Fort Blk. Found  | 70.22  | ug/l  |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 6 of 22

QC Batch Number: GCMS/SEMI-0769

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits |
|-----------|----------------------|----------------------|--------|-------|--------|
| -----     | -----                | -----                | -----  | ----- | -----  |
|           |                      | Lab Fort Blk. % Rec. | 70.22  | %     |        |
|           | Pyrene               | Lab Fort Blank Amt.  | 100.00 | ug/l  |        |
|           |                      | Lab Fort Blk. Found  | 85.00  | ug/l  |        |
|           |                      | Lab Fort Blk. % Rec. | 85.00  | %     |        |
|           | 1,2,4-Trichlorobenze | Lab Fort Blank Amt.  | 100.00 | ug/l  |        |
|           |                      | Lab Fort Blk. Found  | 48.53  | ug/l  |        |
|           |                      | Lab Fort Blk. % Rec. | 48.53  | %     |        |
|           | 4-Chloro-3-methylphe | Lab Fort Blank Amt.  | 200.00 | ug/l  |        |
|           |                      | Lab Fort Blk. Found  | 135.73 | ug/l  |        |
|           |                      | Lab Fort Blk. % Rec. | 67.86  | %     |        |
|           | 2-Chlorophenol       | Lab Fort Blank Amt.  | 200.00 | ug/l  |        |
|           |                      | Lab Fort Blk. Found  | 129.04 | ug/l  |        |
|           |                      | Lab Fort Blk. % Rec. | 64.52  | %     |        |
|           | 4-Nitrophenol        | Lab Fort Blank Amt.  | 200.00 | ug/l  |        |
|           |                      | Lab Fort Blk. Found  | 73.60  | ug/l  |        |
|           |                      | Lab Fort Blk. % Rec. | 36.80  | %     |        |
|           | Phenol               | Lab Fort Blank Amt.  | 200.00 | ug/l  |        |
|           |                      | Lab Fort Blk. Found  | 48.68  | ug/l  |        |
|           |                      | Lab Fort Blk. % Rec. | 24.34  | %     |        |
|           | Pentachlorophenol    | Lab Fort Blank Amt.  | 200.00 | ug/l  |        |
|           |                      | Lab Fort Blk. Found  | 144.95 | ug/l  |        |
|           |                      | Lab Fort Blk. % Rec. | 72.48  | %     |        |

## QC SUMMARY REPORT

 SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 7 of 22

QC Batch Number: GCMS/VOL-1329

| Sample Id   | Analysis              | QC Analysis          | Values | Units | Limits     |
|-------------|-----------------------|----------------------|--------|-------|------------|
| 97809737    | d4-12-Dichloroethane  | Surrogate Recovery   | 109.2  | %     | 56.0-128.0 |
|             | d8-Toluene            | Surrogate Recovery   | 102.4  | %     | 65.0-113.0 |
|             | Bromofluorobenzene    | Surrogate Recovery   | 109.6  | %     | 62.0-137.0 |
| 97809741    | d4-12-Dichloroethane  | Surrogate Recovery   | 110.0  | %     | 56.0-128.0 |
|             | d8-Toluene            | Surrogate Recovery   | 102.4  | %     | 65.0-113.0 |
|             | Bromofluorobenzene    | Surrogate Recovery   | 108.4  | %     | 62.0-137.0 |
| 97809745    | d4-12-Dichloroethane  | Surrogate Recovery   | 105.6  | %     | 56.0-128.0 |
|             | d8-Toluene            | Surrogate Recovery   | 94.4   | %     | 65.0-113.0 |
|             | Bromofluorobenzene    | Surrogate Recovery   | 92.0   | %     | 62.0-137.0 |
| 97809749    | d4-12-Dichloroethane  | Surrogate Recovery   | 108.4  | %     | 56.0-128.0 |
|             | d8-Toluene            | Surrogate Recovery   | 100.0  | %     | 65.0-113.0 |
|             | Bromofluorobenzene    | Surrogate Recovery   | 94.0   | %     | 62.0-137.0 |
| 97809753    | d4-12-Dichloroethane  | Surrogate Recovery   | 106.4  | %     | 56.0-128.0 |
|             | d8-Toluene            | Surrogate Recovery   | 93.6   | %     | 65.0-113.0 |
|             | Bromofluorobenzene    | Surrogate Recovery   | 94.8   | %     | 62.0-137.0 |
| 97809761    | d4-12-Dichloroethane  | Surrogate Recovery   | 111.2  | %     | 56.0-128.0 |
|             | d8-Toluene            | Surrogate Recovery   | 99.6   | %     | 65.0-113.0 |
|             | Bromofluorobenzene    | Surrogate Recovery   | 97.2   | %     | 62.0-137.0 |
| BLANK-08113 | Acetone               | Blank                | <16.1  | ug/l  |            |
|             | Benzene               | Blank                | <0.6   | ug/l  |            |
|             |                       | Matrix Spk Amt Added | 25.0   | ug/l  |            |
|             |                       | MS Amt Measured      | 22.8   | ug/l  |            |
|             |                       | Matrix Spike % Rec.  | 91.4   | %     |            |
|             | Carbon Tetrachloride  | Blank                | <0.5   | ug/l  |            |
|             | Chloroform            | Blank                | <0.8   | ug/l  |            |
|             | 1,2-Dichloroethane    | Blank                | <0.9   | ug/l  |            |
|             | 1,4-Dichlorobenzene   | Blank                | <0.8   | ug/l  |            |
|             | Ethyl Benzene         | Blank                | <0.6   | ug/l  |            |
|             | 2-Butanone (MEK)      | Blank                | <12.0  | ug/l  |            |
|             | 4-Methyl-2-Pentanone  | Blank                | <8.8   | ug/l  |            |
|             | Styrene               | Blank                | <0.7   | ug/l  |            |
|             | Tetrachloroethylene   | Blank                | <0.4   | ug/l  |            |
|             | Toluene               | Blank                | <0.7   | ug/l  |            |
|             |                       | Matrix Spk Amt Added | 25.0   | ug/l  |            |
|             |                       | MS Amt Measured      | 22.5   | ug/l  |            |
|             |                       | Matrix Spike % Rec.  | 90.0   | %     |            |
|             | 1,1,1-Trichloroethane | Blank                | <0.9   | ug/l  |            |





SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 8 of 22

QC Batch Number: GCMS/VOL-1329

| Sample Id | Analysis             | QC Analysis          | Values | Units | Limits |
|-----------|----------------------|----------------------|--------|-------|--------|
| -----     | -----                | -----                | -----  | ----- | -----  |
|           | Trichloroethylene    | Blank                | <1.0   | ug/l  |        |
|           |                      | Matrix Spk Amt Added | 25.0   | ug/l  |        |
|           |                      | MS Amt Measured      | 36.5   | ug/l  |        |
|           |                      | Matrix Spike % Rec.  | 145.9  | %     |        |
|           | Trichlorofluorometha | Blank                | <0.7   | ug/l  |        |
|           | o&p-Xylene           | Blank                | <0.5   | ug/l  |        |
|           | m-Xylene             | Blank                | <1.3   | ug/l  |        |
|           | 1,2-Dichlorobenzene  | Blank                | <0.8   | ug/l  |        |
|           | 1,3-Dichlorobenzene  | Blank                | <0.6   | ug/l  |        |
|           | 1,1-Dichloroethane   | Blank                | <0.7   | ug/l  |        |
|           | 1,1-Dichloroethylene | Blank                | <0.6   | ug/l  |        |
|           |                      | Matrix Spk Amt Added | 25.0   | ug/l  |        |
|           |                      | MS Amt Measured      | 22.4   | ug/l  |        |
|           |                      | Matrix Spike % Rec.  | 89.4   | %     |        |
|           | Methyl tert-Butyl Et | Blank                | <0.8   | ug/l  |        |
|           | t-1,2-Dichloroethyle | Blank                | <0.8   | ug/l  |        |
|           | Vinyl Chloride       | Blank                | <0.3   | ug/l  |        |
|           | Methylene Chloride   | Blank                | 3.2    | ug/l  |        |
|           | Chlorobenzene        | Blank                | <0.6   | ug/l  |        |
|           |                      | Matrix Spk Amt Added | 25.0   | ug/l  |        |
|           |                      | MS Amt Measured      | 26.0   | ug/l  |        |
|           |                      | Matrix Spike % Rec.  | 104.2  | %     |        |
|           | Chloromethane        | Blank                | <1.2   | ug/l  |        |
|           | Bromomethane         | Blank                | <1.2   | ug/l  |        |
|           | Chloroethane         | Blank                | <0.8   | ug/l  |        |
|           | cis-1,3-Dichloroprop | Blank                | <0.5   | ug/l  |        |
|           | t-1,3-Dichloropropen | Blank                | <0.4   | ug/l  |        |
|           | Chlorodibromomethane | Blank                | <0.5   | ug/l  |        |
|           | 1,1,2-Trichloroethan | Blank                | <0.7   | ug/l  |        |
|           | 2-Chloroethylvinylet | Blank                | <9.6   | ug/l  |        |
|           | Bromoform            | Blank                | <1.2   | ug/l  |        |
|           | 1,1,2,2-Tetrachloroe | Blank                | <1.4   | ug/l  |        |
|           | Dibromomethane       | Blank                | <1.1   | ug/l  |        |
|           | cis-1,2-Dichloroethy | Blank                | <0.5   | ug/l  |        |
|           | 1,2-Dichloropropane  | Blank                | <0.6   | ug/l  |        |
|           | 1,2,3-Trichloropropa | Blank                | <1.3   | ug/l  |        |

**SAMPLE QC:** Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

**BATCH QC:** Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 9 of 22

QC Batch Number: GCMS/VOL-1329

| Sample Id | Analysis             | QC Analysis | Values | Units | Limits |
|-----------|----------------------|-------------|--------|-------|--------|
| -----     | -----                | -----       | -----  | ----- | -----  |
|           | Dichlorodifluorometh | Blank       | <1.0   | ug/l  |        |
|           | Iodomethane          | Blank       | <0.8   | ug/l  |        |
|           | Acrolein             | Blank       | <20.0  | ug/l  |        |
|           | Acrylonitrile        | Blank       | <7.6   | ug/l  |        |
|           | Carbon Disulfide     | Blank       | <0.5   | ug/l  |        |
|           | Vinyl Acetate        | Blank       | <16.4  | ug/l  |        |
|           | 2-Hexanone           | Blank       | <9.7   | ug/l  |        |
|           | t-1,4-Dichloro-2-But | Blank       | <2.1   | ug/l  |        |
|           | Ethyl Methacrylate   | Blank       | <0.8   | ug/l  |        |
|           | c-1,4-Dichloro-2-But | Blank       | <2.4   | ug/l  |        |
|           | Bromodichloromethane | Blank       | <0.4   | ug/l  |        |

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike DuplicatesBATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 10 of 22

QC Batch Number: HG-0502

| Sample Id    | Analysis | QC Analysis         | Values  | Units | Limits |
|--------------|----------|---------------------|---------|-------|--------|
| -----        | -----    | -----               | -----   | ----- | -----  |
| BLANK-08054  | Mercury  | Blank               | <0.0002 | mg/l  |        |
| STDADD-05871 | Mercury  | Standard Measured   | 0.0020  | mg/l  |        |
|              |          | Standard Amt Added  | 0.0020  | mg/l  |        |
|              |          | Standard % Recovery | 99.0000 | %     |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 11 of 22

QC Batch Number: ICP-1831

| Sample Id    | Analysis  | QC Analysis         | Values   | Units | Limits |
|--------------|-----------|---------------------|----------|-------|--------|
| -----        | -----     | -----               | -----    | ----- | -----  |
| BLANK-08103  | Silver    | Blank               | <0.005   | mg/l  |        |
|              | Arsenic   | Blank               | <0.05    | mg/l  |        |
|              | Beryllium | Blank               | <0.0010  | mg/l  |        |
|              | Cadmium   | Blank               | <0.0005  | mg/l  |        |
|              | Chromium  | Blank               | <0.004   | mg/l  |        |
|              | Copper    | Blank               | <0.0010  | mg/l  |        |
|              | Nickel    | Blank               | <0.002   | mg/l  |        |
|              | Lead      | Blank               | <0.02    | mg/l  |        |
|              | Selenium  | Blank               | <0.05    | mg/l  |        |
|              | Thallium  | Blank               | <0.10    | mg/l  |        |
|              | Zinc      | Blank               | 0.015    | mg/l  |        |
| STDADD-05902 | Silver    | Standard Measured   | 0.991    | mg/l  |        |
|              |           | Standard Amt Added  | 1.000    | mg/l  |        |
|              |           | Standard % Recovery | 99.090   | %     |        |
|              | Arsenic   | Standard Measured   | 1.00     | mg/l  |        |
|              |           | Standard Amt Added  | 1.00     | mg/l  |        |
|              |           | Standard % Recovery | 100.20   | %     |        |
|              | Beryllium | Standard Measured   | 1.0810   | mg/l  |        |
|              |           | Standard Amt Added  | 1.0000   | mg/l  |        |
|              |           | Standard % Recovery | 108.1000 | %     |        |
|              | Cadmium   | Standard Measured   | 1.0410   | mg/l  |        |
|              |           | Standard Amt Added  | 1.0000   | mg/l  |        |
|              |           | Standard % Recovery | 104.1000 | %     |        |
|              | Chromium  | Standard Measured   | 1.024    | mg/l  |        |
|              |           | Standard Amt Added  | 1.000    | mg/l  |        |
|              |           | Standard % Recovery | 102.400  | %     |        |
|              | Copper    | Standard Measured   | 1.0220   | mg/l  |        |
|              |           | Standard Amt Added  | 1.0000   | mg/l  |        |
|              |           | Standard % Recovery | 102.2000 | %     |        |
|              | Nickel    | Standard Measured   | 1.043    | mg/l  |        |
|              |           | Standard Amt Added  | 1.000    | mg/l  |        |
|              |           | Standard % Recovery | 104.300  | %     |        |
|              | Lead      | Standard Measured   | 1.02     | mg/l  |        |
|              |           | Standard Amt Added  | 1.00     | mg/l  |        |
|              |           | Standard % Recovery | 101.90   | %     |        |
|              | Selenium  | Standard Measured   | 0.99     | mg/l  |        |
|              |           | Standard Amt Added  | 1.00     | mg/l  |        |
|              |           | Standard % Recovery | 99.20    | %     |        |
|              | Thallium  | Standard Measured   | 1.01     | mg/l  |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 12 of 22

QC Batch Number: ICP-1831

| Sample Id | Analysis | QC Analysis         | Values  | Units | Limits |
|-----------|----------|---------------------|---------|-------|--------|
| -----     | -----    | -----               | -----   | ----- | -----  |
|           |          | Standard Amt Added  | 1.00    | mg/l  |        |
|           |          | Standard % Recovery | 101.20  | %     |        |
|           | Zinc     | Standard Measured   | 1.041   | mg/l  |        |
|           |          | Standard Amt Added  | 1.000   | mg/l  |        |
|           |          | Standard % Recovery | 104.100 | %     |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

 BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 13 of 22

QC Batch Number: ICP-1832

| Sample Id    | Analysis  | QC Analysis         | Values   | Units | Limits |
|--------------|-----------|---------------------|----------|-------|--------|
| -----        | -----     | -----               | -----    | ----- | -----  |
| BLANK-08104  | Silver    | Blank               | <0.005   | mg/l  |        |
|              | Aluminum  | Blank               | <0.02    | mg/l  |        |
|              | Arsenic   | Blank               | <0.05    | mg/l  |        |
|              | Cadmium   | Blank               | <0.0005  | mg/l  |        |
|              | Chromium  | Blank               | <0.004   | mg/l  |        |
|              | Copper    | Blank               | <0.0010  | mg/l  |        |
|              | Iron      | Blank               | <0.02    | mg/l  |        |
|              | Manganese | Blank               | <0.0010  | mg/l  |        |
|              | Nickel    | Blank               | <0.002   | mg/l  |        |
|              | Lead      | Blank               | <0.02    | mg/l  |        |
|              | Selenium  | Blank               | <0.05    | mg/l  |        |
|              | Titanium  | Blank               | <0.02    | mg/l  |        |
|              | Zinc      | Blank               | <0.005   | mg/l  |        |
| STDA00-05929 | Silver    | Standard Measured   | 0.991    | mg/l  |        |
|              |           | Standard Amt Added  | 1.000    | mg/l  |        |
|              |           | Standard % Recovery | 99.090   | %     |        |
|              | Aluminum  | Standard Measured   | 1.03     | mg/l  |        |
|              |           | Standard Amt Added  | 1.00     | mg/l  |        |
|              |           | Standard % Recovery | 103.30   | %     |        |
|              | Arsenic   | Standard Measured   | 1.00     | mg/l  |        |
|              |           | Standard Amt Added  | 1.00     | mg/l  |        |
|              |           | Standard % Recovery | 100.20   | %     |        |
|              | Cadmium   | Standard Measured   | 1.0410   | mg/l  |        |
|              |           | Standard Amt Added  | 1.0000   | mg/l  |        |
|              |           | Standard % Recovery | 104.1000 | %     |        |
|              | Chromium  | Standard Measured   | 1.024    | mg/l  |        |
|              |           | Standard Amt Added  | 1.000    | mg/l  |        |
|              |           | Standard % Recovery | 102.400  | %     |        |
|              | Copper    | Standard Measured   | 1.0220   | mg/l  |        |
|              |           | Standard Amt Added  | 1.0000   | mg/l  |        |
|              |           | Standard % Recovery | 102.2000 | %     |        |
|              | Iron      | Standard Measured   | 1.03     | mg/l  |        |
|              |           | Standard Amt Added  | 1.00     | mg/l  |        |
|              |           | Standard % Recovery | 103.30   | %     |        |
|              | Manganese | Standard Measured   | 1.0340   | mg/l  |        |
|              |           | Standard Amt Added  | 1.0000   | mg/l  |        |
|              |           | Standard % Recovery | 103.4000 | %     |        |
|              | Nickel    | Standard Measured   | 1.043    | mg/l  |        |
|              |           | Standard Amt Added  | 1.000    | mg/l  |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 14 of 22

QC Batch Number: ICP-1832

| Sample Id | Analysis | QC Analysis         | Values  | Units | Limits |
|-----------|----------|---------------------|---------|-------|--------|
| -----     | -----    | -----               | -----   | ----- | -----  |
|           |          | Standard % Recovery | 104.300 | %     |        |
|           | Lead     | Standard Measured   | 1.02    | mg/l  |        |
|           |          | Standard Amt Added  | 1.00    | mg/l  |        |
|           |          | Standard % Recovery | 101.90  | %     |        |
|           | Selenium | Standard Measured   | 0.99    | mg/l  |        |
|           |          | Standard Amt Added  | 1.00    | mg/l  |        |
|           |          | Standard % Recovery | 99.20   | %     |        |
|           | Titanium | Standard Measured   | 1.04    | mg/l  |        |
|           |          | Standard Amt Added  | 1.00    | mg/l  |        |
|           |          | Standard % Recovery | 104.00  | %     |        |
|           | Zinc     | Standard Measured   | 1.041   | mg/l  |        |
|           |          | Standard Amt Added  | 1.000   | mg/l  |        |
|           |          | Standard % Recovery | 104.100 | %     |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 15 of 22

QC Batch Number: SOLIDS-0746

| Sample Id    | Analysis             | QC Analysis         | Values | Units | Limits |
|--------------|----------------------|---------------------|--------|-------|--------|
| -----        | -----                | -----               | -----  | ----- | -----  |
| STDA00-05850 | Total Dissolved Soli | Standard Measured   | 262.0  | mg/l  |        |
|              |                      | Standard Amt Added  | 293.0  | mg/l  |        |
|              |                      | Standard % Recovery | 89.4   | %     |        |



SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 16 of 22

QC Batch Number: TITRATION-0373

| Sample Id    | Analysis   | QC Analysis         | Values | Units | Limits   |
|--------------|------------|---------------------|--------|-------|----------|
| -----        | -----      | -----               | -----  | ----- | -----    |
| 97809758     | Alkalinity | Sample Amount       | 394.0  | mg/l  | 0.0-61.5 |
|              |            | Duplicate Value     | 384.0  | mg/l  |          |
|              |            | Duplicate RPD       | 2.6    | %     |          |
| STDADD-05817 | Alkalinity | Standard Measured   | 47.0   | mg/l  |          |
|              |            | Standard Amt Added  | 48.6   | mg/l  |          |
|              |            | Standard % Recovery | 96.6   | %     |          |

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike DuplicatesBATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 17 of 22

QC Batch Number: TITRATION-0374

| Sample Id    | Analysis | QC Analysis         | Values | Units | Limits |
|--------------|----------|---------------------|--------|-------|--------|
| -----        | -----    | -----               | -----  | ----- | -----  |
| STDA00-05846 | Ammonia  | Standard Measured   | 3.08   | mg/l  |        |
|              |          | Standard Amt Added  | 2.67   | mg/l  |        |
|              |          | Standard % Recovery | 115.36 | %     |        |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 18 of 22

QC Batch Number: TPH-0764

| Sample Id     | Analysis             | QC Analysis          | Values | Units | Limits       |
|---------------|----------------------|----------------------|--------|-------|--------------|
| -----         | -----                | -----                | -----  | ----- | -----        |
| LFBLANK-04006 | Total Petroleum Hydr | Lab Fort Blank Amt.  | 20.00  | mg/l  |              |
|               |                      | Lab Fort Blk. Found  | 17.15  | mg/l  |              |
|               |                      | Lab Fort Blk. % Rec. | 85.75  | %     |              |
|               |                      | Dup Lab Fort Bl Amt. | 20.00  | mg/l  |              |
|               |                      | Dup Lab Fort Bl. Fnd | 17.29  | mg/l  |              |
|               |                      | Dup Lab Fort Bl %Rec | 86.45  | %     |              |
|               |                      | Lab Fort Blank Range | 0.70   | units | 0.00-16.30   |
|               |                      | Lab Fort Bl. Av. Rec | 86.10  | %     | 73.50-107.00 |

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 19 of 22

QC Batch Number: WETCHEM-2336

| Sample Id    | Analysis     | QC Analysis         | Values | Units    | Limits |
|--------------|--------------|---------------------|--------|----------|--------|
| -----        | -----        | -----               | -----  | -----    | -----  |
| STDADD-05816 | Conductivity | Standard Measured   | 170.0  | umhos/cm |        |
|              |              | Standard Amt Added  | 147.0  | umhos/cm |        |
|              |              | Standard % Recovery | 115.6  | %        |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 20 of 22

QC Batch Number: WETCHEM-2348

| Sample Id    | Analysis | QC Analysis         | Values   | Units | Limits |
|--------------|----------|---------------------|----------|-------|--------|
| -----        | -----    | -----               | -----    | ----- | -----  |
| STDADD-05900 | Chloride | Standard Measured   | 8.3300   | mg/l  |        |
|              |          | Standard Amt Added  | 8.2000   | mg/l  |        |
|              |          | Standard % Recovery | 101.5854 | %     |        |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 21 of 22

QC Batch Number: WETCHEM-2349

| Sample Id    | Analysis        | QC Analysis          | Values | Units | Limits       |
|--------------|-----------------|----------------------|--------|-------|--------------|
| -----        | -----           | -----                | -----  | ----- | -----        |
| 97B09755     | Nitrate         | Sample Amount        | <0.05  | mg/l  |              |
|              |                 | Duplicate Value      | <0.05  | mg/l  |              |
|              |                 | Sample Amount        | <0.05  | mg/l  |              |
|              |                 | Matrix Spk Amt Added | 4.00   | mg/l  |              |
|              |                 | MS Amt Measured      | 4.23   | mg/l  |              |
|              |                 | Matrix Spike % Rec.  | 105.82 | %     | 85.40-114.00 |
| STDADD-05865 | Nitrate/Nitrite | Standard Measured    | 7.961  | mg/l  |              |
|              |                 | Standard Amt Added   | 8.100  | mg/l  |              |
|              |                 | Standard % Recovery  | 98.284 | %     |              |
|              | Nitrate         | Standard Measured    | 7.96   | mg/l  |              |
|              |                 | Standard Amt Added   | 8.10   | mg/l  |              |
|              |                 | Standard % Recovery  | 98.28  | %     |              |

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
Standard Reference Materials and Duplicates  
Method Blanks

Report Date: 06/13/97

Lims Bat #: LIMS-29802

Page 22 of 22

## NOTES:

QC Batch No.: GCMS/SEMI-0769  
Sample ID: 97809762  
Analysis: Phenol - D6  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CONTROL LIMITS DUE TO SAMPLE MATRIX  
INTERFERENCE.

QC Batch No.: GCMS/SEMI-0769  
Sample ID: 97809762  
Analysis: 2,4,6-Tribromophenol  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CONTROL LIMITS DUE TO SAMPLE MATRIX  
INTERFERENCE.

QC Batch No.: GCMS/SEMI-0769  
Sample ID: 97809762  
Analysis: 2-Fluorophenol  
QC Analysis: Surrogate Recovery  
SURROGATE RECOVERY OUTSIDE OF CONTROL LIMITS DUE TO SAMPLE MATRIX  
INTERFERENCE.

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

| Client Name: <u>Vanasse Hangen Brustlin, Inc.</u>                                 |                    | Telephone: <u>617-924-1770</u> |                                                   |           |      |             |              |           |      |     |       |                         |                      |                   |  |
|-----------------------------------------------------------------------------------|--------------------|--------------------------------|---------------------------------------------------|-----------|------|-------------|--------------|-----------|------|-----|-------|-------------------------|----------------------|-------------------|--|
| Attn: <u>Marc Richards</u>                                                        |                    | Batch #: _____                 |                                                   |           |      |             |              |           |      |     |       |                         |                      |                   |  |
| Address: <u>121 Crescent St.</u>                                                  |                    | Project #: <u>A0163</u>        |                                                   |           |      |             |              |           |      |     |       |                         |                      |                   |  |
| City/State: <u>Watertown, MA 02272</u>                                            |                    | Client P.O. #: <u>A0163</u>    |                                                   |           |      |             |              |           |      |     |       |                         |                      |                   |  |
| Sampled By: <u>Marc Richards</u>                                                  |                    | Fax #: <u>617-923-2336</u>     |                                                   |           |      |             |              |           |      |     |       |                         |                      |                   |  |
| Call Results: Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |                    |                                |                                                   |           |      |             |              |           |      |     |       |                         |                      |                   |  |
| Fax Results: Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>  |                    |                                |                                                   |           |      |             |              |           |      |     |       |                         |                      |                   |  |
| Field Sample I.D.                                                                 | Sample Description | Lab #                          | DATE SAMPLED<br>Start Date/Time<br>Stop Date/Time | Composite | Grab | MATRIX      |              |           |      |     |       | Preservative (Use Code) | Container (Use Code) | Analysis Required |  |
|                                                                                   |                    |                                |                                                   |           |      | WASTE WATER | GROUND WATER | DKG WATER | Soil | Air | Other |                         |                      |                   |  |
| MW-1                                                                              | Monitoring well #1 | 09735                          | 5/27                                              |           | X    | X           | X            |           |      |     |       |                         |                      |                   |  |
| MW-1                                                                              |                    | 09736                          | 5/27                                              |           | X    | X           | X            |           |      |     |       |                         |                      |                   |  |
| MW-1                                                                              |                    | 09737                          | 5/27                                              |           | X    | X           | X            |           |      |     |       |                         |                      |                   |  |
| MW-1                                                                              |                    | 09738                          | 5/27                                              |           | X    | X           | X            |           |      |     |       |                         |                      |                   |  |
| MW-2                                                                              | Monitoring well #2 | 09739                          | 5/27                                              |           | X    | X           | X            |           |      |     |       |                         |                      |                   |  |
| MW-2                                                                              |                    | 09740                          | 5/27                                              |           | X    | X           | X            |           |      |     |       |                         |                      |                   |  |
| MW-2                                                                              |                    | 09741                          | 5/27                                              |           | X    | X           | X            |           |      |     |       |                         |                      |                   |  |
| MW-2                                                                              |                    | 09742                          | 5/27                                              |           | X    | X           | X            |           |      |     |       |                         |                      |                   |  |

P: PLASTIC (\_\_\_ Size) V = 40 ml vial G = Glass (\_\_\_ size) A = 1000 ml Amber 0 = Other

Relinquished by: (Signature) [Signature] Date Time 5/28/97

Relinquished by: (Signature) [Signature] Date Time 5/28/97

Relinquished by: (Signature) [Signature] Date Time 5/28/97

CONTAINER CODE

Received by: (Signature) [Signature] Date Time 5/28/97

Received by: (Signature) [Signature] Date Time 5/28/97

Received by: (Signature) [Signature] Date Time 5/28/97

PREPRESERVATIVE CODE:

I = ICED N = HNO<sub>3</sub> H = HCl S = NaOH T = Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub> O = OTHER Silicic

Turnaround Requested: \_\_\_\_\_ 24-Hour \_\_\_\_\_ 48-Hour X Normal

Other \_\_\_\_\_ Date Required \_\_\_\_\_

Remarks/Comments: Metal Samples need to be filtered

\*MATRIX OTHER \_\_\_\_\_



## CHAIN OF CUSTODY RECORD

|                                                                                   |  |                                |  |
|-----------------------------------------------------------------------------------|--|--------------------------------|--|
| Client Name: <u>Vernesse Hagen Bros. Inc.</u>                                     |  | Telephone: <u>617-92A-1770</u> |  |
| Attn: <u>Mrs. Richards</u>                                                        |  | Batch #: _____                 |  |
| Address: <u>101 Walnut St.</u>                                                    |  | Project #: <u>40163</u>        |  |
| City/State: <u>Watertown, MA 02272</u>                                            |  | Client P.O. #: <u>40163</u>    |  |
| Sampled By: <u>Mrs. Richards</u>                                                  |  | Fax #: <u>617-923-2336</u>     |  |
| Call Results: Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> |  |                                |  |
| Fax Results: Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>  |  |                                |  |

| Field Sample I.D. | Sample Description | Lab #    | DATE SAMPLED    |                | Composite | Grab | MATRIX      |              |           |      |     | Preservative (Use Code) | Container (Use Code) | Analysis Required |          |           |         |                |                        |
|-------------------|--------------------|----------|-----------------|----------------|-----------|------|-------------|--------------|-----------|------|-----|-------------------------|----------------------|-------------------|----------|-----------|---------|----------------|------------------------|
|                   |                    |          | Start Date/Time | Stop Date/Time |           |      | WASTE WATER | GROUND WATER | DKG WATER | Soil | Air |                         |                      |                   | Other    |           |         |                |                        |
| MW-A              | Monitoring Well #4 | 09709743 | 5/27            |                |           | X    |             |              |           |      |     |                         |                      | TPH 418.1         | Voc 8240 | Svoc 8270 | FB 8080 | Habicide, 8156 | 13 Priority Pollutants |
| MW-A              |                    | 09744    | 5/27            |                |           | X    |             |              |           |      |     |                         |                      |                   |          |           |         |                | X                      |
| MW-A              |                    | 09745    | 5/27            |                |           | X    |             |              |           |      |     |                         |                      |                   |          |           |         |                |                        |
| MW-A              |                    | 09746    | 5/27            |                |           | X    |             |              |           |      |     |                         |                      |                   |          |           |         |                | X                      |
| MW-6              | Monitoring Well #6 | 09747    | 5/27            |                |           | X    |             |              |           |      |     |                         |                      |                   |          |           |         |                |                        |
| MW-6              |                    | 09748    | 5/27            |                |           | X    |             |              |           |      |     |                         |                      |                   |          |           |         |                | X                      |
| MW-6              |                    | 09749    | 5/27            |                |           | X    |             |              |           |      |     |                         |                      |                   |          |           |         |                |                        |
| MW-6              |                    | 09750    | 5/27            |                |           | X    |             |              |           |      |     |                         |                      |                   |          |           |         |                | X                      |

|                                                                                       |                                                                                                            |                                                          |  |
|---------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|--|
| CONTAINER CODE                                                                        |                                                                                                            | PRESERVATIVE CODE:                                       |  |
| P: PLASTIC (___ Size) V = 40 ml vial G = Glass (___ size) A = 1000 ml Amber O = Other | I = ICED N = HNO <sub>3</sub> H = HCl S = NaOH T = Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub> O = OTHER | Turnaround Requested: ___ 24-Hour ___ 48-Hour ___ Normal |  |
| Relinquished by: (Signature) <u>[Signature]</u>                                       | Date Time <u>5/28/99 1040</u>                                                                              | Received by: (Signature) <u>[Signature]</u>              |  |
| Relinquished by: (Signature) <u>[Signature]</u>                                       | Date Time <u>5/28/99 1545</u>                                                                              | Received by: (Signature) <u>[Signature]</u>              |  |
| Relinquished by: (Signature) <u>[Signature]</u>                                       | Date Time <u>5/28/99 1545</u>                                                                              | Received by: (Signature) <u>[Signature]</u>              |  |

Remarks/Comments: Metal samples need to be filtered

\*MATRIX OTHER: \_\_\_\_\_



(413) 525-2332  
FAX (413) 525-6405

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

Client Name: Venese Hanger Bresten, Inc.  
Attn: Steve Richards  
Address: 100 Walnut St.  
Watertown, MA 02272  
Site Location: Watertown, CT  
Sampled By: Steve Richards  
Call Results: Yes ☐ No ☒  
Fax Results: Yes ☒ No ☐

Telephone: 617-924-1770

Batch #:

Project #: 40163

Client P.O. #: 40163

Fax #: 617-923-2336

| Field Sample I.D. | Sample Description | Lab #    | DATE SAMPLED    |                | Composite | Grab | MATRIX      |              |           |      |     |       | Preservative (Use Code) | Container (Use Code) |
|-------------------|--------------------|----------|-----------------|----------------|-----------|------|-------------|--------------|-----------|------|-----|-------|-------------------------|----------------------|
|                   |                    |          | Start Date/Time | Stop Date/Time |           |      | WASTE WATER | GROUND WATER | DKG WATER | Soil | Air | Other |                         |                      |
| MW-3              | Monitoring Well #3 | 97B04757 | 5/27            | 5/27           |           | X    |             | X            |           |      |     |       |                         | X                    |
| MW-3              |                    | 97702    | 5/27            | 5/27           |           | X    |             | X            |           |      |     |       |                         | X                    |
| MW-3              |                    | 97753    | 5/27            | 5/27           |           | X    |             | X            |           |      |     |       |                         | X                    |
| MW-3              |                    | 97754    | 5/27            | 5/27           |           | X    |             | X            |           |      |     |       |                         | X                    |
| MW-3              |                    | 97755    | 5/27            | 5/27           |           | X    |             | X            |           |      |     |       |                         | X                    |
| MW-3              |                    | 97756    | 5/27            | 5/27           |           | X    |             | X            |           |      |     |       |                         | X                    |
| MW-3              |                    | 97757    | 5/27            | 5/27           |           | X    |             | X            |           |      |     |       |                         | X                    |
| MW-3              |                    | 97758    | 5/27            | 5/27           |           | X    |             | X            |           |      |     |       |                         | X                    |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |
|                   |                    |          |                 |                |           |      |             |              |           |      |     |       |                         |                      |

### CONTAINER CODE

P: PLASTIC (\_\_\_ Size) V = 40 ml vial G = Glass (\_\_\_ size) A = 1000 ml Amber O = Other \_\_\_

Relinquished by: (Signature)

Date Time

Received by: (Signature)

Date Time

### PRESERVATIVE CODE:

I = ICED N = HNO<sub>3</sub> H = HCl S = NaOH T = Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub> O = OTHER \_\_\_

Relinquished by: (Signature)

Date Time

Received by: (Signature)

Date Time

Turnaround Requested: \_\_\_

24-Hour

48-Hour

Normal

Relinquished by: (Signature)

Date Time

Received by: (Signature)

Date Time

Turnaround Requested: \_\_\_

24-Hour

48-Hour

Normal

Relinquished by: (Signature)

Date Time

Received by: (Signature)

Date Time

Turnaround Requested: \_\_\_

24-Hour

48-Hour

Normal

Remarks/Comments:

Actual samples need to be filtered, except for Iron & Manganese

Date Required

Analysis Required

TPH 418.1

VOC B240

SVEC B270

PCB B280

Herbicide B50

13 Priority Pesticide Metals

Good Solids, Chloride, Nitrate

Ammonia

Total Iron, Total Manganese

Total Dissolved Solids, TSS, pH

Specific Conductance, Alkalinity

\*MATRIX OTHER



(413) 525-2332  
FAX (413) 525-6405

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

Page 1 of 1

Client Name: Unesco Hergen Breston, Inc.  
Attn: Marc Richards  
Address: 100 Webster St.  
Westerton, MA 02273  
Site Location: Middleton, CT  
Sampled By: Marc Richards  
Call Results: Yes ☐ No ☒  
Fax Results: Yes ☒ No ☐  
Telephone: 617-924-1770  
Batch #: \_\_\_\_\_  
Project #: 40163  
Client P.O. #: 40163  
Fax #: 617-923-2336

| Field Sample I.D. | Sample Description | Lab #   | DATE SAMPLED    |                | Composite | Grab | MATRIX      |              |           |      |     |       | Preservative (Use Code) | Container (Use Code) |
|-------------------|--------------------|---------|-----------------|----------------|-----------|------|-------------|--------------|-----------|------|-----|-------|-------------------------|----------------------|
|                   |                    |         | Start Date/Time | Stop Date/Time |           |      | WASTE WATER | GROUND WATER | DKG WATER | Soil | Air | Other |                         |                      |
| MW-5              | Monitoring well #5 | 0976059 |                 | 5/27           |           | X    |             | X            |           |      |     |       | 0                       |                      |
| MW-5              |                    | 097600  |                 | 5/27           |           | X    |             | X            |           |      |     |       | N                       |                      |
| MW-5              |                    | 097601  |                 | 5/27           |           | X    |             | X            |           |      |     |       | H                       |                      |
| MW-5              |                    | 097602  |                 | 5/27           |           | X    |             | X            |           |      |     |       | -                       |                      |
| MW-5              |                    | 097603  |                 | 5/27           |           |      |             |              |           |      |     |       | -                       |                      |
| MW-5              |                    | 097604  |                 | 5/27           |           |      |             |              |           |      |     |       | 0                       |                      |
| MW-5              |                    | 097605  |                 | 5/27           |           |      |             |              |           |      |     |       | N                       |                      |
| MW-5              |                    | 097606  |                 | 5/27           |           |      |             |              |           |      |     |       | -                       |                      |

### CONTAINER CODE

P: PLASTIC (\_\_\_ Size) V = 40 ml vial G = Glass (\_\_\_ size) A = 1000 ml Amber 0 = Other \_\_\_

| Relinquished by: (Signature) | Date Time | Received by: (Signature) | Date Time |
|------------------------------|-----------|--------------------------|-----------|
| <u>[Signature]</u>           | 1240      | <u>[Signature]</u>       | 5/28/07   |
| Relinquished by: (Signature) | Date Time | Received by: (Signature) | Date Time |
| <u>[Signature]</u>           | 1547      | <u>[Signature]</u>       | 5/28/07   |
| Relinquished by: (Signature) | Date Time | Received by: (Signature) | Date Time |
| <u>[Signature]</u>           |           | <u>[Signature]</u>       |           |

### PRESERVATIVE CODE:

I = ICED N = HNO<sub>3</sub> H = HCl S = NaOH T = Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub> O = OTHER Substrate

Turnaround Requested: \_\_\_ 24-Hour \_\_\_ 48-Hour \_\_\_ Normal  
Other: \_\_\_

### Date Required

Remarks/Comments: Make samples need to be filtered, except for Iron & Manganese

\*MATRIX OTHER: \_\_\_\_\_

| Analysis Required               |  |  |  |  |  |
|---------------------------------|--|--|--|--|--|
| VOC 8240                        |  |  |  |  |  |
| SUCC 8270                       |  |  |  |  |  |
| Herbicides 850                  |  |  |  |  |  |
| 13 Priority Pollutants          |  |  |  |  |  |
| Boo Seely, Chloride, Nitrate    |  |  |  |  |  |
| Amonia                          |  |  |  |  |  |
| Total Iron, Total Manganese     |  |  |  |  |  |
| Total Dissolved Solids, TSS, PH |  |  |  |  |  |

Specific Conductance, Alkalinity



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL. 413/525-2332

VANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: DAVE CARLSON

REPORT DATE: 06/17/97

PURCHASE ORDER NUMBER: (40163)  
PROJECT NUMBER: PROJ.# 40163

ANALYTICAL SUMMARY

LIMS BAT #: LIMS-30083  
JOB NUMBER: 30083

The results of analyses performed on the following samples submitted to the CON-TEST Analytical Laboratory are found in this report

PROJECT LOCATION: REMINGTON RAND

| FIELD SAMPLE # | LAB ID   | MATRIX     | SAMPLE DESCRIPTION | TEST             |
|----------------|----------|------------|--------------------|------------------|
| MW-5 RESAMPLE  | 97B11271 | GRND WATER | 2X1 L AMBERS       | 625 - acid fract |

The CON-TEST Environmental Laboratory operates under the following certifications and accreditations:

|                             |                              |
|-----------------------------|------------------------------|
| AIHA 308                    | AIHA ELLAP (LEAD) 6838       |
| MASSACHUSETTS MA100         | MAINE (POTABLE/NON-POTABLE)  |
| CONNECTICUT PH-0567         | VERMONT DOH (LEAD) No. 15036 |
| NEW YORK ELAP 10899         | RHODE ISLAND (LIC. No. 112)  |
| OHIO (ENVIRO. LEAD) # 10005 |                              |
| NEW HAMPSHIRE 2516          |                              |

I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document.

Edward Denson 6/17/97  
SIGNATURE DATE

Tod Kopyscinski  
Director of Operations

Edward Denson  
Technical Director



39 Spruce Street • 2nd Floor • East Longmeadow, MA 01028 • FAX 413/525-6405 • TEL 413/525-2332

DAVE CARLSON  
ANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272

Purchase Order Number: (40163)  
Project Number: PROJ.# 40163

06/17/97  
page 1 of 1

Project Location: REMINGTON RAND  
Date Received: 06/11/97

LIMS-BAT #: LIMS-30083  
Job Number: 30083  
Sample Matrix: GRND WATER

Sampled: 06/11/97

2X1 L AMBERS

MW-5 RESAMPLE

|                                  | Units | 97B11271 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------------------------------|-------|----------|---------------|---------|------|------------|-----|
| 4-Chloro-3-methylphenol          | ug/l  | ND       | 06/16/97      | WSD     | 20.0 |            |     |
| 2-Chlorophenol                   | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| 2,4-Dichlorophenol               | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| 2,4-Dimethylphenol               | ug/l  | ND       | 06/16/97      | WSD     | 40.0 |            |     |
| 4,6-Dinitro-2-methylphenol       | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| 2,4-Dinitrophenol                | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| 2-Methylphenol (o-cresol)        | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| 3- & 4-Methylphenol (m&p-cresol) | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| 2-Nitrophenol                    | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| 4-Nitrophenol                    | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| Pentachlorophenol                | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| Phenol                           | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| 2,4,5-Trichlorophenol            | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |
| 2,4,6-Trichlorophenol            | ug/l  | ND       | 06/16/97      | WSD     | 10.0 |            |     |

Analytical Method(s):

EPA 625

SAMPLES ARE EXTRACTED INTO METHYLENE CHLORIDE, FOLLOWED BY KUDERNA-DANISH  
EVAPORATIVE CONCENTRATION AND QUANTITATED BY GC/MS TARGET COMPOUND ANALYSIS

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

## QC SUMMARY REPORT

SAMPLE QC: Sample Results with Duplicates  
 Sample Matrix Spikes and Matrix Spike Duplicates

BATCH QC: Lab Fortified Blanks and Duplicates  
 Standard Reference Materials and Duplicates  
 Method Blanks

Report Date: 06/17/97

Lims Bat #: LIMS-30083

Page 1 of 1

QC Batch Number: GCMS/SEMI-0788

| Sample Id   | Analysis             | QC Analysis        | Values | Units | Limits     |
|-------------|----------------------|--------------------|--------|-------|------------|
| -----       | -----                | -----              | -----  | ----- | -----      |
| 97B11271    | Phenol - D6 wet reco | Surrogate Recovery | 21.3   | %     | 10.0-94.0  |
|             | 2,4,6-Tribromophenol | Surrogate Recovery | 51.2   | %     | 10.0-123.0 |
|             | 2-Fluorophenol wet r | Surrogate Recovery | 38.4   | %     | 21.0-100.0 |
| BLANK-08277 | 4-Chloro-3-methylphe | Blank              | <20.00 | ug/l  |            |
|             | 2-Chlorophenol       | Blank              | <10.00 | ug/l  |            |
|             | 2,4-Dichlorophenol   | Blank              | <10.00 | ug/l  |            |
|             | 2,4-Dimethylphenol   | Blank              | <40.00 | ug/l  |            |
|             | 4,6-Dinitro-2-methyl | Blank              | <10.00 | ug/l  |            |
|             | 2,4-Dinitrophenol    | Blank              | <10.00 | ug/l  |            |
|             | 2-Methylphenol (o-cr | Blank              | <10.00 | ug/l  |            |
|             | 3- & 4-Methylphenol  | Blank              | <10.00 | ug/l  |            |
|             | 2-Nitrophenol        | Blank              | <10.00 | ug/l  |            |
|             | 4-Nitrophenol        | Blank              | <10.00 | ug/l  |            |
|             | Phenol               | Blank              | <10.00 | ug/l  |            |
|             | 2,4,5-Trichloropheno | Blank              | <10.00 | ug/l  |            |
|             | 2,4,6-Trichloropheno | Blank              | <10.00 | ug/l  |            |
|             | Pentachlorophenol    | Blank              | <10.00 | ug/l  |            |

## CHAIN OF CUSTODY RECORD

39 SPRUCE ST. • 2ND FLOOR • EAST LONGMEADOW, MA 01028

[illegible]

VANASSE HANGEN BRUSTLIN, INC.  
101 WALNUT STREET  
WATERTOWN, MA 02272  
ATTN: MARC RICHARDS

REPORT DATE: 06/17/97

PURCHASE ORDER NUMBER: 40163  
PROJECT NUMBER: PROJ.# 40163

ANALYTICAL SUMMARY

LIHS BAT #: LIHS-30046  
JOB NUMBER: 30046

The results of analyses performed on the following samples submitted to the CON-TEST Analytical Laboratory are found in this report

PROJECT LOCATION: MIDDLETOWN, CT

| FIELD SAMPLE # | LAB ID   | MATRIX | SAMPLE DESCRIPTION | TEST             |
|----------------|----------|--------|--------------------|------------------|
| B-10/6-7'      | 97B10968 | SOIL   | SOIL BORING        | splp - metals 13 |
| B-18/5-7'      | 97B10969 | SOIL   | SOIL BORING        | splp - metals 13 |
| B-4/8-10'      | 97B10965 | SOIL   | SOIL BORING        | splp - metals 13 |
| B-8/8-10'      | 97B10966 | SOIL   | SOIL BORING        | splp - metals 13 |
| B-9/9-11'      | 97B10967 | SOIL   | SOIL BORING        | splp - metals 13 |
| ROW/TP1/0-2'   | 97B10972 | SOIL   | R.O.W.             | splp - metals 13 |
| ROW/TP10/4-6'  | 97B10975 | SOIL   | R.O.W.             | splp - metals 13 |
| ROW/TP6/3-4'   | 97B10973 | SOIL   | R.O.W.             | splp - metals 13 |
| ROW/TP7/2-3'   | 97B10974 | SOIL   | R.O.W.             | splp - metals 13 |
| SUR-1          | 97B10970 | SOIL   | HARD AUGER         | splp - metals 13 |
| SUR-2          | 97B10971 | SOIL   | HARD AUGER         | splp - metals 13 |
| UST3/TP1/0-2'  | 97B10976 | SOIL   | BURN PIT           | splp - metals 13 |

The CON-TEST Environmental Laboratory operates under the following certifications and accreditations:

|                             |                              |
|-----------------------------|------------------------------|
| AIHA 308                    | AIHA ELLAP (LEAD) 6838       |
| MASSACHUSETTS MA100         | MAINE (POTABLE/NON-POTABLE)  |
| CONNECTICUT PH-0567         | VERMONT DOH (LEAD) No. 15036 |
| NEW YORK ELAP 10899         | RHODE ISLAND (LIC. No. 112)  |
| OHIO (ENVIRO. LEAD) # 10005 |                              |
| NEW HAMPSHIRE 2516          |                              |

I certify that the analyses listed above, unless specifically listed as subcontracted, if any, were performed under my direction according to the approved methodologies listed in this document.

*Edward Denson* 6/18/97

SIGNATURE

DATE

Tod Kopyscinski  
Director of Operations

Edward Denson  
Technical Director



MARC RICHARDS  
VANASSE HANGEN BRUSTLIN, INC.  
1 WALNUT STREET  
MIDDLETOWN, MA 02272

06/17/97  
page 1 of 8

Purchase Order Number: 40163  
Project Number: PROJ.# 40163

Project Location: MIDDLETOWN, CT  
Date Received: 06/11/97

LIMS-BAT #: LIMS-30046  
Job Number: 30046  
Sample Matrix: SOIL

Sampled: 06/11/97  
SOIL BORING  
B-10/6-7'

|           | Units         | 97B10968 | Date Analyzed | Analyst | MDL     | SPEC LIMIT | P/F |
|-----------|---------------|----------|---------------|---------|---------|------------|-----|
| Antimony  | MG/L LEACHATE | ND       | 06/16/97      | KLF     | 0.05    |            |     |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10    | 5.00       | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 1.00       | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Copper    | MG/L LEACHATE | 0.30     | 06/13/97      | KLF     | 0.05    |            |     |
| Lead      | MG/L LEACHATE | 1.37     | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97      | APP     | 0.00020 | 0.20       | P   |
| Nickel    | MG/L LEACHATE | 0.16     | 06/13/97      | KLF     | 0.05    |            |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10    | 1.00       | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Thallium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.20    |            |     |
| Zinc      | MG/L LEACHATE | 6.55     | 06/13/97      | KLF     | 0.05    |            |     |

Sampled: 06/11/97  
SOIL BORING  
B-18/5-7'

|           | Units         | 97B10969 | Date Analyzed | Analyst | MDL     | SPEC LIMIT | P/F |
|-----------|---------------|----------|---------------|---------|---------|------------|-----|
| Antimony  | MG/L LEACHATE | ND       | 06/16/97      | KLF     | 0.05    |            |     |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10    | 5.00       | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 1.00       | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Copper    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Lead      | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97      | APP     | 0.00020 | 0.20       | P   |
| Nickel    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10    | 1.00       | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/17/97  
page 2 of 8Purchase Order Number: 40163  
Project Number: PROJ.# 40163LIMS-BAT #: LIMS-30046  
Job Number: 30046  
Sample Matrix: SOILSampled: 06/11/97  
SOIL BORING  
B-18/5-7'

|          | Units         | 97B10969 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------|---------------|----------|------------------|---------|------|---------------|-----|
| Thallium | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.20 |               |     |
| Zinc     | MG/L LEACHATE | 0.15     | 06/13/97         | KLF     | 0.05 |               |     |

Sampled: 06/11/97  
SOIL BORING  
B-4/8-10'

|           | Units         | 97B10965 | Date<br>Analyzed | Analyst | MDL     | SPEC<br>LIMIT | P/F |
|-----------|---------------|----------|------------------|---------|---------|---------------|-----|
| Antimony  | MG/L LEACHATE | ND       | 06/16/97         | KLF     | 0.05    |               |     |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 5.00          | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 1.00          | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Copper    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Lead      | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97         | APP     | 0.00020 | 0.20          | P   |
| Nickel    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 1.00          | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Thallium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.20    |               |     |
| Zinc      | MG/L LEACHATE | 0.35     | 06/13/97         | KLF     | 0.05    |               |     |

Sampled: 06/11/97  
SOIL BORING  
B-8/8-10'

|          | Units         | 97B10966 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------|---------------|----------|------------------|---------|------|---------------|-----|
| Antimony | MG/L LEACHATE | ND       | 06/16/97         | KLF     | 0.05 |               |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/17/97  
page 3 of 8Purchase Order Number: 40163  
Project Number: PROJ.# 40163LIMS-BAT #: LIMS-30046  
Job Number: 30046  
Sample Matrix: SOILSampled: 06/11/97  
SOIL BORING  
B-8/8-10'

|           | Units         | 97B10966 | Date<br>Analyzed | Analyst | MDL     | SPEC<br>LIMIT | P/F |
|-----------|---------------|----------|------------------|---------|---------|---------------|-----|
| Antimony  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 5.00          | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 1.00          | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Copper    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Lead      | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97         | APP     | 0.00020 | 0.20          | P   |
| Nickel    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 1.00          | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Thallium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.20    |               |     |
| Inc       | MG/L LEACHATE | 0.76     | 06/13/97         | KLF     | 0.05    |               |     |

Sampled: 06/11/97  
SOIL BORING  
B-9/9-11'

|           | Units         | 97B10967 | Date<br>Analyzed | Analyst | MDL     | SPEC<br>LIMIT | P/F |
|-----------|---------------|----------|------------------|---------|---------|---------------|-----|
| Antimony  | MG/L LEACHATE | ND       | 06/16/97         | KLF     | 0.05    |               |     |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 5.00          | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 1.00          | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Copper    | MG/L LEACHATE | 0.26     | 06/13/97         | KLF     | 0.05    |               |     |
| Lead      | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97         | APP     | 0.00020 | 0.20          | P   |
| Nickel    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 1.00          | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Thallium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.20    |               |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/17/97  
page 4 of 8

Purchase Order Number: 40163  
Project Number: PROJ.# 40163

LIMS-BAT #: LIMS-30046  
Job Number: 30046  
Sample Matrix: SOIL

Sampled: 06/11/97  
SOIL BORING  
B-9/9-11'

|      | Units         | 97B10967 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|------|---------------|----------|---------------|---------|------|------------|-----|
| Zinc | MG/L LEACHATE | 0.26     | 06/13/97      | KLF     | 0.05 |            |     |

Sampled: 06/11/97  
R.O.W.  
ROW/TP1/0-2'

|           | Units         | 97B10972 | Date Analyzed | Analyst | MDL     | SPEC LIMIT | P/F |
|-----------|---------------|----------|---------------|---------|---------|------------|-----|
| Antimony  | MG/L LEACHATE | ND       | 06/16/97      | KLF     | 0.05    |            |     |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10    | 5.00       | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 1.00       | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Copper    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Lead      | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97      | APP     | 0.00020 | 0.20       | P   |
| Nickel    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10    | 1.00       | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Thallium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.20    |            |     |
| Zinc      | MG/L LEACHATE | 0.19     | 06/13/97      | KLF     | 0.05    |            |     |

Sampled: 06/11/97  
R.O.W.  
ROW/TP10/4-6'

|          | Units         | 97B10975 | Date Analyzed | Analyst | MDL  | SPEC LIMIT | P/F |
|----------|---------------|----------|---------------|---------|------|------------|-----|
| Antimony | MG/L LEACHATE | ND       | 06/16/97      | KLF     | 0.05 |            |     |
| Arsenic  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10 | 5.00       | P   |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/17/97  
page 5 of 8

Purchase Order Number: 40163  
Project Number: PROJ.# 40163

LIMS-BAT #: LIMS-30046  
Job Number: 30046  
Sample Matrix: SOIL

Sampled: 06/11/97  
R.O.W.  
ROW/TP10/4-6'

|          | Units         | 97B10975 | Date Analyzed | Analyst | MDL     | SPEC LIMIT | P/F |
|----------|---------------|----------|---------------|---------|---------|------------|-----|
| Yttrium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Cadmium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 1.00       | P   |
| Chromium | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Copper   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Lead     | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Mercury  | MG/L LEACHATE | ND       | 06/14/97      | APP     | 0.00020 | 0.20       | P   |
| Nickel   | MG/L LEACHATE | 0.08     | 06/13/97      | KLF     | 0.05    |            |     |
| Selenium | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10    | 1.00       | P   |
| Silver   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Thallium | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.20    |            |     |
| Zinc     | MG/L LEACHATE | 0.30     | 06/13/97      | KLF     | 0.05    |            |     |

Sampled: 06/11/97  
R.O.W.  
ROW/TP6/3-4'

|           | Units         | 97B10973 | Date Analyzed | Analyst | MDL     | SPEC LIMIT | P/F |
|-----------|---------------|----------|---------------|---------|---------|------------|-----|
| Antimony  | MG/L LEACHATE | ND       | 06/16/97      | KLF     | 0.05    |            |     |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10    | 5.00       | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 1.00       | P   |
| Chromium  | MG/L LEACHATE | 0.09     | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Copper    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Lead      | MG/L LEACHATE | 0.31     | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97      | APP     | 0.00020 | 0.20       | P   |
| Nickel    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    |            |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.10    | 1.00       | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.05    | 5.00       | P   |
| Thallium  | MG/L LEACHATE | ND       | 06/13/97      | KLF     | 0.20    |            |     |
| Zinc      | MG/L LEACHATE | 0.30     | 06/13/97      | KLF     | 0.05    |            |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or regulatory level for comparison with data to determine PASS (P) or FAIL (F) condition of results.

06/17/97  
page 6 of 8

Purchase Order Number: 40163  
Project Number: PROJ.# 40163

LIHS-BAT #: LIHS-30046  
Job Number: 30046  
Sample Matrix: SOIL

Sampled: 06/11/97  
R.O.W.  
ROW/TP7/2-3'

|           | Units         | 97B10974 | Date<br>Analyzed | Analyst | MDL     | SPEC<br>LIMIT | P/F |
|-----------|---------------|----------|------------------|---------|---------|---------------|-----|
| -----     | -----         | -----    | -----            | -----   | ---     | -----         | --- |
| Antimony  | MG/L LEACHATE | ND       | 06/16/97         | KLF     | 0.05    |               |     |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 5.00          | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 1.00          | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Copper    | MG/L LEACHATE | 0.09     | 06/13/97         | KLF     | 0.05    |               |     |
| Lead      | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97         | APP     | 0.00020 | 0.20          | P   |
| Nickel    | MG/L LEACHATE | 0.28     | 06/13/97         | KLF     | 0.05    |               |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 1.00          | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Thallium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.20    |               |     |
| Zinc      | MG/L LEACHATE | 5.45     | 06/13/97         | KLF     | 0.05    |               |     |

Sampled: 06/11/97  
HARD AUGER  
SUR-1

|           | Units         | 97B10970 | Date<br>Analyzed | Analyst | MDL     | SPEC<br>LIMIT | P/F |
|-----------|---------------|----------|------------------|---------|---------|---------------|-----|
| -----     | -----         | -----    | -----            | -----   | ---     | -----         | --- |
| Antimony  | MG/L LEACHATE | ND       | 06/16/97         | KLF     | 0.05    |               |     |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 5.00          | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 1.00          | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Copper    | MG/L LEACHATE | 1.07     | 06/13/97         | KLF     | 0.05    |               |     |
| Lead      | MG/L LEACHATE | BDL      | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97         | APP     | 0.00020 | 0.20          | P   |
| Nickel    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 1.00          | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not Measured

SPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/17/97  
page 7 of 8Purchase Order Number: 40163  
Project Number: PROJ.# 40163LIMS-BAT #: LIMS-30046  
Job Number: 30046  
Sample Matrix: SOILSampled: 06/11/97  
HARD AUGER  
SUR-1

|        | Units         | 97B10970 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|--------|---------------|----------|------------------|---------|------|---------------|-----|
| -----  | -----         | -----    | -----            | -----   | ---  | -----         | --- |
| Sodium | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.20 |               |     |
| inc    | MG/L LEACHATE | 3.12     | 06/13/97         | KLF     | 0.05 |               |     |

Sampled: 06/11/97  
HARD AUGER  
SUR-2

|           | Units         | 97B10971 | Date<br>Analyzed | Analyst | MDL     | SPEC<br>LIMIT | P/F |
|-----------|---------------|----------|------------------|---------|---------|---------------|-----|
| -----     | -----         | -----    | -----            | -----   | ---     | -----         | --- |
| Antimony  | MG/L LEACHATE | ND       | 06/16/97         | KLF     | 0.05    |               |     |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 5.00          | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 1.00          | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Copper    | MG/L LEACHATE | 0.73     | 06/13/97         | KLF     | 0.05    |               |     |
| Lead      | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97         | APP     | 0.00020 | 0.20          | P   |
| Nickel    | MG/L LEACHATE | 0.33     | 06/13/97         | KLF     | 0.05    |               |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 1.00          | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Thallium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.20    |               |     |
| Zinc      | MG/L LEACHATE | 1.10     | 06/13/97         | KLF     | 0.05    |               |     |

Sampled: 06/11/97  
BURN PIT  
UST3/TP1/0-2'

|          | Units         | 97B10976 | Date<br>Analyzed | Analyst | MDL  | SPEC<br>LIMIT | P/F |
|----------|---------------|----------|------------------|---------|------|---------------|-----|
| -----    | -----         | -----    | -----            | -----   | ---  | -----         | --- |
| Antimony | MG/L LEACHATE | ND       | 06/16/97         | KLF     | 0.05 |               |     |

MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.

06/17/97  
page 8 of 8Purchase Order Number: 40163  
Project Number: PROJ.# 40163LIMS-BAY #: LIMS-30046  
Job Number: 30046  
Sample Matrix: SOILSampled: 06/11/97  
BURN PIT  
UST3/TP1/0-2'

|           | Units         | 97B10976 | Date<br>Analyzed | Analyst | MDL     | SPEC<br>LIMIT | P/F |
|-----------|---------------|----------|------------------|---------|---------|---------------|-----|
| -----     | -----         | -----    | -----            | -----   | ---     | -----         | --- |
| Arsenic   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 5.00          | P   |
| Beryllium | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    |               |     |
| Cadmium   | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 1.00          | P   |
| Chromium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Copper    | MG/L LEACHATE | 0.16     | 06/13/97         | KLF     | 0.05    |               |     |
| Lead      | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Mercury   | MG/L LEACHATE | ND       | 06/14/97         | APP     | 0.00020 | 0.20          | P   |
| Nickel    | MG/L LEACHATE | 1.87     | 06/13/97         | KLF     | 0.05    |               |     |
| Selenium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.10    | 1.00          | P   |
| Silver    | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.05    | 5.00          | P   |
| Thallium  | MG/L LEACHATE | ND       | 06/13/97         | KLF     | 0.20    |               |     |
| Zinc      | MG/L LEACHATE | 1.47     | 06/13/97         | KLF     | 0.05    |               |     |

## Analytical Method(s):

SW846 1312/6010 1312/7470

SW846 1312 SYNTHETIC PRECIPITATION LEACHING PROCEDURE (SPLP). SAMPLES  
ARE LEACHED FOR 16-20 HOURS IN THE APPROPRIATE LEACHING  
SOLUTION ACCORDING TO SPLP.SW846 6010 ALL METALS OTHER THAN MERCURY ARE ANALYZED BY INDUCTIVELY  
COUPLED PLASMA EMISSION SPECTROMETRY.SW846 7470 MERCURY LEACHATE IS ANALYZED BY COLD VAPOR (FLAMELESS) ATOMIC  
ABSORPTION SPECTROPHOTOMETRY.MDL = Method Detection Limit  
ND = Not Detected  
BDL = Below Detection Limit  
NM = Not MeasuredSPEC LIMIT = a client specified, recommended, or  
regulatory level for comparison with data to  
determine PASS (P) or FAIL (F) condition of results.





## LABORATORY REPORT

Eastern Analytical, Inc. ID#: 9123 VHBMA

Client: Vanasse, Hangen &amp; Brustlin

Client Designation: Middletown, CT 40163

Sample ID: TP-3/0-2'  
Matrix: solid  
Date Rec'd: 06/20/97  
Units (unless noted): mg/kg

Date of  
Analysis Analyst Method

|               |     |          |    |       |
|---------------|-----|----------|----|-------|
| Total Cyanide | 1.2 | 06/24/97 | LO | 335.2 |
|---------------|-----|----------|----|-------|

Approved by: Lorraine Olashaw, Inorganic Supervisor

Lorraine Olashaw





---

# Appendix E

## Asbestos Summary Tables and Laboratory Analytical Results



Table 1  
ACM Inventory  
180 Johnson Street

| Homogeneous Area # | Functional Space                                            | Type of Material                                | Asbestos |      |          | Comments                              |
|--------------------|-------------------------------------------------------------|-------------------------------------------------|----------|------|----------|---------------------------------------|
|                    |                                                             |                                                 | F/NF     | Y/N? | Quantity |                                       |
| 01                 | Rest room area, hall between buildings #11 & #1A, 1st Floor | Tan brick-style 12"x12" floor tile              | NF       | N    | 200 SF   |                                       |
| 02                 | Foyer, #1A, 1st Floor                                       | Tan speckled 12"x12" floor tile                 | NF       | N    | 210 SF   |                                       |
| 03                 | Foyer & adjoining rest room area, #1A, 1st Floor            | Tan spray-applied insulation/fireproofing       | F        | N    | 400 SF   | Above ceiling tile                    |
| 04                 | Warehouse/office area #1A, 1st Floor                        | Sheet rock/joint compound composite system      | NF       | N    | 750 SF   |                                       |
| 05                 | Office, #1B, 1st Floor                                      | Tan 12"x12" floor tile                          | NF       | N    | 320 SF   | Beneath carpet                        |
| 06                 | Storage rooms, #1C, 1st & 2nd Floors                        | White interior door insulation                  | F        | Y    | 505 SF   | Interior door insulation/fireproofing |
| 07                 | East corner, #1C, 2nd Floor                                 | Red plaster                                     | NF       | Y    | 125 SF   | Embedded in wire lath                 |
| 08                 | By entrance to #8, northeast wall, Building #1B, 2nd Floor  | Black mastic beneath red/white floor tile       | NF       | Y    | 1,100 SF | Attached to wood floor                |
| 09                 | By entrance to #8, northeast wall, Building #1B, 2nd Floor  | Red & white 9"x9" checkered floor tile          | NF       | N    | 1,100 SF |                                       |
| 10                 | North corner, #8, 2nd Floor                                 | Black mastic beneath green checkered floor tile | NF       | Y    | 250 SF   | Attached to wood floor                |
| 11                 | North corner, #8, 2nd Floor                                 | Green checkered 9"x9" floor tile                | NF       | Y    | 250 SF   |                                       |
| 12                 | Northeast corner, #3, 2nd Floor                             | Red with white streaks 9"x9" floor tile         | NF       | Y    | 350 SF   | Attached to wood                      |

Table 1  
ACM Inventory  
180 Johnson Street

| Homogeneous Area # | Functional Space                 | Type of Material               | Asbestos |      |          | Comments                        |
|--------------------|----------------------------------|--------------------------------|----------|------|----------|---------------------------------|
|                    |                                  |                                | F/NF     | Y/N? | Quantity |                                 |
| 13                 | Northeast corner, #3, 2nd Floor  | Black paper beneath floor tile | NF       | Y    | 350 SF   |                                 |
| 14                 | Southeast corner, #1A, 2nd Floor | White plaster                  | NF       | N    | 2,000 SF | Water damaged                   |
| 15                 | Hall, #1A, 2nd Floor             | Brown 9"x9" floor tile         | NF       | Y    | 500 SF   | Beneath carpet attached to wood |
| 16                 | Building #10                     | Paper-type pipe insulation     | F        | Y    | 70 LF    |                                 |
|                    | Building #11A                    |                                |          |      | 45 LF    |                                 |
|                    | Building #1A, 1st Floor          |                                |          |      | 400 LF   |                                 |
|                    | Building #1A, 2nd Floor          |                                |          |      | 250 LF   |                                 |
|                    | Building #1B, 1st Floor          |                                |          |      | 600 LF   |                                 |
|                    | Building #1B, 2nd Floor          |                                |          |      | 2 LF     |                                 |
|                    | Building #1C, 1st Floor          |                                |          |      | 200 LF   |                                 |
|                    | Building #1C, 2nd Floor          |                                |          |      | 15 LF    |                                 |
|                    | Building #8, 1st Floor           |                                |          |      | 50 LF    |                                 |
|                    | Building #8, 2nd Floor           |                                |          |      | 2 LF     |                                 |
|                    | Building #8 & #1B, 1st Floor     |                                |          |      | 30 LF    |                                 |
|                    | Building #10                     |                                |          |      | 250 LF   |                                 |
|                    | Building #9, 1st Floor           |                                |          |      | 4 LF     |                                 |

Table 1  
ACM Inventory  
180 Johnson Street

| Homogeneous Area # |  | Functional Space                | Type of Material                   | F/NF | Asbestos Y/N? | Quantity       | Comments                |
|--------------------|--|---------------------------------|------------------------------------|------|---------------|----------------|-------------------------|
| 16 (Cont.)         |  | Building #9, 1st Floor          | Paper-type pipe insulation (cont.) | F    | Y             | 10 LF          |                         |
|                    |  | Building #2, 1st Floor          |                                    |      |               | 40 LF          |                         |
|                    |  | Building #3                     |                                    |      |               | 30 LF          |                         |
|                    |  | Building #5                     |                                    |      |               | 175 LF         |                         |
|                    |  | Building #7 (Boiler House)      |                                    |      |               | 200 LF         |                         |
|                    |  | Building #6, Room #1, 1st Floor |                                    |      |               | 2 LF           |                         |
| 17                 |  | Building #1A, 1st Floor         | Block-type pipe insulation         | F    | Y             | 30 LF          |                         |
|                    |  | Building #1C, 1st Floor         |                                    |      |               | 20 LF          |                         |
|                    |  | Building #1C, 2nd Floor         |                                    |      |               | 20 LF          |                         |
|                    |  | Building #8, 1st Floor          |                                    |      |               | 165 LF         |                         |
|                    |  | Building #9, 1st Floor          |                                    |      |               | 275 LF         |                         |
|                    |  | Building #7                     |                                    |      |               | 100 LF         |                         |
|                    |  | Building #6, 2nd Floor          |                                    |      |               | 75 LF<br>30 LF | 24" outside diameter    |
| 18                 |  | Building #1B, 2nd Floor         | Cementitious switches/panels       | NF   | Y             | 65 F           | In electric transformer |
|                    |  | Building #1C, 2nd Floor         |                                    |      |               | 65 F           |                         |
|                    |  | Building #8, 2nd Floor          |                                    |      |               | 65 F           |                         |

Table 1  
ACM Inventory  
180 Johnson Street

| Homogeneous |                                               | Asbestos                         |      |      |                                                     |
|-------------|-----------------------------------------------|----------------------------------|------|------|-----------------------------------------------------|
| Area #      | Functional Space                              | Type of Material                 | F/NF | Y/N? | Quantity                                            |
| 18 (cont.)  | Building #6, rear storage, 1st Floor          |                                  |      |      | 65 F                                                |
| 19          | Buildings #1A, 1B, 1C, 2, 3, 4, 5, 8, 10 & 11 | Black flashing cement            | NF   | Y    | 30,000 SF                                           |
| 20          | Buildings #1A, 1B, 1C, 2, 3, 4, 5, 8, 10, 11  | Black asphaltic roofing material | NF   | N    | 180,00 SF                                           |
| 21          | Building #1B                                  | Black asphaltic shingle          | NF   | N    | 250 SF                                              |
|             |                                               |                                  |      |      | Throughout all penetrations, perimeters & junctions |





Date: 6/13/97 Lab QC Approval By: MM

Fax #: 617-923-2336

[illegible]

[illegible]



300 West Cummings Park, Suite 1900  
Noburn, MA 01801  
Phone (617) 933-5074 Fax (617) 938-1

### INTERVAL / ATC INFORMATION

Branch & Office #:  
 Recv'd By: \_\_\_\_\_ On: \_\_\_\_\_  
 Qty Recv'd: \_\_\_\_\_ Rate:\$ \_\_\_\_\_  
 Requested Completion Date: \_\_\_\_\_  
 Project #: \_\_\_\_\_  
 Supplemental #: \_\_\_\_\_  
 Project Manager: \_\_\_\_\_  
 Comments/Special Instructions: \_\_\_\_\_

**Please Circle Desired Turn Around Time**

|                       | Same Day | 24 Hour | 48 Hour |
|-----------------------|----------|---------|---------|
| 1. <b>Prevalence</b>  | 10%      | 10%     | 10%     |
| 2. <b>Incidence</b>   | 10%      | 10%     | 10%     |
| 3. <b>Prevalence</b>  | 10%      | 10%     | 10%     |
| 4. <b>Incidence</b>   | 10%      | 10%     | 10%     |
| 5. <b>Prevalence</b>  | 10%      | 10%     | 10%     |
| 6. <b>Incidence</b>   | 10%      | 10%     | 10%     |
| 7. <b>Prevalence</b>  | 10%      | 10%     | 10%     |
| 8. <b>Incidence</b>   | 10%      | 10%     | 10%     |
| 9. <b>Prevalence</b>  | 10%      | 10%     | 10%     |
| 10. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 11. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 12. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 13. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 14. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 15. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 16. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 17. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 18. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 19. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 20. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 21. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 22. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 23. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 24. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 25. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 26. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 27. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 28. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 29. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 30. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 31. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 32. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 33. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 34. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 35. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 36. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 37. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 38. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 39. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 40. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 41. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 42. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 43. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 44. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 45. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 46. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 47. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 48. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 49. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 50. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 51. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 52. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 53. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 54. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 55. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 56. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 57. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 58. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 59. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 60. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 61. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 62. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 63. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 64. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 65. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 66. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 67. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 68. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 69. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 70. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 71. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 72. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 73. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 74. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 75. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 76. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 77. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 78. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 79. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 80. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 81. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 82. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 83. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 84. <b>Incidence</b>  | 10%      | 10%     | 10%     |
| 85. <b>Prevalence</b> | 10%      | 10%     | 10%     |
| 86. <b>Incidence</b>  |          |         |         |

### 3-4 Days

**Standard 5-7 Days**

**Analyzed By:**

ML

Date: 6/13/97 Lab QC Approval By: \_\_\_\_\_

Wm

**GENERAL CLIENT INFORMATION**

Client/Project: VHB  
Address: 101 Walnut St. P.O. Box 9151  
Waterbury, MA 02272  
Sampled By: Tim Downey  
Results to: SANÉ  
Phone #: 617-924-1770 x1243  
Fax #: 617-923-2336

[illegible]

## INTERNAL / ATC INFORMATION

Branch &amp; Office #:

Rec'd By: \_\_\_\_\_ On: \_\_\_\_\_

Qty Rec'd: \_\_\_\_\_ Rate: \$ \_\_\_\_\_

Requested Completion Date: \_\_\_\_\_

Project #:

Supplemental #:

Project Manager:

Comments/Special Instructions:

Date: 6/13/97 Lab QC Approval By: MM

## GENERAL CLIENT INFORMATION

Client/Project: VABAddress: 101 Walnut St. P.O. Box 951Watertown, MA 02272Sampled By: Tim DowneyResults to: SAMEPhone #: 617-924-1770 X1243Fax #: 617-923-2336

Please Circle Desired Turn Around Time

Same Day 24 Hour 48 Hour

3-4 Days Standard 5-7 DaysAnalyzed By: MR.

| Lab ID | Field ID | Description                                                                 | Visual |             |         | Optical Properties |            |            |                  | Refractive Indices |             | % Asbestos Fibers Present |        |            |         |             | % Non Asbestos Present |               |            |            |              |           |      |           |       |             |
|--------|----------|-----------------------------------------------------------------------------|--------|-------------|---------|--------------------|------------|------------|------------------|--------------------|-------------|---------------------------|--------|------------|---------|-------------|------------------------|---------------|------------|------------|--------------|-----------|------|-----------|-------|-------------|
|        |          |                                                                             | Color  | Homogeneity | Texture | Fracture           | Morphology | Extinction | 3.0 μ elongation | Birefringence      | Pleochroism | OIL                       | Fibers | Chrysotile | Amosite | Crocidolite | Tremolite              | Anthophyllite | Actinolite | Fiberglass | Mineral Wool | Cellulose | Hair | Synthetic | Other | Non Fibrous |
| 13037  | 13037    | Black paper backing beneath red floor tile, north end, building # 2nd Floor | N      | N           | N       | N                  |            |            |                  |                    |             | 1.550                     |        |            |         |             |                        |               |            |            |              | 55        |      |           |       | 45          |
| 13038  | 13038    | SAME AS ABOVE                                                               | N      | N           | N       | N                  |            |            |                  |                    |             | 1.550                     |        |            |         |             |                        |               |            |            |              | 55        |      |           |       | 45          |
| 13039  | 13039    | SAME AS ABOVE                                                               | N      | N           | N       | N                  |            |            |                  |                    |             | 1.550                     |        |            |         |             |                        |               |            |            |              | 55        |      |           |       | 45          |
| 14040  | 14040    | White floor/ceiling plaster, south end, building # 1, 4, 2nd Floor          | N      | N           | N       | N                  |            |            |                  |                    |             | 1.550                     |        |            |         |             |                        |               |            |            |              | 20        |      |           |       | 80          |
| 14041  | 14041    | SAME AS ABOVE                                                               | N      | N           | N       | N                  |            |            |                  |                    |             | 1.550                     |        |            |         |             |                        |               |            |            |              | 30        |      |           |       | 70          |
| 14042  | 14042    | SAME AS ABOVE                                                               | N      | N           | N       | N                  |            |            |                  |                    |             | 1.550                     |        |            |         |             |                        |               |            |            |              | 30        |      |           |       | 70          |







Please Circle Desired Turn Around Time

Same Day 24 Hour 48 Hour

3-4 Days

Standard 5-7 Days

Analyzed By: NR

Comments/Special Instructions:

Date: 6/13/97 Lab QC Approval By: MM

# INTERNAL / ATC INFORMATION

Branch & Office #:

Rec'd By: \_\_\_\_\_ On: \_\_\_\_\_

Qty Rec'd: \_\_\_\_\_ Rate: \$ \_\_\_\_\_

Requested Completion Date: \_\_\_\_\_

Project #:

Supplemental #:

Project Manager:

# GENERAL CLIENT INFORMATION

Client/Project: VAB

Address: 101 Walnut St. P.O. Box 9051

Watertown, MA 02222

Sampled By: Jim Downey

Results to: SAF

Phone #: 617-924-1770 X1243

Fax #: 617-923-2336

| Lab ID | Field ID | Description                                           | Visual |             |         | Optical Properties |            |            |                    | Refractive Indices |             |                | % Asbestos Fibers Present |            |         |             |           |               | % Non Asbestos Present |            |              |           |      |           |       |             |
|--------|----------|-------------------------------------------------------|--------|-------------|---------|--------------------|------------|------------|--------------------|--------------------|-------------|----------------|---------------------------|------------|---------|-------------|-----------|---------------|------------------------|------------|--------------|-----------|------|-----------|-------|-------------|
|        |          |                                                       | Color  | Homogeneity | Texture | Friable            | Morphology | Extinction | Sign of Elongation | Birefringence      | Pleochroism | OIL            | Fibers                    | Chrysotile | Amosite | Crocidolite | Tremolite | Anthophyllite | Actinolite             | Fiberglass | Mineral Wool | Cellulose | Hair | Synthetic | Other | Non Fibrous |
| 58037  | * 19-055 | Black flashing cement, roof of Building #3            | Black  | 1 1/4"      | 1 1/4"  | N                  | WP         | 1 1/4"     | N                  | 1 1/4"             | N           | 1.550<br>1.680 | 15                        |            |         |             |           |               |                        | 10         |              |           |      |           |       | 95          |
| 58038  | * 19-056 | SAME AS ABOVE                                         | Black  | 1 1/4"      | 1 1/4"  | N                  | N          |            |                    |                    |             | 1.550<br>1.680 |                           |            |         |             |           |               |                        |            |              |           |      |           |       | 98          |
| 58039  | * 19-057 | SAME AS ABOVE                                         | Black  | 1 1/4"      | 1 1/4"  | N                  | N          |            |                    |                    |             | 1.550<br>1.680 |                           |            |         |             |           |               |                        |            |              |           |      |           |       | 98          |
| 58040  | * 20-058 | Black asphaltic roofing material, roof of Building #3 | Black  | 1 1/4"      | 1 1/4"  | N                  | N          |            |                    |                    |             | 1.550<br>1.680 |                           |            |         |             |           |               |                        |            |              | 2         |      |           |       | 98          |
| 58041  | * 20-059 | SAME AS ABOVE                                         | Black  | 1 1/4"      | 1 1/4"  | N                  | N          |            |                    |                    |             | 1.550<br>1.680 |                           |            |         |             |           |               |                        |            |              | 2         |      |           |       | 98          |
| 58042  | * 20-060 | SAME AS ABOVE                                         | Black  | 1 1/4"      | 1 1/4"  | N                  | N          |            |                    |                    |             | 1.550<br>1.680 |                           |            |         |             |           |               |                        | 2          |              | 5         |      |           |       | 93          |

---

# Appendix F

## Lead-Based Paint Summary Tables and Laboratory Analytical Results



## XRF FIELD TESTING RESULTS

Site Access: Yes ☒ No  
 Demo Permitted?: Yes ☒ No  
 Project#: 40163.06  
 Location: 180 Johnson Street  
 Middletown, CT

Date: 5/14/97  
 Page: 1 of 8  
 Project Name: Remington Rand  
 Inspector: TMD

| Location                         | Surface Tested         | Substrate    | Concentration<br>(mg/cm <sup>2</sup> ) |
|----------------------------------|------------------------|--------------|----------------------------------------|
| <b>Building #11A</b>             |                        |              |                                        |
|                                  | Green lower wall       | brick        | < 0.1                                  |
|                                  | White upper wall       | brick        | 0.3                                    |
|                                  | <b>Red fire door</b>   | <b>metal</b> | <b>&gt; 5.0</b>                        |
|                                  | Green lower column     | metal        | 1.6                                    |
|                                  | White upper column     | metal        | 1.4                                    |
|                                  | Red floor              | concrete     | < 0.1                                  |
|                                  | <b>Brown door jamb</b> | <b>wood</b>  | <b>4.1</b>                             |
| <b>Rest Room Hallway</b>         |                        |              |                                        |
|                                  | Tan wall               | sheet rock   | 0.1                                    |
|                                  | Blue door casing       | wood         | < 0.1                                  |
|                                  | Blue baseboard         | wood         | < 0.1                                  |
| <b>Men's Room</b>                |                        |              |                                        |
|                                  | Blue stall divider     | wood         | < 0.1                                  |
|                                  | Tan wall               | brick        | 0.1                                    |
| <b>Foyer/Main Entrance</b>       |                        |              |                                        |
|                                  | Tan wainscoting        | wood         | < 0.1                                  |
|                                  | Tan door               | wood         | 0.1                                    |
| <b>Building #1A, First Floor</b> |                        |              |                                        |
|                                  | Gray lower column      | metal        | 1.3                                    |
|                                  | White upper column     | metal        | 1.5                                    |
|                                  | Tan upper wall         | brick        | 0.2                                    |
|                                  | Blue lower wall        | brick        | 0.4                                    |
|                                  | White window sash      | wood         | 4.0                                    |
|                                  | White window casing    | wood         | 2.4                                    |
| <b>Building #1B, First Floor</b> |                        |              |                                        |
|                                  | Green lower wall       | brick        | 0.7                                    |
|                                  | Gray upper wall        | brick        | 0.5                                    |
|                                  | White upper wall       | brick        | 0.1                                    |
|                                  | White overhead door    | wood         | < 0.1                                  |
|                                  | White window sash      | wood         | 1.5                                    |
|                                  | White window casing    | wood         | 2.4                                    |
|                                  | Brown door             | wood         | 0.1                                    |
|                                  | Brown door casing      | wood         | 0.4                                    |

Limit of detection of NITON XRF is < 0.1 mg/cm<sup>2</sup>

**BOLD** indicates building components that should be segregated and disposed as hazardous waste.

Z: EVADOWNEYLBP\_CT.DOC



## XRF FIELD TESTING RESULTS

Site Access: Yes ☒ No

Date: 5/14/97

Demo Permitted?: Yes ☒ No

Page: 2 of 8

Project#: 40163.06

Project Name: Remington Rand Facility

Location: 180 Johnson Street

Inspector: TMD

Middletown, CT

| Location                                 | Surface Tested         | Substrate    | Concentration<br>(mg/cm <sup>2</sup> ) |
|------------------------------------------|------------------------|--------------|----------------------------------------|
| <b>Building #1B, First Floor (cont.)</b> |                        |              |                                        |
|                                          | Gray lower column      | metal        | 0.2                                    |
|                                          | White upper column     | metal        | 0.9                                    |
|                                          | White window sash      | wood         | 2.0                                    |
|                                          | Red fire door          | metal        | 0.6                                    |
|                                          | White wall             | sheet rock   | 0.1                                    |
|                                          | White wainscoting      | wood         | 0.3                                    |
|                                          | White window casings   | wood         | 0.3                                    |
| <b>Building #1B (cont.)</b>              |                        |              |                                        |
|                                          | Green door             | wood         | 0.4                                    |
| <b>Building #1C, First Floor</b>         |                        |              |                                        |
|                                          | Gray lower wall        | brick        | 0.4                                    |
|                                          | White upper wall       | brick        | 0.6                                    |
|                                          | Gray lower column      | metal        | 0.2                                    |
|                                          | White upper column     | metal        | 0.6                                    |
|                                          | Gray wainscoting       | wood         | 0.2                                    |
|                                          | Gray door              | wood         | 2.8                                    |
|                                          | Gray door casing       | wood         | 0.1                                    |
|                                          | White window sash      | wood         | 3.4                                    |
|                                          | White window casing    | wood         | > 5.0                                  |
|                                          | Gray column            | metal        | 1.5                                    |
| <b>Men's Room</b>                        | <b>Tan wall</b>        | <b>wood</b>  | <b>&gt; 5.0</b>                        |
|                                          | <b>Tan wall</b>        | <b>brick</b> | <b>3.8</b>                             |
|                                          | White ceiling          | wood         | 0.1                                    |
|                                          | Black electrical board | wood         | < 0.1                                  |
|                                          | Gray door              | wood         | 2.7                                    |
|                                          | White cross beam       | wood         | 0.1                                    |
|                                          | Gray inner stair wall  | wood         | 1.7                                    |
| <b>Building #1C, Second Floor</b>        |                        |              |                                        |
|                                          | White window sash      | wood         | 4.1                                    |
|                                          | White window casing    | wood         | > 5.0                                  |
|                                          | White ceiling          | wood         | 0.1                                    |
|                                          | White upper wall       | brick        | 0.4                                    |

Limit of detection of NITON XRF is < 0.1 mg/cm<sup>2</sup>

**BOLD** indicates building components that should be segregated and disposed as hazardous waste.

Z: EVDOWNEYLBP\_CT.DOC



## XRF FIELD TESTING RESULTS

Site Access: Yes ☒ No  
 Demo Permitted?: Yes ☒ No  
 Project#: 40163.06  
 Location: 180 Johnson Street  
 Middletown, CT

Date: 5/14/97  
 Page: 3 of 8  
 Project Name: Remington Rand Facility  
 Inspector: TMD

| Location                                  | Surface Tested          | Substrate | Concentration<br>(mg/cm <sup>2</sup> ) |
|-------------------------------------------|-------------------------|-----------|----------------------------------------|
| <b>Building #1C, Second Floor (cont.)</b> |                         |           |                                        |
|                                           | Gray lower wall         | brick     | 0.6                                    |
|                                           | White upper column      | wood      | 0.3                                    |
|                                           | Gray lower column       | wood      | 0.2                                    |
| <b>Building #1B, Second Floor</b>         |                         |           |                                        |
|                                           | White window sash       | wood      | > 5.0                                  |
|                                           | White window casing     | wood      | > 5.0                                  |
|                                           | Gray lower column       | wood      | 0.9                                    |
|                                           | White upper column      | wood      | 1.0                                    |
|                                           |                         |           |                                        |
|                                           |                         |           |                                        |
| <b>Building #1B, Second Floor (cont.)</b> | Green Stairs            | wood      | < 0.1                                  |
|                                           | Gray lower wall         | brick     | 0.3                                    |
|                                           | White upper wall        | brick     | 0.1                                    |
| <b>Building #9, Second Floor</b>          |                         |           |                                        |
|                                           | Green lower column      | wood      | 0.4                                    |
|                                           | Yellow upper column     | wood      | 0.1                                    |
|                                           | Green lower wall        | brick     | 1.4                                    |
|                                           | Tan upper wall          | brick     | 0.3                                    |
|                                           | Bright green lower wall | brick     | 1.5                                    |
|                                           | Yellow/green fire door  | metal     | > 5.0                                  |
| <b>Building #1A, Second Floor</b>         |                         |           |                                        |
|                                           | White window sash       | wood      | 1.9                                    |
|                                           | White window casing     | wood      | 2.6                                    |
|                                           | Gray lower wall         | brick     | 0.2                                    |
|                                           | White upper wall        | brick     | 0.1                                    |
|                                           | Gray lower column       | wood      | 0.6                                    |
|                                           | White upper column      | wood      | 1.0                                    |
|                                           | Yellow pipe             | metal     | 1.2                                    |
| <b>Side Stairs</b>                        | Gray newel post         | wood      | 3.5                                    |

Limit of detection of NITON XRF is < 0.1 mg/cm<sup>2</sup>

**BOLD** indicates building components that should be segregated and disposed as hazardous waste.



## XRF FIELD TESTING RESULTS

Site Access: Yes ☒ No

Date: 5/14/97

Demo Permitted?: Yes ☒ No

Page: 4 of 8

Project#: 40163.06

Project Name: Remington Rand Facility

Location: 180 Johnson Street

Inspector: TMD

Middletown, CT

| Location                                 | Surface Tested     | Substrate | Concentration<br>(mg/cm <sup>2</sup> ) |
|------------------------------------------|--------------------|-----------|----------------------------------------|
| Side Stairs (cont.)                      |                    |           |                                        |
|                                          | Gray inner wall    | wood      | 3.1                                    |
| Building #8, Second Floor                |                    |           |                                        |
|                                          | White wall         |           | 0.3                                    |
|                                          | Gray lower wall    |           | 0.9                                    |
|                                          | White upper column |           | 0.1                                    |
|                                          | Green lower column |           | 0.6                                    |
|                                          | Gray door          |           | 0.2                                    |
|                                          | Gray fire door     |           | 4.7                                    |
| Hall to #1B, Second Floor                |                    |           |                                        |
|                                          | Gray elevator door | metal     | 0.6                                    |
|                                          | Gray fire door     | metal     | 0.6                                    |
| Storage Room, Building #1C, Second Floor |                    |           |                                        |
|                                          | White wall         | brick     | 0.4                                    |
| Building #8, First Floor                 |                    |           |                                        |
|                                          | Gray lower wall    | brick     | 0.1                                    |
|                                          | White upper wall   | brick     | 0.1                                    |
|                                          | Gray lower column  | wood      | 0.1                                    |
|                                          | White upper column | wood      | < 0.1                                  |
|                                          | Tan ceiling        | wood      | 0.2                                    |
| Building #8, First Floor (cont.)         |                    |           |                                        |
|                                          | Tan cross beam     | wood      | 0.5                                    |
|                                          | Gray door          | wood      | 0.3                                    |
|                                          | Gray fire door     | metal     | 4.6                                    |
|                                          | Gray overhead door | wood      | 1.7                                    |
| Hall to #1B, First Floor                 |                    |           |                                        |
|                                          | Gray door          | wood      | 0.5                                    |
|                                          | Gray fire door     | metal     | 1.5                                    |
| Building #4                              | Gray lower wall    | brick     | 0.2                                    |

Limit of detection of NITON XRF is < 0.1 mg/cm<sup>2</sup>

BOLD indicates building components that should be segregated and disposed as hazardous waste.



## XRF FIELD TESTING RESULTS

Site Access: Yes X No  
 Demo Permitted?: Yes X No  
 Project#: 40163.06  
 Location: 180 Johnson Street  
 Middletown, CT

Date: 5/14/97  
 Page: 5 of 8  
 Project Name: Remington Rand Facility  
 Inspector: TMD

| Location                   | Surface Tested        | Substrate | Concentration<br>(mg/cm <sup>2</sup> ) |
|----------------------------|-----------------------|-----------|----------------------------------------|
| <b>Building #4 (cont.)</b> |                       |           |                                        |
|                            | White upper wall      | brick     | 0.2                                    |
|                            | Gay fire door         | metal     | 1.8                                    |
|                            | Gray column           | metal     | 0.2                                    |
| <b>Building #2</b>         |                       |           |                                        |
|                            | Green lower wall      | brick     | 0.1                                    |
|                            | White upper wall      | brick     | < 0.1                                  |
|                            | Red fire door         | metal     | 0.5                                    |
|                            | White window sash     | wood      | > 5.0                                  |
|                            | White window casing   | wood      | > 5.0                                  |
| <b>Building #11B</b>       |                       |           |                                        |
|                            | Red structural beam   | metal     | 2.8                                    |
|                            | Green door            | metal     | 2.4                                    |
| <b>Building #11C</b>       |                       |           |                                        |
|                            | Green wall            | brick     | 0.1                                    |
|                            | White wall            | brick     | 0.1                                    |
|                            | Brown overhead door   | wood      | < 0.1                                  |
|                            | Brown exterior door   | metal     | 0.7                                    |
| <b>Building #9C</b>        |                       |           |                                        |
|                            | Green overhead door   | wood      | 2.6                                    |
|                            | Red floor             | concrete  | 0.2                                    |
|                            | Brown wall            | wood      | < 0.1                                  |
|                            | Gray fire door        | metal     | 3.9                                    |
| <b>Building #4</b>         |                       |           |                                        |
|                            | Gray lower wall       | brick     | 0.4                                    |
| <b>Building #4 (cont.)</b> |                       |           |                                        |
|                            | White upper wall      | brick     | < 0.1                                  |
|                            | Gray fire door        | metal     | 1.2                                    |
| <b>Building #12</b>        |                       |           |                                        |
|                            | Gray lower wall       | brick     | 0.1                                    |
|                            | White upper wall      | brick     | < 0.1                                  |
|                            | White window sash     | wood      | N/A                                    |
|                            | White window casing   | wood      | N/A                                    |
|                            | Gray fire door        | metal     | 3.0                                    |
| <b>Building #7</b>         |                       |           |                                        |
|                            | Silver hot water tank | metal     | 3.2                                    |

Limit of detection of NITON XRF is < 0.1 mg/cm<sup>2</sup>

**BOLD** indicates building components that should be segregated and disposed as hazardous waste.

Z: EVDOWNEYALBP\_CT.DOC



## XRF FIELD TESTING RESULTS

Site Access: Yes ☒ No ☐  
 Demo Permitted?: Yes ☒ No ☐  
 Project#: 40163.06  
 Location: 180 Johnson Street  
 Middletown, CT

Date: 5/14/97  
 Page: 6 of 8  
 Project Name: Remington Rand Facility  
 Inspector: TMD

| Location                                      | Surface Tested             | Substrate       | Concentration<br>(mg/cm <sup>2</sup> ) |
|-----------------------------------------------|----------------------------|-----------------|----------------------------------------|
| <b>Building #7 (cont.)</b>                    |                            |                 |                                        |
|                                               | Silver boiler              | metal           | 0.3                                    |
|                                               | Green lower wall           | brick           | 0.2                                    |
|                                               | White upper wall           | brick           | < 0.1                                  |
|                                               | <b>Red pad</b>             | <b>concrete</b> | <b>&gt; 5.0</b>                        |
|                                               | Red floor                  | concrete        | 0.1                                    |
|                                               | Red stair riser            | wood            | 1.3                                    |
|                                               | Green structural beam      | metal           | 0.5                                    |
|                                               | Green vertical column      | metal           | 1.0                                    |
| <b>Building #6, Second Floor</b>              |                            |                 |                                        |
|                                               | Green door                 | wood            | 0.4                                    |
|                                               | White wall                 | brick           | 0.1                                    |
|                                               | <b>White window sash</b>   | <b>wood</b>     | <b>&gt; 5.0</b>                        |
|                                               | Black structural beam      | metal           | 0.7                                    |
| <b>Building #6, First Floor, Center Space</b> |                            |                 |                                        |
|                                               | <b>White window sash</b>   | <b>wood</b>     | <b>&gt; 5.0</b>                        |
|                                               | <b>White window casing</b> | <b>wood</b>     | <b>&gt; 5.0</b>                        |
|                                               | Brown door                 | wood            | 0.4                                    |
|                                               | Green wall                 | brick           | 0.5                                    |
| <b>Building #6, First Floor, Front Space</b>  |                            |                 |                                        |
|                                               | White door                 | wood            | 0.1                                    |
|                                               |                            |                 |                                        |
|                                               |                            |                 |                                        |
|                                               |                            |                 |                                        |
| <b>Building #3</b>                            |                            |                 |                                        |
|                                               | Gray fire door             | metal           | 3.2                                    |
|                                               | White window casing        | wood            | 1.5                                    |
|                                               | <b>White window sash</b>   | <b>wood</b>     | <b>4.5</b>                             |
|                                               | Gray wall                  | brick           | < 0.1                                  |
|                                               | White wall                 | sheet rock      | < 0.1                                  |

Limit of detection of NITON XRF is < 0.1 mg/cm<sup>2</sup>

**BOLD** indicates building components that should be segregated and disposed as hazardous waste.





## XRF FIELD TESTING RESULTS

Site Access: Yes ☒ No  
Demo Permitted?: Yes ☒ No  
Project#: 40163.06  
Location: 180 Johnson Street  
Middletown, CT

Date: 5/14/97  
Page: 7 of 8  
Project Name: Remington Rand Facility  
Inspector: TMD

| Location                                  | Surface Tested      | Substrate  | Concentration<br>(mg/cm <sup>2</sup> ) |
|-------------------------------------------|---------------------|------------|----------------------------------------|
| <b>Demers Expo Space,<br/>First Floor</b> |                     |            |                                        |
|                                           | Cream wall          | sheet rock | < 0.1                                  |
|                                           | White window sash   | wood       | vinyl                                  |
|                                           | White window casing | wood       | 1.5                                    |
|                                           | Cream vertical beam | wood       | 0.9                                    |
|                                           | Cream wall          | brick      | 0.2                                    |
|                                           | Cream door          | wood       | < 0.1                                  |
|                                           | Cream door frame    | wood       | < 0.1                                  |
|                                           |                     |            |                                        |
| <b>Second Floor</b>                       | Cream wall          | sheet rock | 0.1                                    |
|                                           | Cream wall          | brick      | 0.1                                    |
|                                           | White window casing | wood       | 2.0                                    |
|                                           | Cream wainscoting   | wood       | 2.0                                    |
|                                           | Blue hand rail      | wood       | 1.3                                    |
|                                           | Blue newel post     | wood       | 1.9                                    |
| <b>Room #1, Second Floor</b>              |                     |            |                                        |
|                                           | Brown window sash   | wood       | > 5.0                                  |
|                                           | Brown window casing | wood       | 0.7                                    |
|                                           | Brown window sill   | wood       | < 0.1                                  |
|                                           | Brown chair rail    | wood       | < 0.1                                  |
|                                           | Brown baseboard     | wood       | 0.1                                    |
|                                           | White wall          | plaster    | 0.2                                    |
|                                           | Brown door casing   | wood       | 0.1                                    |
|                                           | Brown door jamb     | wood       | 0.1                                    |
| <b>Room #2, Second Floor</b>              |                     |            |                                        |
|                                           | Brown window casing | wood       | 1.1                                    |
|                                           | Brown window sill   | wood       | 0.1                                    |
|                                           | Cream wall          | plaster    | 0.2                                    |
| <b>Hall, Second Floor</b>                 |                     |            |                                        |
|                                           | Cream wall          | sheet rock | 0.2                                    |
| <b>Storage Room, Second<br/>Floor</b>     |                     |            |                                        |
|                                           | Cream wall          | brick      | < 0.1                                  |
| <b>Building #5</b>                        | White window sash   | wood       | > 5.0                                  |
|                                           | White window casing | wood       | 3.1                                    |

Limit of detection of NITON XRF is < 0.1 mg/cm<sup>2</sup>

**BOLD** indicates building components that should be segregated and disposed as hazardous waste.

Z: EV\DOWNNEY\BP\_CT.DOC



## XRF FIELD TESTING RESULTS

Site Access: Yes X No  
Demo Permitted?: Yes X No  
Project#: 40163.06  
Location: 180 Johnson Street  
Middletown, CT

Date: 5/14/97  
Page: 8 of 8  
Project Name: Remington Rand Facility  
Inspector: TMD

| Location                      | Surface Tested        | Substrate | Concentration<br>(mg/cm <sup>2</sup> ) |
|-------------------------------|-----------------------|-----------|----------------------------------------|
| Building #5 (cont.)           |                       |           |                                        |
|                               | Gray lower wall       | brick     | 0.1                                    |
|                               | White upper wall      | brick     | < 0.1                                  |
| Building #7, Band Room, Front |                       |           |                                        |
|                               | Green door            | wood      | 0.8                                    |
|                               | Green door casing     | wood      | 0.6                                    |
|                               | White door            | wood      | < 0.1                                  |
|                               | White window sash     | wood      | > 5.0                                  |
|                               | White window casing   | wood      | 4.1                                    |
|                               | Brown exterior door   | wood      | 2.1                                    |
| Building #6, Boiler Room      |                       |           |                                        |
|                               | Black structural beam | metal     | 0.8                                    |
|                               | Yellow hand rails     | metal     | 2.4                                    |
|                               | Silver duct           | metal     | 0.4                                    |
| "Mattress" Space              |                       |           |                                        |
|                               | Red structural beam   | metal     | < 0.1                                  |
|                               | Red vertical column   | metal     | 0.1                                    |
| Exterior Areas                |                       |           |                                        |
| Building #4                   | Green siding          | wood      | 2.2                                    |
|                               | Brown door            | wood      | 2.1                                    |
| Building #6                   | White storage shed    | wood      | > 5.0                                  |
| Building #10                  |                       |           |                                        |
|                               | White window casing   | wood      | > 5.0                                  |
|                               | White window sash     | wood      | > 5.0                                  |

Limit of detection of NITON XRF is < 0.1 mg/cm<sup>2</sup>

BOLD indicates building components that should be segregated and disposed as hazardous waste.

NLLAP (A2LA) CERTIFICATE # 539.01  
RHODE ISLAND LICENSE #86  
MASSACHUSETTS LISTED  
NYDOH ELAP #11346

MIDDLETOWN CT

DATE COLLECTED 05-16-97      DATE RECEIVED 05-19-97      DATE REPORTED 05-22-97

| SAMPLE IDENTIFICATION               | PERCENT<br>LEAD |
|-------------------------------------|-----------------|
| WHITE CEILING BY FIRE DOOR BLDNG 1C | 0.840           |
| GRAY VERTICAL COLUMN #65B BLDNG 1C  | 0.207           |

RESULTS REVIEWED BY:

DIRECTOR

DISCLAIMER: This report may be transferred to a third party only in its entirety. The results represent the concentration of lead in the samples submitted and identified by the person or firm shown above. Incorrect identification of critical parameters will affect test results. Taken alone this report does not constitute a lead inspection or risk assessment. Only licensed or certified professionals may provide a complete interpretation. Environmental Science Lab., Inc., its employees or agents are not responsible for the consequences of any actions taken or not taken based on the results shown on this report or for any written or verbal interpretations of the results shown.





# Appendix G Inventory of Oil and Hazardous Materials

## Inventory of Oil and Hazardous Materials

| Location                 | Material                           | Container Size    | Quantity |
|--------------------------|------------------------------------|-------------------|----------|
| 1A, 2nd Floor            | CFC-containing refrigerator        | ---               | 1        |
|                          | Dry chemical fire extinguisher     | ---               | 2        |
|                          | Starter fluid                      | 11 oz.            | 1        |
|                          | Glazing compound                   | 33 oz.            | 1        |
|                          | Paint                              | 1-gallon          | 1        |
| 1B, 1st Floor            | Dry chemical fire extinguisher     | ---               | 2        |
|                          | Compressor oil                     | 5-gallon          | 2        |
|                          | Unknown liquid                     | 1-gallon          | 1        |
| 1B, 2nd Floor            | Asphalt Roof Sealant               | 5-gallon          | 1        |
|                          | PCB oils within electric panel     | 1/2 pint cylinder | 9        |
|                          | PCB oils within electric panel     | 1/2 pint cylinder | 10       |
| 1B, Elevator Room (roof) | Asphaltic Roof Flashing            | 5 gallon pail     | 1        |
|                          | Motor Oil                          | 1 quart           | 1        |
|                          | Gear Oil                           | 11 oz.            | 1        |
|                          | Transmission Oil                   | 1 gallon          | 1        |
| 1C, 1st Floor            | Dry chemical fire extinguisher     | ---               | 4        |
| 1C, 2nd Floor            | PCB oils within electric panel     | 1/2 pint cylinder | 9        |
|                          | Dry chemical fire extinguisher     | ---               | 2        |
|                          | Latex paint                        | 5 gallon          | 9        |
|                          | Polyurethane                       | 15 gallons        | 1        |
|                          | Car battery                        | ---               | 2        |
|                          | Antifreeze                         | 1 gallon          | 1        |
| 4                        | Used motor oil                     | 20 gallons        | 1        |
| 5                        | Window mounted CFC air conditioner | ---               | 10       |
|                          | Acetylene cylinder                 | Four foot         | 1        |
|                          | Oxygen cylinder                    | Four foot         | 1        |
|                          | Unknown gas cylinder               | 25 lb.            | 1        |
|                          | CFC-containing refrigerators       | ---               | 17       |

## Inventory of Oil and Hazardous Materials

| Location                       | Material                               | Container Size    | Quantity |
|--------------------------------|----------------------------------------|-------------------|----------|
| 6, 1st Floor                   | Degreaser                              | 4 gallons         | 1        |
|                                | Turpentine                             | 1 gallon          | 1        |
|                                | Spray paint cans                       | can               | 10       |
|                                | Latex paint                            | 5 gallon          | 16       |
|                                | Oil-based paint                        | 1 quart           | 5        |
|                                | "Clear baking synthetic"               | 5 gallon          | 1        |
|                                | Ortho insecticides                     | 1 pint glass      | 4        |
|                                | Gear lubricant                         | 1 quart           | 1        |
|                                | Oil lubricant                          | 5 lb.             | 1        |
|                                | Ortho insecticides                     | 1 pint plastic    | 10       |
|                                | PCB oils within electric panel         | 1/2 pint cylinder | 7        |
| 6, 2nd Floor                   | Latex Paint                            | 1 gallon          | 25       |
|                                | Oil-based paint                        | 1 gallon          | 25       |
|                                | Hydrochloric acid                      | 1 gallon          | 1        |
|                                | Acidic solution                        | 1 gallon          | 1        |
|                                | Latex paint                            | 5 gallon          | 5        |
|                                | Mineral spirits/lead naphenate mixture | 5 gallon          | 2        |
|                                | Polyurethane                           | 5 gallon          | 1        |
|                                | Naphtha                                | 1/2 gallon        | 1        |
| 7                              | Bleach                                 | 1 gallon          | 1        |
|                                | Latex paint                            | 5 gallon          | 14       |
|                                | Stain                                  | 5 gallon          | 1        |
|                                | Oil-based paint                        | 5 gallon          | 1        |
|                                | No. 2 fuel oil                         | 20 gallons        | 1        |
| 8, 1st Floor                   | Dry chemical fire extinguisher         | ---               | 1        |
|                                | Driveway sealer                        | 5-gallon          | 2        |
|                                | Motor oil                              | Quart             | 5        |
| 8, 2nd Floor                   | PCB oils within electric panel         | 1/2 pint cylinder | 9        |
| Hall between 8 & 1B, 1st Floor | Dry chemical fire extinguisher         | ---               | 1        |
| 9B                             | Lacquer thinner                        | 1 gallon          | 5        |
|                                | Used motor oil                         | 1 gallon          | 2        |
|                                | Degreaser                              | 1 gallon          | 4        |
|                                | Spray paint cans                       | Can               | 12       |
|                                | Oil-based paint                        | 1 gallon          | 2        |

## Inventory of Oil and Hazardous Materials

| Location             | Material                    | Container Size  | Quantity |
|----------------------|-----------------------------|-----------------|----------|
| 10                   | CFC-containing refrigerator | ---             | 1        |
|                      | Used motor Oil              | 55-gallon       | 3        |
| 11B                  | Used motor oil              | 55-gallon       | 1        |
| 11C                  | Empty freon cylinder        | 5 lb.           | 1        |
|                      | Used motor oil              | 10 gallons      | 1        |
| 11D                  | Argon gas cylinder          | Four foot       | 1        |
|                      | Used motor oil              | 55 gallon       | 2        |
| 14                   | Hydrochloric acid           | 15 gallon glass | 1        |
|                      | Grease                      | 30 gallons      | 1        |
|                      | Unknown                     | 55 gallon       | 1        |
|                      | Unknown                     | 55 gallon       | 1        |
|                      | Oil                         | 5 gallon        | 9        |
|                      | Brake fluid                 | 1 gallon        | 1        |
|                      | Unknown                     | 30 gallon       | 1        |
|                      | Lacquer                     | 1 gallon        | 2        |
|                      | Baking lacquer              | 5 gallon        | 1        |
| 15                   | CFC-containing refrigerator | ---             | 1        |
| Quonset Bldg.        | Motor oil                   | 55 gallon       | 3        |
|                      | Used motor oil              | 10 gallons      | 1        |
| <u>Exterior</u>      |                             |                 |          |
| Adjacent to No. 15   | Used motor oil and water    | 55 gallon       | 1        |
| Behind Quonset Bldg. | Used motor oil              | 55 gallon       | 1        |
| Adjacent to 13       | Rail Road Ties              | ---             | 40       |